



Testing Laboratory 1045.1 accredited by the Czech Accreditation Institute pursuant to
ČSN EN ISO/IEC 17025:2018

Strojírenský zkušební ústav, s.p. Zkušební laboratoř
(Engineering Test Institute, Public Enterprise, Testing Laboratory)
Hudcova 424/56b, Medlánky, 621 00 Brno

Page 1 of 14



TEST REPORT

39-16511/H

Product: Outdoor Air/Water Heat Pump – monobloc

Type designation: Airkompakt p0916

Customer: KOŁTON SPÓŁKA KOMANDYTOWA
ul. Sosnowa 2
34-480 34-480 Jabłonka
POLAND

Manufacturer: KOŁTON SPÓŁKA KOMANDYTOWA
ul. Sosnowa 2
34-480 34-480 Jabłonka
POLAND

Responsible employee: Ing. Antonín Kolbábek, Ph.D.

Report issue date: 2022-09-16

Distribution list: 1 copy to the Customer
1 copy to the Engineering Test Institute

This document may be copied in its entirety without written consent of the Engineering Test Institute. Partial copies are subject to approval. The results of the tests and verifications shall relate only to the products tested as received or presented. The testing laboratory is not responsible for the data provided by the customer specified in the report.

I. Description of product tested

The Heat pump **Airkompakt p0916**, supplied by the company **KOLTON SPÓŁKA KOMANDYTOWA**, is structurally adapted to operate in air/water system. Device is designed as monobloc unit placed outdoors on a pedestal. Refrigerant R290 is used with charge of 1.50 kg. Power supply is three-phase. Heat pump is able to work in heating and cooling mode. Heat pump is working with fixed flow rate.

Main components of the outdoor unit **Airkompakt p0916**:

- Serial number 22PC09020010085
- Cuboid shape with dimensions 1300 × 590 × 1030 mm (W × D × H)
- Frame and casing made of varnished steel sheets
- Compressor Copeland Scroll ZH08KCU-TFMN-524
- Refrigerant R290 (charge: 1.50 kg)
- Cuboid-shaped evaporator Fin&Tube (3-rows), with dimensions: 800 × 55 × 885 mm (W × D × H), spacing 2.0 mm
- PHE condenser with dimensions 160 × 140 × 560 mm (W × D × H), including insulation
- Electronic expansion valve
- 4-way reversing valve Sanhua SHF(L)-11H-35U-52 (with coil)
- Refrigerant accumulator
- Axial fan ø 650 mm with motor
- Filter/dehydrator
- Pressure sensors
- Temperature sensors on water, refrigerant pipes, outside
- Refrigerant pipes

Scheme:

(i.e., illustrative connection of device)





Photo-documentation:



Air/Water Heat pump Airkompakt p0916
– Front view with cover /on left/, Back view without cover /on right/ –



Air/Water Heat pump Airkompakt p0916
– Side view without cover –



Air/Water Heat pump Airkompakt p0916
– Compressor label –

KOLTON 	
PPAU Kolton s.c. Součava 2 32-080 Jablonka www.kolton.pl	
Büro servis pumpy ciepła serwis klimatyzacji	
Kontakt 18 264 26 67 608 432 606, 608 432 200, 576 608 901 53 873 95 80	
Typ Model/Model	AIRKOMPACT P0916
Rek produkcji Production year/Baujahr	2022
Numer fabryczny Serial number/Identifikationsnummer	22PC09020010086
Zasilanie elektryczne Power supply/Elektrische Versorgung	400 V; 3 ~; 50 Hz;
Maksymalny prąd pracy Max. operation current/ Maximaler Arbeitsstrom	7,1 A
Stopień ochrony IP IP code/IP-Bewertung	IP 24
Masa w pomieszczeniu zewn. (dB)	44/52
Moc grzewcza (A7/W35) Heating capacity/Wärmeleistung	3,85 kW
Moc elektryczna (A7/W35) Rated power/Elektrische Leistungsleistung	2,14 kW
COP A7/W35	4,61
Czynnik chłodniczy/Ilość Kühlmittel/Menge	R290 / 1,3 kg
Max. ciśnienie robocze obiegu chłodniczego Max. working pressure of refrigerant/Max. Kühlmitteldruck	26 bar
Max. ciśnienie robocze obiegu grzewczego Max. working pressure/Max. Arbeitsdruck	2,5 bar
Max. temp. zasilania Max. water temperature/Max. Wassertemperatur	65 °C
Pojemność wodna Heat pump capacity/Wärmepumpenvolumen	4 L
Masa Weight/Gewicht	180 kg
UWAGA! Serwis tylko dla wykwalifikowanego personelu! WARNING! Service only for qualified in hydrocarbon refrigerant (HC) staff! ACHTUNG! Service nur für qualifizierte Mitarbeiter mit Kohlenwasserstoffkältemittel (HC)!	

Air/Water Heat pump **Airkompakt p0916**
– Outdoor unit label –

II. Sample tested

SZU reg. no.	Product name	Date of submission
0213.22.37137.001	Air/Water Heat pump Airkompakt p0916	2022-08-22

The visual inspection, tests and verification were carried out by Ing. Antonín Kolbábek, Ph.D. – Test engineer at the test station of SZU.

III. Measuring and test equipment:

The tests were performed using measuring and testing equipment with valid calibration.

No.	Description	Inventory number
1.	Electrical energy meter	022370/1
2.	Digital watt meter	MaR01/EM01
3.	Flow meter Krohne Optiflux	022370/5
4.	Barometer	022370/7
5.	Differential pressure gauge	MaR01_TI
6.	Temperature-humidity meter HC2-IC305	022370/10 022370/11
7.	Thermometers	022370/13
8.	Tape measure	ME 475
9.	Thermo-hydro meter 608-H1	117043
10.	Multi-analyser SINUS SoundBook MK2	000-000-000-875/1
11.	Microphone pair G.R.A.S. 40 AK, wind deflector	000-000-000-875/2
12.	Calibrator G.R.A.S. 42AG	000-000-000-875/3

IV. Methods, results of tests and verifications

No.	Test objective	Requirement	Method of test	Documentation	Test evaluation/ verification *
1.	Acoustic measurements – Sound power level	Art. 7	ČSN EN 12102-1:2018	Page No. 9+13	+

*) **Evaluation / statement of conformity:**

+Requirement fulfilled
 -Requirement not fulfilled

0..... Not applicable
 x..... Not evaluated

Note:

The stated extended measurement uncertainties are calculated as a factor of the measurement uncertainty and the extension coefficient $k=2$, corresponding to the coverage certainty of 95% as regards standard classification.

If a statement of conformity is provided, the decision rule pursuant to ILAC-G8:09/2019, Art. 4.2.1 – binary statement for the simple acceptance rule shall apply.

Test objective:	Heating and cooling equipment
Exact name of the test procedure:	T 076* - Measurement of noise characteristics
Test method:	ČSN EN 12102-1:2018; ČSN ISO 9614-2:1997; EHPA Testing regulation – Testing of Air/Water Heat Pumps – Version 2.4a
Sample tested:	Air/Water Heat pump Airkompakt p0916
Measuring equipment used:	see Chapter III
Place of test:	Engineering Test Institute, Hudcova 424/56b, 621 00 Brno, CZ

Measurement uncertainty:

Measured quantity	Unit	Uncertainty of measurement	Evaluation
Liquid			
- temperature difference (dT)	[K]	± 0.15 K	fulfilled
- temperature inlet/outlet	[°C]	± 0.15 K	fulfilled
- volume flow	[m ³ /s]	± 1 %	fulfilled
- static pressure difference	[kPa]	± 1 kPa ($\Delta p \leq 20$ kPa) or ± 5 % ($\Delta p > 20$ kPa)	fulfilled
Air			
- dry bulb temperature	[°C]	± 0.2 K	fulfilled
- wet bulb temperature	[°C]	± 0.4 K	fulfilled
- volume flow	[m ³ /s]	± 5 %	not applied
- static pressure difference	[Pa]	± 5 Pa ($\Delta p \leq 100$ Pa) or ± 5 % ($\Delta p > 100$ Pa)	not applied
Refrigerant			
- pressure at compressor outlet	[kPa]	± 1 %	not applied
- temperature	[°C]	± 0.5 K	not applied
Concentration (in volume)			
- heat transfer medium	[%]	± 2	not related
Electrical quantities			
- electric power	[W]	± 1 %	fulfilled
- voltage	[V]	± 0.5 %	fulfilled
- current	[A]	± 0.5 %	fulfilled
- electric energy	[kWh]	± 1 %	not applied
Compressor rotational speed	[min ⁻¹]	± 0.5 %	not applied

The heating or cooling capacities measured on the liquid side shall be determined within a maximum uncertainty of 5 % independent of the individual uncertainties of measurement including the uncertainties on the properties of fluids.	fulfilled
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------


a) Measurement surface

Tested samples were surrounded by a cuboid-shape measuring surface set in distance d [m].

Test sample			For outdoor unit	For indoor unit
Distance from the test sample	d	[m]	0.200	---
Height of measurement surface	h	[m]	1.230	---
Width of measurement surface	w	[m]	1.700	---
Depth of measurement surface	l	[m]	0.990	---
Total measurement surface area	S	[m ²]	8.2804	---
Minimal measuring time	t_M	[s]	5 × 40	---

Sketch of measurement surface (not in scale):

Air/Water Heat pump Airkompakt p0916
– Outdoor unit –



Note:

Segment I. (Front) was reduced into 2.0710 m² because of water pipe connections.

b) Acoustic environment

The testing samples were placed inside climatic-chambers (with dimensions see below); on walls and ceiling of the chambers were mounted sound absorption panels. Both samples were placed in the middle of the chamber, at a sufficient distance from the surrounding walls, and were rotated by about $5\div 10^\circ$.

An indoor unit of heat pump unit was hanged on a rigid tubular frame, without any reflective wall – the noise was emitted in all directions i.e., through a spatial angle 4π .

Climatic-acoustic chamber <i>(Corresponds to free-field over a reflecting plane)</i>			For outdoor unit	For indoor unit
Width of testing chamber	l_1	[m]	4.000	2.600
Length of testing chamber	l_2	[m]	6.000	2.800
Height of testing chamber	l_3	[m]	2.350	2.400

c) Measured and calculated data – General overview:

The measured values are in accordance with ČSN EN 12102-1:2018			YES	
The measured values are in accordance with ČSN ISO 9614-2:1997			YES	
Operation mode			Heating	
Specification of the assessment condition			A7/W55 ^{*)}	
Type of HP capacity regulation			ON/FF	
Control settings of heat pump / compressor			Fixed	
Fan speed settings			AUTO	
Water pump settings – secondary circuit			---	
Designation of HP setting			"ErP"	
Test sample			Air/Water Heat pump Airkompakt p0916	
			– Outdoor unit –	– Indoor unit –
Date of testing			2022-09-02	---
Reference air temperature	t_{amb}	[°C]	6.8	---
Relative humidity of air	RH	[%]	86.4	---
Ambient pressure	p_{amb}	[hPa]	986.36	---
Overall sound power level (linear)	L_W	[dB]	71.0 ± 1.5	--- ± 1.5
Overall A-weighted sound power level	L_{WA}	[dB]	62.9 ± 1.5	--- ± 1.5
Accuracy class			Engineering (Grade 2)	Engineering (Grade 2)

^{*)} Comment to abbreviated marking: i.e. A7/W55
 A (air), 7 (input air, dry-bulb temperature in °C) / W (water), 55 (outlet heating water temperature in °C)

1A) Measurement results – octave bands

Air/Water Heat pump Airkompakt p0916 – Outdoor unit at A7/W55 / <u>Compressor: FIXED, Fan: AUTO, Water pump: -- /</u>	Engineering (Grade 2)
---------------------------------------------------------------------------------------------------------------------------------	----------------------------------

f_m [Hz]	Criterion 1			Criterion 2		Criterion 3	All criteria passed?	L_w [dB]	L_{WA} [dB(A)]	U [dB]	Evaluation
	L_d	F_{pl}	$L_d > F_{pl}$	$F_{+/-}$	$F_{+/-} \leq 3$	$L_{w(1)} - L_{w(2)} \leq s$					
125	20.6	2.7	YES	0.0	YES	YES	YES	68.6	52.1	± 3.0	passed
250	21.0	4.0	YES	0.0	YES	YES	YES	64.9	56.0	± 2.0	passed
500	22.0	2.8	YES	0.0	YES	YES	YES	61.1	57.7	± 1.5	passed
1000	23.3	2.4	YES	0.0	YES	YES	YES	57.5	57.4	± 1.5	passed
2000	21.3	1.9	YES	0.0	YES	YES	YES	51.9	53.1	± 1.5	passed
4000	20.7	2.4	YES	0.0	YES	YES	YES	46.9	47.9	± 1.5	c
8000 ^{*)}	20.7	2.9	YES	0.0	YES	YES	YES	38.3	38.2	± 2.5	c
Total								71.0	63.0	± 1.5	


^{*)} Due to the sound intensity method, the frequency of 6300 Hz was measured only.

Legend:

- passed* Third frequency bands with this description are significant for calculation of A-weighted total sound power level L_{WA} . Required accuracy class is fulfilled in this band.
- not passed* Third frequency bands with this description are significant for calculation of A-weighted total sound power level L_{WA} . Required accuracy class is not fulfilled in this band.
- c* Third frequency bands with this description are not significant for calculating of A-weighted total sound power level L_{WA} . These bands are evaluated in calculating of L_{WA} .
- nc* Third frequency bands with this description are not significant for calculating of A-weighted total sound power level L_{WA} . This bands are not evaluated in calculating of L_{WA} .

Spectrum of Sound power level L_w – octave bands

Air/Water Heat pump Airkompakt p0916 – Outdoor unit at A7/W55 <i>/ Compressor: FIXED, Fan: AUTO, Water pump: -- /</i>	Engineering (Grade 2)
---------------------------------------------------------------------------------------------------------------------------------	----------------------------------



1B) Measurement results – one-third octave bands

Air/Water Heat pump Airkompakt p0916 – Outdoor unit at A7/W55 / Compressor: <u>FIXED</u> , Fan: <u>AUTO</u> , Water pump: -- /	Engineering (Grade 2)
------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------

f _m [Hz]	Criterion 1			Criterion 2		Criterion 3	All criteria passed?	L _w [dB]	L _{WA} [dB(A)]	U [dB]	Evaluation	
	L _d	F _{pl}	L _d > F _{pl}	F ₊₋	F ₊₋ ≤ 3	L _{w(1)} -L _{w(2)} ≤ s						
100	21.0	2.5	YES	0.0	YES	YES	YES	66.0	46.9	± 3.0	passed	
125	20.6	2.7	YES	0.0	YES	YES	YES	62.8	46.7	± 3.0	passed	
160	20.8	4.0	YES	0.0	YES	YES	YES	61.7	48.3	± 3.0	passed	
200	20.9	4.5	YES	0.0	YES	YES	YES	61.6	50.7	± 2.0	passed	
250	21.0	4.0	YES	0.0	YES	YES	YES	60.0	51.4	± 2.0	passed	
315	21.5	3.5	YES	0.0	YES	YES	YES	58.2	51.6	± 2.0	passed	
400	21.9	3.1	YES	0.0	YES	YES	YES	57.1	52.3	± 1.5	passed	
500	22.0	2.8	YES	0.0	YES	YES	YES	56.7	53.5	± 1.5	passed	
630	22.3	2.7	YES	0.0	YES	YES	YES	55.0	53.1	± 1.5	passed	
800	22.3	2.4	YES	0.0	YES	YES	YES	53.5	52.7	± 1.5	passed	
1000	23.3	2.4	YES	0.0	YES	YES	YES	52.3	52.3	± 1.5	passed	
1250	22.5	2.5	YES	0.0	YES	YES	YES	52.2	52.8	± 1.5	passed	
1600	22.9	2.2	YES	0.0	YES	YES	YES	48.0	49.0	± 1.5	passed	
2000	21.3	1.9	YES	0.0	YES	YES	YES	46.0	47.2	± 1.5	passed	
2500	20.4	2.2	YES	0.0	YES	YES	YES	47.2	48.5	± 1.5	passed	
3150	20.8	2.4	YES	0.0	YES	YES	YES	43.9	45.1	± 1.5	passed	
4000	20.7	2.4	YES	0.0	YES	YES	YES	41.0	42.0	± 1.5	c	
5000	20.4	2.3	YES	0.0	YES	YES	YES	40.6	41.1	± 1.5	c	
6300	20.7	2.9	YES	0.0	YES	YES	YES	33.6	33.5	± 2.5	c	
Total									71.0	62.9	± 1.5	

Legend:

passed Third frequency bands with this description are significant for calculation of A-weighted total sound power level L_{WA}. Required accuracy class is fulfilled in this band.


not passed Third frequency bands with this description are significant for calculation of A-weighted total sound power level L_{WA}. Required accuracy class is not fulfilled in this band.

c Third frequency bands with this description are not significant for calculating of A-weighted total sound power level L_{WA}. These bands are evaluated in calculating of L_{WA}.

nc Third frequency bands with this description are not significant for calculating of A-weighted total sound power level L_{WA}. This bands are not evaluated in calculating of L_{WA}.

Spectrum of Sound power level L_w – one-third octave bands

Air/Water Heat pump Airkompakt p0916 – Outdoor unit at A7/W55 / Compressor: <i>FIXED</i> , Fan: <i>AUTO</i> , Water pump: <i>---</i> /	Engineering (Grade 2)
--------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------



Tested by: Ing. Antonín Kolbábek, Ph.D.

Date: 2022-09-14

Signed: 

Reviewed and approved by: Milan Holomek

Date: 2022-09-14

Signed: 

V. A list of referenced documents

- Order B-76791 of 2022-06-29 (Order reg. no. B-76791, received on 2022-06-29)
- Contract B-76791/39

- ČSN EN 14511-2:2019 - Air conditioners, liquid chilling packages and heat pumps for space heating and cooling and process chillers, with electrically driven compressors - Part 2: Test conditions
- ČSN EN 14511-3:2019 - Air conditioners, liquid chilling packages and heat pumps for space heating and cooling a process chillers with electrically driven compressors - Part 3: Test methods
- ČSN EN 14511-4:2019 - Air conditioners, liquid chilling packages and heat pumps for space heating and cooling and process chillers, with electrically driven compressors - Part 4: Requirements
- ČSN EN 14825:2020 - Air conditioners, liquid chilling packages and heat pumps, with electrically driven compressors, for space heating and cooling - Testing and rating at part load conditions and calculation of seasonal performance


- ČSN EN 12102-1:2018 - Air conditioners, liquid chilling packages, heat pumps, process chillers and dehumidifiers with electrically driven compressors - Determination of the sound power level - Part 1: Air conditioners, liquid chilling packages, heat pumps for space heating and cooling, dehumidifiers and process chillers
- ČSN ISO 9614-2:1997 - Acoustics - Determination of sound power levels of noise sources using sound intensity - Part 2: Measurement by scannig

- EHPA Testing regulation – Testing of Air/Water Heat Pumps – Additional requirements for granting the international quality label for heat pumps – Version 2.4a

- Background of the SZÚ task No. 39-16511

- Record measurement file: 39-16511 P.P.H.U. (AW-EHPA).zip

Test Report compiled by: Ing. Antonín Kolbábek, Ph.D.
Head of Acoustics and Ventilation systems department / Test engineer

Test Report approved by: 
Milan Holomek
Head of Heat and Environment-Friendly Equipment Test Station



– End of Test Report –



CORRECTED COPY

Testing Laboratory 1045.1 accredited by the Czech Accreditation Institute pursuant to
ČSN EN ISO/IEC 17025:2018

Strojírenský zkušební ústav, s.p. Zkušební laboratoř
(Engineering Test Institute, Public Enterprise, Testing Laboratory)
Hudcova 424/56b, Medlánky, 621 00 Brno

Page 1 of 55



TEST REPORT

39-16511/T

Product: Outdoor Air/Water Heat Pump – monobloc

Type designation: Airkompakt p0916

Customer: KOŁTON SPÓŁKA KOMANDYTOWA
ul. Sosnowa 2
34-480 Jabłonka
POLSKA

Manufacturer: KOŁTON SPÓŁKA KOMANDYTOWA
ul. Sosnowa 2
34-480 Jabłonka
POLSKA

Employee responsible: Ing. Mario Jankola

Report issue date: 2022-09-16

Distribution list: 1 copy to the Customer
1 copy to the Engineering Test Institute

This document may be copied in its entirety without written consent of the Engineering Test Institute. Partial copies are subject to approval. The results of the tests and verifications shall relate only to the products tested as received or presented. The testing laboratory is not responsible for the data provided by the customer specified in the report.

SP-2021-000012_1_4_Protokol_ZL_2022_AKR_EN


I. Description of product tested

The Heat pump **Airkompakt p0916** supplied by the company **KOLTON SPÓLKA KOMANDYTOWA** is structurally adapted to operate in air/water system. Device is designed as monobloc. Refrigerant R290 is used with charge 1.5 kg. Power supply is a three-phase. Heat pump is able to work in heating and cooling mode. Heat pump is working with fixed flow rate.

Main components of the unit **Airkompakt p0916**:

- Serial number 22PC09020010085
- Cubic shape with dimensions 1300 × 590 × 1030 mm (W × D × H)
- Frame and casing made of varnished steel sheets
- Cubic-shaped evaporator, 3 rows, dimensions 800 × 55 × 885 mm (W × D × H), spacing 2.0 mm
- Plate condenser, dimensions 160 × 140 × 560 mm (W × D × H) including insulation
- Compressor Copeland Scroll ZH08KCU-TFMN-524
- Refrigerant R290 (1.5 kg)
- Electric expansion valve
- 4-way reversing valve Sanhua SHF(L)-11H-35U-52
- Refrigerant accumulator
- Axial fan Ø65 cm
- Pressure sensors
- Temperature sensors
- Filter drier
- Refrigerant pipes

Scheme:




Photodocumentation:



Heat pump **Airkompakt p0916**
– Front view –



Heat pump **Airkompakt p0916**
– Back view –



Heat pump **Airkompakt p0916**
– Compressor label –

KOLTON	
PPH/Kolton s.r.o. Savova 2 26400 Jatečka www.kolton.cz	Typ: AIRKOMPACT P0916
Roční výroba: 12 202 26 07 26-06/2023a 2023	Model: 2SPC0900010028
Typ: AIRKOMPACT P0916	Max. výkon: 400 V; 3 ~; 50 Hz
Max. výkon: 400 V; 3 ~; 50 Hz	Max. proud: 7,1 A
Max. proud: 7,1 A	Stupeň ochrany IP: IP 24
Stupeň ochrany IP: IP 24	Max. výkon: 44-52 [dB]
Max. výkon: 44-52 [dB]	Max. výkon: 9,36 kW
Max. výkon: 9,36 kW	Max. výkon: 2,18 kW
Max. výkon: 2,18 kW	COP A7 W35: 4,61
COP A7 W35: 4,61	Max. výkon: 9200 / 1,2 kg
Max. výkon: 9200 / 1,2 kg	Max. výkon: 26 bar
Max. výkon: 26 bar	Max. výkon: 3,6 bar
Max. výkon: 3,6 bar	Max. výkon: 65 °C
Max. výkon: 65 °C	Max. výkon: 4 L
Max. výkon: 4 L	Max. výkon: 180 kg
Max. výkon: 180 kg	
<p>UWAGA! Serwis tylko dla wykwalifikowanego personelu (AUTOMATY) Service only for qualified in high-voltage refrigerant (HC) staff! ACHTUNG! Service nur für qualifizierte Mitarbeiter mit Kühlmittel-Service (HC)!</p>	

Heat pump **Airkompakt p0916**
– Label –



Heat pump Airkompakt p0916
– Without cover –

II. Sample tested

SZU reg. no.	Product name	Date of submission
0213.22.37137.001	Airkompakt p0916	2022-08-22

The visual inspection, tests and verification were carried out by Ing. Michal Faltýnek at the test station of SZU

The tests were performed using measuring and testing equipment with valid calibration.

III. Measuring and test equipment:

No.	Description:	Inventory number:
1.	Electrical energy meter	022370/1
2.	Flow meter Krohne Optiflux	022370/5
3.	Barometer	022370/7
4.	Differential pressure gauge	MaR01_T1
5.	Temperature-humidity meter HC2-IC305	022370/10
6.	Temperature-humidity meter HC2-IC305	022370/11
7.	Thermometers	022370/13

Measured quantity	Unit	Uncertainty measurement	of	Evaluation
Liquid				
- temperature difference (dT)	[K]	± 0.15 K		fulfilled
- temperature inlet/outlet	[°C]	± 0.15 K		fulfilled
- volume flow	[m ³ /s]	± 1 %		fulfilled
- static pressure difference	[kPa]	± 1 kPa ($\Delta p \leq 20$ kPa) or ± 5 % ($\Delta p > 20$ kPa)		fulfilled
Air				
- dry bulb temperature	[°C]	± 0.2 K		fulfilled
- wet bulb temperature	[°C]	± 0.4 K		fulfilled
- volume flow	[m ³ /s]	± 5 %		not applied
- static pressure difference	[Pa]	± 5 Pa ($\Delta p \leq 100$ Pa) or ± 5 % ($\Delta p > 100$ Pa)		not applied
Refrigerant				
- pressure at compressor outlet	[kPa]	± 1 %		not applied
- temperature	[°C]	± 0.5 K		not applied
Concentration (in volume)				
- heat transfer medium	[%]	± 2		not related
Electrical quantities				
- electric power	[W]	± 1 %		fulfilled
- voltage	[V]	± 0.5 %		fulfilled
- current	[A]	± 0.5 %		fulfilled
- electric energy	[kWh]	± 1 %		not applied
Compressor rotational speed	[min ⁻¹]	± 0.5 %		not applied
The heating or cooling capacities measured on the liquid side shall be determined within a maximum uncertainty of 5 % independent of the individual uncertainties of measurement including the uncertainties on the properties of fluids.				fulfilled

Note:

The stated extended measurement uncertainties are calculated as a factor of the measurement uncertainty and the extension coefficient $k=2$, corresponding to the coverage certainty of 95% as regards standard classification.

If a statement of conformity is provided, the decision rule pursuant to ILAC-G8:09/2019, Art. 4.2.1 - binary statement for the simple acceptance rule shall apply.

Comment to abbreviated marking: e.g. A7/W35

A (air) 7 (input air, dry-bulb temperature in °C) / W (water), 35 (output heating water temperature in °C)

Test objective:	Rating conditions
Exact name of the test procedure:	T 037* - Tests of leakage, pressure resistance, thermal and technical parameters, combustion efficiency, safety functions
Test method:	ČSN EN 14511-2:2019, ČSN EN 14511-3:2019
Sample tested:	Heat pump Airkompakt p0916
Measuring equipment used:	see Chapter III

Specification of the assessment condition*		A7/W35	A7/W55
Date of testing		2022-08-22	2022-08-24
Transient test procedure	YES / NO	NO	NO
Average defrost time of 1 cycle	[min]	–	–
Average time of 1 cycle	[min]	–	–
Calculation time	[min]	70.0	70.0
Output heating water – temperature calculation	[°C]	34.96	55.01
Input heating water – temperature calculation	[°C]	30.00	46.98
Output heating water temperature	[°C]	34.96	55.01
Input heating water temperature	[°C]	30.00	46.98
Air temperature – dry bulb temperature	[°C]	7.11	7.11
Air temperature – wet bulb temperature	[°C]	6.12	6.11
Relative humidity	[%]	87.02	86.83
Barometric pressure	[kPa]	98.164	98.730
Ambient temperature	[°C]	7.11	7.11
Secondary circuit pressure difference	[kPa]	-15.335	-5.270
Efficiency of the secondary liquid pump	[-]	0.196	0.129
Volume flow rate of heating water	[m ³ ·h ⁻¹]	1.5781	0.9178
Density of heating water	[kg·m ⁻³]	994.0	985.8
Specific heat capacity of heating water	[kJ·kg ⁻¹ ·K ⁻¹]	4.180	4.180
Voltage	[V]	399.52	399.50
Total current	[A]	11.44	14.13
Overall power input	[kW]	1.916	2.667
Capacity correction of sec. liquid pump	[W]	-27.543	-9.036
Power input correction of sec. liquid pump	[W]	-34.27	-10.38
Heating capacity – heating water	[kW]	9.034	8.419
Corrected heating capacity – heating water	[kW]	9.062	8.428
Uncertainty of corrected heating capacity	[kW]	± 0.156	± 0.094
Effective electric power input	[kW]	1.950	2.678
COP	[-]	4.647	3.148
Uncertainty of COP	[-]	± 0.081	± 0.035
Control settings	[-]	–	–
Circulation pump settings – heating water	[-]	–	–

Test objective:	Seasonal performance tests and SCOP calculation – Low temperature application
Exact name of the test procedure:	T 037* - Tests of leakage, pressure resistance, thermal and technical parameters, combustion efficiency, safety functions
Test method:	ČSN EN 14511-3:2019, ČSN EN 14825:2020
Sample tested:	Heat pump Airkompakt p0916
Measuring equipment used:	see Chapter III

Design		Air / water – monobloc			
Conditions specification according to ČSN EN 14825:2020	Temperature application		Low (reference water temperature 35 °C)		
	Reference heating season		Average		
	Outlet water temperature - indoor heat exchanger		Variable		
	Compressor speed control		Fixed		
	Water flow rate – primary circuit		–		
	Water flow rate – secondary circuit		Fixed		
Seasonal space heating energy efficiency	Heating	Average	η_s	157.2	%
		Warmer	η_s	196.9 (Not tested)	%
		Colder	η_s	138.7 (Not tested)	%
Seasonal efficiency according to ČSN EN 14825:2020	Heating	Average	SCOP	4.00	–
		Warmer	SCOP	5.00 (Not tested)	–
		Colder	SCOP	3.54 (Not tested)	–
Function	Cooling		Yes		
	Heating	Yes	Reference heating season	Average	Yes
				Warmer	Yes
				Colder	Yes
Full heating load	Cooling		$P_{designc}$	–	kW
	Heating	Average	$P_{designh}$	6.20	kW
		Warmer	$P_{designh}$	7.00	kW
		Colder	$P_{designh}$	5.65	kW
Bivalent temperatures	Heating	Average	$T_{bivalent}$	-7	°C
		Warmer	$T_{bivalent}$	2	°C
		Colder	$T_{bivalent}$	-15	°C
Operation limit temperatures	Heating	Average	TOL	-10	°C
		Warmer	TOL	2	°C
		Colder	TOL	-22	°C
Seasonal power consumption according to ČSN EN 14825:2020	Cooling		Q_{CE}	–	kWh
	Heating	Average	Q_{HE}	3197	kWh
		Warmer	Q_{HE}	1870 (Not tested)	kWh
		Colder	Q_{HE}	3930 (Not tested)	kWh
Modes other than „active mode“	Off mode		P_{OFF}	14.8	W
	Thermostat off mode		P_{TO}	14.7	W
	Standby mode		P_{SB}	14.8	W
	Crankcase heater mode		P_{CK}	0.0	W

(Not tested): The technical data were declared by the Manufacturer and were not tested by the Testing Laboratory.

Calculation of SCOP according to ČSN EN 14825:2020:

Number of hours used for calculation of reference SCOP (Annex B – Table B. 2, B. 3)

- For reversible heat pumps and reference heating season „A“ = average

H_{HE}	2066	[h]
H_{TO}	178	[h]
H_{SB}	0	[h]
H_{CK}	178	[h]
H_{OFF}	0	[h]

Measured data:

P_{TO}	0.0147	[kW]
P_{SB}	0.0148	[kW]
P_{CK}	0.0000	[kW]
P_{OFF}	0.0148	[kW]
$P_{designh}$	6.20	[kW]
$SCOP_{ON}$	4.01	[-]

Coefficient and correction:

$F(1)$	3	[%]
$F(2)$	0	[%]
CC	2.5	[-]

Calculation of SCOP:

7.3 Calculation of the reference annual heating demand (Q_H)

$$Q_H = P_{designh} \cdot H_{HE} \quad [kWh]$$

$$Q_H = 6.2 \cdot 2066 = 12802 \quad [kWh]$$

7.4 Calculation of the annual electricity consumption (Q_{HE})

$$Q_{HE} = Q_H / SCOP_{on} + H_{TO} \cdot P_{TO} + H_{SB} \cdot P_{SB} + H_{CK} \cdot P_{CK} + H_{OFF} \cdot P_{OFF} \quad [kWh]$$

$$Q_{HE} = 12802 / 4.01 + 178 \cdot 0.0147 + 0 \cdot 0.0148 + 178 \cdot 0 + 0 \cdot 0.0148 = 3197 \quad [kWh]$$

7.2 General formula for calculation of reference SCOP

$$SCOP = Q_H / Q_{HE} \quad [-]$$

$$SCOP = 12802 / 3197 = 4 \quad [-]$$

7.1 Calculation of the seasonal space heating efficiency η_s

$$\Sigma F(i) = F(1) + F(2) \quad [-]$$

$$\Sigma F = 0.03 + 0 = 0.03 \quad [-]$$

$$\eta_s = 1 / CC \cdot SCOP - \Sigma F(i) \quad [-]$$

$$\eta_s (A) = (1 / 2.5) \cdot 4 - 0.03 = \underline{1.572} \quad [-]$$

Temperature level		Low (reference water temperature 35 °C)		
Reference heating season		„A“ = average ($T_{designh} = -10\text{ °C}$)		
Assessment condition		B	C	D
Specification of the assessment condition*		A2/W32.06	A7/W30.9	A12/W29.33
Date of testing		2022-08-26	2022-08-29	2022-08-29
Transient test procedure	YES / NO	YES	NO	NO
Average defrost time of 1 cycle	[min]	3.1	–	–
Average time of 1 cycle	[min]	69.0	–	–
Calculation time	[min]	137.9	70.0	70.0
Output heating water – temperature calculation	[°C]	31.44	30.87	29.27
Input heating water – temperature calculation	[°C]	27.57	25.83	23.45
Output heating water temperature	[°C]	32.02	30.87	29.27
Input heating water temperature	[°C]	27.74	25.83	23.45
Air temperature – dry bulb temperature	[°C]	2.09	7.10	12.03
Air temperature – wet bulb temperature	[°C]	1.08	6.08	11.01
Relative humidity	[%]	83.73	86.60	88.78
Barometric pressure	[kPa]	98.053	98.765	98.687
Ambient temperature	[°C]	2.09	7.10	12.03
Secondary circuit pressure difference	[kPa]	-15.867	-16.100	-16.248
Efficiency of the secondary liquid pump	[-]	0.199	0.200	0.200
Volume flow rate of heating water	[m ³ ·h ⁻¹]	1.5755	1.5745	1.5737
Density of heating water	[kg·m ⁻³]	995.1	995.3	995.7
Specific heat capacity of heating water	[kJ·kg ⁻¹ ·K ⁻¹]	4.180	4.180	4.180
Voltage	[V]	399.53	399.75	399.75
Total current	[A]	11.02	10.93	10.83
Overall power input	[kW]	1.787	1.760	1.726
Capacity correction of sec. liquid pump	[W]	-28.006	-28.203	-28.329
Power input correction of sec. liquid pump	[W]	-34.95	-35.24	-35.43
Heating capacity – heating water	[kW]	7.038	9.181	10.583
Corrected heating capacity – heating water	[kW]	7.066	9.209	10.611
Uncertainty of corrected heating capacity	[kW]	± 0.156	± 0.156	± 0.157
Effective electric power input	[kW]	1.822	1.795	1.761
COP	[-]	3.878	5.130	6.025
Uncertainty of COP	[-]	± 0.086	± 0.088	± 0.090
Control settings	[-]	–	–	–
Circulation pump settings – heating water	[-]	–	–	–

Temperature level		Low (reference water temperature 35 °C)		
Reference heating season		„A“ = average (T _{designh} = -10 °C)	„W“ = warmer (T _{designh} = 2 °C)	
Assessment condition		TOL (E)	Tbiv (F)	Tbiv (F)
Specification of the assessment condition*		A-10/W35	A-7/W34	A2/W35
Date of testing		2022-08-24	2022-08-24	2022-08-26
Transient test procedure	YES / NO	NO	YES	YES
Average defrost time of 1 cycle	[min]	–	2.8	3.0
Average time of 1 cycle	[min]	–	133.4	71.4
Calculation time	[min]	70.0	133.4	142.9
Output heating water – temperature calculation	[°C]	34.99	33.74	34.35
Input heating water – temperature calculation	[°C]	32.11	30.74	30.52
Output heating water temperature	[°C]	34.99	34.00	34.99
Input heating water temperature	[°C]	32.11	30.84	30.76
Air temperature – dry bulb temperature	[°C]	-9.97	-7.00	2.09
Air temperature – wet bulb temperature	[°C]	-10.97	-8.05	1.07
Relative humidity	[%]	69.93	73.77	83.66
Barometric pressure	[kPa]	98.767	98.770	98.204
Ambient temperature	[°C]	-9.97	-7.00	2.09
Secondary circuit pressure difference	[kPa]	-15.669	-15.785	-15.727
Efficiency of the secondary liquid pump	[-]	0.198	0.198	0.198
Volume flow rate of heating water	[m ³ ·h ⁻¹]	1.5749	1.5767	1.5754
Density of heating water	[kg·m ⁻³]	994.0	994.4	994.1
Specific heat capacity of heating water	[kJ·kg ⁻¹ ·K ⁻¹]	4.180	4.180	4.180
Voltage	[V]	399.61	399.85	399.87
Total current	[A]	11.27	11.24	11.32
Overall power input	[kW]	1.868	1.854	1.877
Capacity correction of sec. liquid pump	[W]	-27.820	-27.943	-27.878
Power input correction of sec. liquid pump	[W]	-34.68	-34.86	-34.76
Heating capacity – heating water	[kW]	5.232	5.454	6.968
Corrected heating capacity – heating water	[kW]	5.260	5.482	6.996
Uncertainty of corrected heating capacity	[kW]	± 0.155	± 0.155	± 0.155
Effective electric power input	[kW]	1.902	1.889	1.911
COP	[-]	2.765	2.902	3.660
Uncertainty of COP	[-]	± 0.082	± 0.082	± 0.082
Control settings	[-]	–	–	–
Circulation pump settings – heating water	[-]	–	–	–

Temperature level		Low (reference water temperature 35 °C)	
Reference heating season		„C“ = colder ($T_{designh} = -22\text{ °C}$)	
Assessment condition		TOL (E)	Tbiv (F)
Specification of the assessment condition*		A-22/W35	A-15/W32
Date of testing		2022-08-23	2022-08-23
Transient test procedure	YES / NO	NO	NO
Average defrost time of 1 cycle	[min]	–	–
Average time of 1 cycle	[min]	–	–
Calculation time	[min]	70.0	70.0
Output heating water – temperature calculation	[°C]	35.00	32.00
Input heating water – temperature calculation	[°C]	32.99	29.49
Output heating water temperature	[°C]	35.00	32.00
Input heating water temperature	[°C]	32.99	29.49
Air temperature – dry bulb temperature	[°C]	-22.08	-14.97
Air temperature – wet bulb temperature	[°C]	-22.58	-15.83
Relative humidity	[%]	61.85	63.38
Barometric pressure	[kPa]	98.447	98.480
Ambient temperature	[°C]	-22.08	-14.97
Secondary circuit pressure difference	[kPa]	-20.282	-12.377
Efficiency of the secondary liquid pump	[-]	0.220	0.181
Volume flow rate of heating water	[m ³ ·h ⁻¹]	1.5786	1.5814
Density of heating water	[kg·m ⁻³]	994.0	994.9
Specific heat capacity of heating water	[kJ·kg ⁻¹ ·K ⁻¹]	4.180	4.180
Voltage	[V]	400.22	399.76
Total current	[A]	10.97	10.92
Overall power input	[kW]	1.774	1.760
Capacity correction of sec. liquid pump	[W]	-31.622	-24.571
Power input correction of sec. liquid pump	[W]	-40.52	-30.01
Heating capacity – heating water	[kW]	3.654	4.581
Corrected heating capacity – heating water	[kW]	3.686	4.606
Uncertainty of corrected heating capacity	[kW]	± 0.155	± 0.155
Effective electric power input	[kW]	1.814	1.790
COP	[-]	2.031	2.573
Uncertainty of COP	[-]	± 0.086	± 0.087
Control settings	[-]	–	–
Circulation pump settings – heating water	[-]	–	–

Data for SCOP calculation

- Low temperature application (reference water temperature 35 °C)
- Reference heating season „A“ – average

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (Tj)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]	[%]	[kW]	[kW]	[-]	[-]	[-]	[-]	[kW]
A	-7	34.00	88.46	5.48	5.482	2.902	0.900	1.00	2.902	–
B	2	32.06	53.85	3.34	7.066	3.878	0.992	0.47	3.843	0.0147
C	7	30.90	34.62	2.15	9.209	5.130	0.992	0.23	4.995	0.0147
D	12	29.33	15.38	0.95	10.611	6.025	0.992	0.09	5.555	0.0147
TOL (E)	-10	35.00	100.00	6.20	5.260	2.765	0.900	1.18	2.765	–
Tbiv (F)	-7	34.00	88.46	5.48	5.482	2.902	0.900	1.00	2.902	–

Adaption of water temperature – according to ČSN EN 14825:2020, Annex F

- Low temperature application (reference water temperature 35 °C)
- Reference season „A“ – average
- Condition D
- Fixed water flow rate – secondary circuit

General formulas and derivation:

$$t_{\text{outlet, average}} = t_{\text{inlet, capacity test}} + (t_{\text{outlet, capacity test}} - t_{\text{inlet, capacity test}}) \cdot CR \quad [^{\circ}\text{C}]$$

$$t_{\text{outlet, average}} = t_{\text{inlet, capacity test}} + (\Delta t) \cdot CR \quad [^{\circ}\text{C}]$$

$$t_{\text{outlet, average}} = t_{\text{outlet, capacity test}} - \Delta t + \Delta t \cdot CR \quad [^{\circ}\text{C}]$$

$$t_{\text{outlet, capacity test}} = t_{\text{outlet, average}} + \Delta t - \Delta t \cdot CR \quad [^{\circ}\text{C}]$$

For fixed flow:

$$\Delta t = \text{Declared capacity} / \text{Declared capacity}_{\text{standard rating conditions A7W35}} \cdot 5$$

$$CR \cdot \Delta t = \text{Part load} / \text{Declared capacity} \cdot \text{Declared capacity} / \text{Declared capacity}_{\text{standard rating conditions A7W35}} \cdot 5$$

$$CR \cdot \Delta t = \text{Part load} / \text{Declared capacity}_{\text{standard rating conditions A7W35}} \cdot 5$$

$$t_{\text{outlet, capacity test, fixed flow}} = t_{\text{outlet, average}} + \text{Declared capacity} / \text{Declared capacity}_{\text{standard rating conditions A7W35}} \cdot 5 - \text{Part load} / \text{Declared capacity}_{\text{standard rating conditions A7W35}} \cdot 5$$

$$t_{\text{outlet, capacity test, fixed flow}} = t_{\text{outlet, average}} + 5 / \text{Declared capacity}_{\text{standard rating conditions A7W35}} \cdot (\text{Declared capacity} - \text{Part load})$$

Measured data:

$t_{\text{outlet, average}}$	24.00	[°C]
Declared capacity	10.611	[kW]
Declared capacity standard rating condition A7W35	9.062	[kW]
Part load	0.95	[kW]

Calculation of water temperature

$$t_{\text{outlet, capacity test, fixed flow}} = 24 + 5 / 9.062 \cdot (10.611 - 0.95) = \underline{\underline{29.33}} \quad [^{\circ}\text{C}]$$

Calculation SCOP, SCOP_{on}, SCOP_{net}


- Low temperature application (reference water temperature 35 °C)
- Reference heating season „A” – average

Bin	Outdoor temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistive heat elbu (Tj)	Annual resistive heat	COPbin (Tj)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating	
j	Tj	hj		Ph(Tj)			elbu(Tj)	hj x elbu(Tj)	COPbin (Tj)	hj x Ph(Tj)		hj x (Ph(Tj) - elbu(Tj))		
[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]	
TOL (E)	21	-10	1	100.00	6.20	5.26	5.26	0.94	0.94	2.77	6	3	5	2
	22	-9	25	96.15	5.96	5.33	5.33	0.62	15.62	2.81	149	63	133	47
	23	-8	23	92.31	5.72	5.41	5.41	0.31	7.19	2.86	132	51	124	44
A, Tdiv (F)	24	-7	24	88.46	5.48	5.48	5.48	0.00	0.00	2.90	132	45	132	45
	25	-6	27	84.62	5.24	5.66	5.24	0.00	0.00	3.01	142	47	142	47
	26	-5	68	80.77	5.01	5.83	5.01	0.00	0.00	3.11	340	109	340	109
	27	-4	91	76.92	4.77	6.01	4.77	0.00	0.00	3.22	434	135	434	135
	28	-3	89	73.08	4.53	6.19	4.53	0.00	0.00	3.32	403	121	403	121
	29	-2	165	69.23	4.29	6.36	4.29	0.00	0.00	3.42	708	207	708	207
	30	-1	173	65.38	4.05	6.54	4.05	0.00	0.00	3.53	701	199	701	199
	31	0	240	61.54	3.81	6.71	3.81	0.00	0.00	3.63	915	252	915	252
	32	1	280	57.69	3.58	6.89	3.58	0.00	0.00	3.74	1001	268	1001	268
B	33	2	320	53.85	3.34	7.07	3.34	0.00	0.00	3.84	1068	278	1068	278
	34	3	357	50.00	3.10	7.49	3.10	0.00	0.00	4.07	1106	272	1106	272
	35	4	356	46.15	2.86	7.92	2.86	0.00	0.00	4.30	1018	237	1018	237
	36	5	303	42.31	2.62	8.35	2.62	0.00	0.00	4.53	794	175	794	175
	37	6	330	38.46	2.38	8.78	2.38	0.00	0.00	4.76	787	165	787	165
C	38	7	326	34.62	2.15	9.21	2.15	0.00	0.00	5.00	699	140	699	140
	39	8	348	30.77	1.91	9.49	1.91	0.00	0.00	5.11	664	130	664	130
	40	9	335	26.92	1.67	8.77	1.67	0.00	0.00	5.22	559	107	559	107
	41	10	315	23.08	1.43	10.05	1.43	0.00	0.00	5.33	450	84	450	84
	42	11	215	19.23	1.19	10.33	1.19	0.00	0.00	5.44	256	47	256	47
D	43	12	169	15.38	0.95	10.61	0.95	0.00	0.00	5.56	161	29	161	29
	44	13	151	11.54	0.72	10.89	0.72	0.00	0.00	5.67	108	19	108	19
	45	14	105	7.69	0.48	11.17	0.48	0.00	0.00	5.78	50	9	50	9
	46	15	74	3.85	0.24	11.45	0.24	0.00	0.00	5.89	18	3	18	3
	Σ		4910							Σ	12800	3194	12776	3170

SCOP _{on}	4.01	SCOP _{net}	4.03
		SCOP	4.00

Part load performance diagram

- Low temperature application (reference water temperature 35 °C)
- Reference heating season „A“ – average



Test objective:	Seasonal performance tests and SCOP calculation – Medium temperature application
Exact name of the test procedure:	T 037* - Tests of leakage, pressure resistance, thermal and technical parameters, combustion efficiency, safety functions
Test method:	ČSN EN 14511-3:2019, ČSN EN 14825:2020
Sample tested:	Heat pump Airkompakt p0916
Measuring equipment used:	see Chapter III

Design		Air / water – monobloc			
Conditions specification according to ČSN EN 14825:2020	Temperature application		Medium (reference water temperature 55 °C)		
	Reference heating season		Average		
	Outlet water temperature - indoor heat exchanger		Variable		
	Compressor speed control		Fixed		
	Water flow rate – primary circuit		–		
	Water flow rate – secondary circuit		Fixed		
Seasonal space heating energy efficiency	Heating	Average	η_s	127.0	%
		Warmer	η_s	158.4 (Not tested)	%
		Colder	η_s	109.8 (Not tested)	%
Seasonal efficiency according to ČSN EN 14825:2020	Heating	Average	SCOP	3.25	–
		Warmer	SCOP	4.03 (Not tested)	–
		Colder	SCOP	2.82 (Not tested)	–
Function	Cooling		Yes		
	Heating	Yes	Reference heating season	Average	Yes
				Warmer	Yes
				Colder	Yes
Full heating load	Cooling		$P_{designc}$	–	kW
	Heating	Average	$P_{designh}$	6.28	kW
		Warmer	$P_{designh}$	6.52	kW
		Colder	$P_{designh}$	5.29	kW
Bivalent temperatures	Heating	Average	$T_{bivalent}$	-7	°C
		Warmer	$T_{bivalent}$	2	°C
		Colder	$T_{bivalent}$	-15	°C
Operation limit temperatures	Heating	Average	TOL	-10	°C
		Warmer	TOL	2	°C
		Colder	TOL	-19	°C
Seasonal power consumption according to ČSN EN 14825:2020	Cooling		Q_{CE}	–	kWh
	Heating	Average	Q_{HE}	3995	kWh
		Warmer	Q_{HE}	2159 (Not tested)	kWh
		Colder	Q_{HE}	4624 (Not tested)	kWh
Modes other than „active mode“	Off mode		P_{OFF}	14.8	W
	Thermostat off mode		P_{TO}	14.7	W
	Standby mode		P_{SB}	14.8	W
	Crankcase heater mode		P_{CK}	0.0	W

(Not tested): The technical data were declared by the Manufacturer and were not tested by the Testing Laboratory.

Calculation of SCOP according to ČSN EN 14825:2020:

Number of hours used for calculation of reference SCOP (Annex B – Table B. 2, B. 3)

- For reversible heat pumps and reference heating season „A“ = average

H _{HE}	2066	[h]
H _{TO}	178	[h]
H _{SB}	0	[h]
H _{CK}	178	[h]
H _{OFF}	0	[h]

Measured data:

P _{TO}	0.0147	[kW]
P _{SB}	0.0148	[kW]
P _{CK}	0.0000	[kW]
P _{OFF}	0.0148	[kW]
P _{designh}	6.28	[kW]
SCOP _{ON}	3.25	[-]

Coefficient and correction:

F(1)	3	[%]
F(2)	0	[%]
CC	2.5	[-]

Calculation of SCOP:

7.3 Calculation of the reference annual heating demand (Q_H)

$$Q_H = P_{designh} \cdot H_{HE} \quad [kWh]$$

$$Q_H = 6.28 \cdot 2066 = 12981 \quad [kWh]$$

7.4 Calculation of the annual electricity consumption (Q_{HE})

$$Q_{HE} = Q_H / SCOP_{on} + H_{TO} \cdot P_{TO} + H_{SB} \cdot P_{SB} + H_{CK} \cdot P_{CK} + H_{OFF} \cdot P_{OFF} \quad [kWh]$$

$$Q_{HE} = 12981 / 3.25 + 178 \cdot 0.0147 + 0 \cdot 0.0148 + 178 \cdot 0 + 0 \cdot 0.0148 = 3995 \quad [kWh]$$

7.2 General formula for calculation of reference SCOP

$$SCOP = Q_H / Q_{HE} \quad [-]$$

$$SCOP = 12981 / 3995 = 3.25 \quad [-]$$

7.1 Calculation of the seasonal space heating efficiency η_s

$$\Sigma F(i) = F(1) + F(2) \quad [-]$$

$$\Sigma F = 0.03 + 0 = 0.03 \quad [-]$$

$$\eta_s = 1 / CC \cdot SCOP - \Sigma F(i) \quad [-]$$

$$\eta_s (A) = (1 / 2.5) \cdot 3.25 - 0.03 = 1.27 \quad [-]$$

Temperature level		Medium (reference water temperature 55 °C)		
Reference heating season		„A“ = average ($T_{design} = -10\text{ °C}$)		
Assessment condition		B	C	D
Specification of the assessment condition*		A2/W45.3	A7/W42.34	A12/W38.95
Date of testing		2022-08-29	2022-08-25	2022-08-25
Transient test procedure	YES / NO	YES	NO	NO
Average defrost time of 1 cycle	[min]	2.9	–	–
Average time of 1 cycle	[min]	77.8	–	–
Calculation time	[min]	155.5	70.0	70.0
Output heating water – temperature calculation	[°C]	44.43	42.34	38.95
Input heating water – temperature calculation	[°C]	37.93	33.97	29.13
Output heating water temperature	[°C]	45.30	42.34	38.95
Input heating water temperature	[°C]	38.23	33.97	29.13
Air temperature – dry bulb temperature	[°C]	2.03	7.09	12.02
Air temperature – wet bulb temperature	[°C]	1.03	6.08	11.01
Relative humidity	[%]	83.76	86.76	88.86
Barometric pressure	[kPa]	98.853	98.487	98.398
Ambient temperature	[°C]	2.03	7.09	12.02
Secondary circuit pressure difference	[kPa]	-5.461	-5.384	-5.387
Efficiency of the secondary liquid pump	[-]	0.130	0.130	0.130
Volume flow rate of heating water	[m ³ ·h ⁻¹]	0.9181	0.9191	0.9160
Density of heating water	[kg·m ⁻³]	990.4	991.3	992.6
Specific heat capacity of heating water	[kJ·kg ⁻¹ ·K ⁻¹]	4.180	4.180	4.180
Voltage	[V]	399.66	399.50	399.74
Total current	[A]	12.37	12.08	11.64
Overall power input	[kW]	2.186	2.103	1.972
Capacity correction of sec. liquid pump	[W]	-9.311	-9.208	-9.186
Power input correction of sec. liquid pump	[W]	-10.70	-10.58	-10.56
Heating capacity – heating water	[kW]	6.856	8.845	10.359
Corrected heating capacity – heating water	[kW]	6.865	8.854	10.368
Uncertainty of corrected heating capacity	[kW]	± 0.093	± 0.095	± 0.097
Effective electric power input	[kW]	2.197	2.114	1.982
COP	[-]	3.125	4.189	5.230
Uncertainty of COP	[-]	± 0.042	± 0.045	± 0.049
Control settings	[-]	–	–	–
Circulation pump settings – heating water	[-]	–	–	–

Temperature level		Medium (reference water temperature 55 °C)		
Reference heating season		„A“ = average ($T_{designh} = -10\text{ °C}$)	„W“ = warmer ($T_{designh} = 2\text{ °C}$)	
Assessment condition		TOL (E)	Tbiv (F)	Tbiv (F)
Specification of the assessment condition*		A-10/W55	A-7/W52	A2/W55
Date of testing		2022-08-25	2022-08-25	2022-08-26
Transient test procedure	YES / NO	NO	NO	YES
Average defrost time of 1 cycle	[min]	–	–	2.8
Average time of 1 cycle	[min]	–	–	79.4
Calculation time	[min]	70.0	70.0	158.9
Output heating water – temperature calculation	[°C]	55.00	52.00	54.13
Input heating water – temperature calculation	[°C]	50.12	46.72	47.92
Output heating water temperature	[°C]	55.00	52.00	55.02
Input heating water temperature	[°C]	50.12	46.72	48.25
Air temperature – dry bulb temperature	[°C]	-9.96	-6.93	2.07
Air temperature – wet bulb temperature	[°C]	-10.97	-7.93	1.05
Relative humidity	[%]	69.69	73.80	83.71
Barometric pressure	[kPa]	98.642	98.612	97.958
Ambient temperature	[°C]	-9.96	-6.93	2.07
Secondary circuit pressure difference	[kPa]	-5.220	-5.252	-5.244
Efficiency of the secondary liquid pump	[-]	0.129	0.129	0.129
Volume flow rate of heating water	[m ³ ·h ⁻¹]	0.9165	0.9176	0.9159
Density of heating water	[kg·m ⁻³]	985.8	987.2	986.2
Specific heat capacity of heating water	[kJ·kg ⁻¹ ·K ⁻¹]	4.180	4.180	4.180
Voltage	[V]	399.82	399.64	399.75
Total current	[A]	13.67	13.21	13.89
Overall power input	[kW]	2.549	2.422	2.599
Capacity correction of sec. liquid pump	[W]	-8.951	-9.008	-8.982
Power input correction of sec. liquid pump	[W]	-10.28	-10.35	-10.32
Heating capacity – heating water	[kW]	5.118	5.549	6.512
Corrected heating capacity – heating water	[kW]	5.127	5.558	6.521
Uncertainty of corrected heating capacity	[kW]	± 0.091	± 0.091	± 0.092
Effective electric power input	[kW]	2.559	2.433	2.609
COP	[-]	2.003	2.285	2.500
Uncertainty of COP	[-]	± 0.036	± 0.038	± 0.035
Control settings	[-]	–	–	–
Circulation pump settings – heating water	[-]	–	–	–

Temperature level		Medium (reference water temperature 55 °C)	
Reference heating season		„C“ = colder ($T_{designh} = -22\text{ °C}$)	
Assessment condition		D	Tbiv (F)
Specification of the assessment condition*		A12/W37.4	A-15/W49
Date of testing		2022-08-31	2022-08-30
Transient test procedure	ANO / NE	NO	NO
Average defrost time of 1 cycle	[min]	–	–
Average time of 1 cycle	[min]	–	–
Calculation time	[min]	70.0	70.0
Output heating water – temperature calculation	[°C]	37.35	49.00
Input heating water – temperature calculation	[°C]	27.46	44.91
Output heating water temperature	[°C]	37.35	49.00
Input heating water temperature	[°C]	27.46	44.91
Air temperature – dry bulb temperature	[°C]	12.02	-14.93
Air temperature – wet bulb temperature	[°C]	11.01	-15.79
Relative humidity	[%]	88.87	63.15
Barometric pressure	[kPa]	98.790	98.740
Ambient temperature	[°C]	12.02	-14.93
Secondary circuit pressure difference	[kPa]	-6.160	-22.546
Efficiency of the secondary liquid pump	[-]	0.132	0.185
Volume flow rate of heating water	[m ³ ·h ⁻¹]	0.9179	0.9142
Density of heating water	[kg·m ⁻³]	993.2	988.5
Specific heat capacity of heating water	[kJ·kg ⁻¹ ·K ⁻¹]	4.180	4.180
Voltage	[V]	399.54	399.82
Total current	[A]	11.45	12.44
Overall power input	[kW]	1.928	2.214
Capacity correction of sec. liquid pump	[W]	-10.293	-25.287
Power input correction of sec. liquid pump	[W]	-11.86	-31.01
Heating capacity – heating water	[kW]	10.450	4.289
Corrected heating capacity – heating water	[kW]	10.461	4.314
Uncertainty of corrected heating capacity	[kW]	± 0.097	± 0.090
Effective electric power input	[kW]	1.939	2.245
COP	[-]	5.394	1.921
Uncertainty of COP	[-]	± 0.050	± 0.040
Control settings	[-]	–	–
Circulation pump settings – heating water	[-]	--	–

Data for SCOP calculation

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season „A“ – average

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (Tj)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]	[%]	[kW]	[kW]	[-]	[-]	[-]	[-]	[kW]
A	-7	52.00	88.46	5.56	5.558	2.285	0.900	1.00	2.285	-
B	2	45.30	53.85	3.38	6.865	3.125	0.993	0.49	3.104	0.0147
C	7	42.34	34.62	2.17	8.854	4.189	0.993	0.25	4.101	0.0147
D	12	38.95	15.38	0.97	10.398	5.230	0.993	0.09	4.878	0.0147
TOL (E)	-10	55.00	100.00	6.28	5.127	2.003	0.900	1.23	2.003	-
Tbiv (F)	-7	52.00	88.46	5.56	5.558	2.285	0.900	1.00	2.285	-

Adaption of water temperature – according to ČSN EN 14825:2020, Annex F

- Medium temperature application (reference water temperature 55 °C)
- Reference season „A“– average
- Condition D
- Fixed water flow rate – secondary circuit

General formulas and derivation:

$$\begin{aligned} \dot{t}_{\text{outlet, average}} &= \dot{t}_{\text{inlet, capacity test}} + (\dot{t}_{\text{outlet, capacity test}} - \dot{t}_{\text{inlet, capacity test}}) \cdot \text{CR} && [^{\circ}\text{C}] \\ \dot{t}_{\text{outlet, average}} &= \dot{t}_{\text{inlet, capacity test}} + (\Delta t) \cdot \text{CR} && [^{\circ}\text{C}] \\ \dot{t}_{\text{outlet, average}} &= \dot{t}_{\text{outlet, capacity test}} - \Delta t + \Delta t \cdot \text{CR} && [^{\circ}\text{C}] \\ \dot{t}_{\text{outlet, capacity test}} &= \dot{t}_{\text{outlet, average}} + \Delta t - \Delta t \cdot \text{CR} && [^{\circ}\text{C}] \end{aligned}$$

For fixed flow:

$$\Delta t = \text{Declared capacity} / \text{Declared capacity}_{\text{standard rating conditions A7W55}} \cdot 8$$

$$\text{CR} \cdot \Delta t = \text{Part load} / \text{Declared capacity} \cdot \text{Declared capacity} / \text{Declared capacity}_{\text{standard rating conditions A7W55}} \cdot 8$$

$$\text{CR} \cdot \Delta t = \text{Part load} / \text{Declared capacity}_{\text{standard rating conditions A7W55}} \cdot 8$$

$$\dot{t}_{\text{outlet, capacity test, fixed flow}} = \dot{t}_{\text{outlet, average}} + \text{Declared capacity} / \text{Declared capacity}_{\text{standard rating conditions A7W55}} \cdot 8 - \text{Part load} / \text{Declared capacity}_{\text{standard rating conditions A7W55}} \cdot 8$$

$$\dot{t}_{\text{outlet, capacity test, fixed flow}} = \dot{t}_{\text{outlet, average}} + 8 / \text{Declared capacity}_{\text{standard rating conditions A7W55}} \cdot (\text{Declared capacity} - \text{Part load})$$

Measured data:

$\dot{t}_{\text{outlet, average}}$	30.00	[°C]
Declared capacity	10.398	[kW]
Declared capacity standard rating condition A7W55	8.428	[kW]
Part load	0.97	[kW]

Calculation of water temperature

$$\dot{t}_{\text{outlet, capacity test, fixed flow}} = 30 + 8 / 8.428 \cdot (10.398 - 0.97) = \mathbf{38.95} \quad [^{\circ}\text{C}]$$

Calculation SCOP, SCOP_{on}, SCOP_{net}


- Medium temperature application (reference water temperature 55 °C)
- Reference heating season „A“ – average

BIn	Outdoor temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistive heat elbu (Tj)	Annual resistive heat	COP _{bin} (Tj)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating	
j	Tj	hj		Ph(Tj)			elbu(Tj)	hj x elbu(Tj)	COP _{bin} (Tj)	hj x Ph(Tj)		hj x (Ph(Tj) - elbu(Tj))		
[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]	
TOL (E)	21	-10	1	100.00	6.28	5.13	5.13	1.16	1.16	2.00	6	4	5	3
	22	-9	25	96.15	6.04	5.27	5.27	0.77	19.27	2.10	151	82	132	83
	23	-8	23	92.31	5.80	5.41	5.41	0.39	8.87	2.19	133	66	125	57
A, Tblv (F)	24	-7	24	88.46	5.56	5.56	5.56	0.00	0.00	2.29	133	58	133	58
	25	-6	27	84.62	5.32	5.70	5.32	0.00	0.00	2.38	144	60	144	60
	26	-5	68	80.77	5.07	5.85	5.07	0.00	0.00	2.47	345	140	345	140
	27	-4	91	76.92	4.83	5.99	4.83	0.00	0.00	2.56	440	172	440	172
	28	-3	89	73.08	4.59	6.14	4.59	0.00	0.00	2.65	409	154	409	154
	29	-2	165	69.23	4.35	6.28	4.35	0.00	0.00	2.74	718	262	718	262
	30	-1	173	65.38	4.11	6.43	4.11	0.00	0.00	2.83	711	251	711	251
	31	0	240	61.54	3.87	6.57	3.87	0.00	0.00	2.92	928	318	928	318
	32	1	280	57.69	3.62	6.72	3.62	0.00	0.00	3.01	1015	337	1015	337
B	33	2	320	53.85	3.38	6.87	3.38	0.00	0.00	3.10	1083	349	1083	349
	34	3	357	50.00	3.14	7.26	3.14	0.00	0.00	3.30	1122	340	1122	340
	35	4	356	46.15	2.90	7.66	2.90	0.00	0.00	3.50	1032	296	1032	296
	36	5	303	42.31	2.66	8.06	2.66	0.00	0.00	3.70	805	218	805	218
	37	6	330	38.46	2.42	8.46	2.42	0.00	0.00	3.90	797	204	797	204
C	38	7	326	34.62	2.17	8.85	2.17	0.00	0.00	4.10	709	173	709	173
	39	8	348	30.77	1.93	9.16	1.93	0.00	0.00	4.26	673	158	673	158
	40	9	335	26.92	1.69	9.47	1.69	0.00	0.00	4.41	587	128	587	128
	41	10	315	23.08	1.45	9.78	1.45	0.00	0.00	4.57	457	100	457	100
	42	11	215	19.23	1.21	10.09	1.21	0.00	0.00	4.72	260	55	260	55
D	43	12	169	15.38	0.97	10.40	0.97	0.00	0.00	4.88	163	33	163	33
	44	13	151	11.54	0.72	10.71	0.72	0.00	0.00	5.03	109	22	109	22
	45	14	105	7.69	0.48	11.02	0.48	0.00	0.00	5.19	51	10	51	10
	46	15	74	3.85	0.24	11.32	0.24	0.00	0.00	5.34	18	3	18	3
	Σ		4910							Σ	12979	3992	12950	3963

SCOP _{on}	3.25	SCOP _{net}	3.27
		SCOP	3.25


Part load performance diagram

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season „A“ – average



Test objective:	Safety tests
Exact name of the test procedure:	T 037* - Tests of leakage, pressure resistance, thermal and technical parameters, combustion efficiency, safety functions
Test method:	ČSN EN 14511-4:2019
Sample tested:	Heat pump Airkompakt p0916
Measuring equipment used:	see Chapter III

1) Temperature operating range



Test point	Inlet air dry bulb temperature [°C]		Outlet heating water temperature [°C]		Water flow rate in condenser [m ³ /h]	Note
Heating mode						
1.	A	-25	W	20	Minimum	Minimum water flow rate: 0.9142 m³·h⁻¹ Maximum water flow rate: 1.5814 m³·h⁻¹
2.	A	-25	W	45	Minimum	
Cooling mode						
1.	A	19	W	7	Minimum	Minimum starting water flow rate: 0.9142 m³·h⁻¹ Maximum water flow rate: 1.5814 m³·h⁻¹
2.	A	43	W	25	Maximum	

Heat pump **Airkompakt p0916** is fully operational in the temperature operating range.

Starting and operating tests (heating mode)

Test according to Article 4.2.1.2 of ČSN EN 14511-4:2019

Operational requirements conditions for air-to-water units					
Test point	Inlet temperature at outdoor heat exchanger (°C)	Inlet temperature at indoor heat exchanger (°C)	Water flow rate at indoor heat exchanger	Voltage (V)	Test result
1 (starting)	Lower limit of use	Lower limit of use	minimum	Rated voltage	+
2 (operating)	Lower limit of use	Upper limit of use	minimum	Rated voltage	+

Evaluation: +... For a starting test, the unit shall start and operate during 15 min, for an operating test, the unit shall be able to operate during 1 h, without tripping of the motor overload protective devices.

-... The unit did not fulfill test requirements.

0... The requirement does not apply to the product concerned.

x... Test was not required.

Starting and operating tests (cooling mode)

Test according to Article 4.2.1.3 of ČSN EN 14511-4:2019

Operational requirements conditions for air-to-water units					
Test point	Inlet temperature at outdoor heat exchanger (°C)	Inlet temperature at indoor heat exchanger (°C)	Water flow rate at indoor heat exchanger	Voltage (V)	Test result
1 (starting)	Lower limit of use	Lower limit of use	minimum	Rated voltage	+
2 (starting)	Upper limit of use	Upper limit of use	maximum	Rated voltage	+

Evaluation: +... For a starting test, the unit shall start and operate during 15 min, without tripping of the motor overload protective devices.

-... The unit did not fulfill test requirements.

0... The requirement does not apply to the product concerned.

x... Test was not required.

2) Outside the operating range

Requirements for outside the operating range	Requirement specification	Test result	Note
If operating outside the temperature range can cause damage to the unit, it shall be provided with safety devices which ensure that the unit suffers no damage when the operating limits of use indicated by the manufacturer are exceeded and remains capable of operating when coming back within these limits. A safety device that does not automatically reset may trip provided that a warning device is fitted. The manufacturer shall indicate any safety devices provided and their operating conditions according to 7.2.3.	ČSN EN 14511-4:2019 Art. 4.3	x	-

Evaluation: +... The unit fulfills test requirements.

-... The unit did not fulfill test requirements.

0... The requirement does not apply to the product concerned.

x... Test was not required.

3) Freeze-up test in cooling mode
Air-to-air and water(brine)-to-air units

Required operating conditions	Test result	Note
Test according to Article 4.4 of ČSN EN 14511-4:2019	0	-

Evaluation:	+...	After the unit has operated for 6 hours or after the last freeze up cycle has been completed after these 6 h, the following requirements shall be fulfilled: - no ice shall have accumulated on the evaporator; - no ice shall drip from the unit; - no water shall drip or be blown off the unit into the room.
	-...	The unit did not fulfill test requirements.
	0...	The requirement does not apply to the product concerned.
	x...	Test was not required.

4) Shutting off the heat transfer medium flows

Required operating conditions	Test result	Note
Test for section a) Art. 4.5 ČSN EN 14511-4:2019 – heating	+	No flow error
Test for section a) Art. 4.5 ČSN EN 14511-4:2019 – cooling	+	Unit shut down instantly, no flow error
Test for section b) Art. 4.5 ČSN EN 14511-4:2019 – heating	+	Unit kept working with lower output
Test for section b) Art. 4.5 ČSN EN 14511-4:2019 – cooling	+	Unit turned off and on 3 times
Test for section c) Art. 4.5 ČSN EN 14511-4:2019	0	--

Evaluation:	+...	The unit shall remain capable of operating after restoration of the flow rates for 30 min once the compressor has restarted.
	-...	The unit did not fulfill test requirements.
	0...	The requirement does not apply to the product concerned.
	x...	Test was not required.

5) Complete power supply failure

Required operating conditions	Test result	Note
Test according to Article 4.6 of ČSN EN 14511-4:2019	+	--

Evaluation:	+...	The unit has to restart automatically within 30 min. When manufacturer states that the unit does not automatically restart, fault detection is necessary. The unit is checked for any damage sustained during the test and if any safety devices have operated during the test.
	-...	The unit did not fulfill test requirements.
	0...	The requirement does not apply to the product concerned.
	x...	Test was not required.

6) Condensate draining and enclosure sweat test

Air-to-air and water(brine)-to-air units

Required operating conditions	Test result	Note
Test according to Article 4.7 of ČSN EN 14511-4:2019	0	--

Evaluation:	+...	During the test of 4 hours no condensed water shall drip, run or blow off the unit except through the drain. For indoor units, drain holes shall be provided with suitable pipe connection, the minimum diameter of which shall be 12 mm.
	-...	The unit did not fulfill test requirements.
	0...	The requirement does not apply to the product concerned.
	x...	Test was not required.

Test objective:	Out of accredited tests – SCOP calculations
Exact name of the test procedure:	SCOP calculations – based on values provided by the customer
Test method:	ČSN EN 14511-3:2019, ČSN EN 14825:2020
Sample tested:	Heat pump Airkompakt p0916

Data for SCOP calculation

- Low temperature application (reference water temperature 35 °C)
- Reference heating season „W” – warmer

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (Tj)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]								
A	–	–	–	–	–	–	–	–	–	–
B	2	35.00	100.00	7.00	6.996	3.660	0.900	1.00	3.660	–
C	7	33.43	64.29	4.50	8.900	4.790	0.992	0.51	4.753	0.0147
D	12	30.69	28.57	2.00	10.500	5.700	0.992	0.19	5.513	0.0147
TOL (E)	2	35.00	100.00	7.00	6.996	3.660	0.900	1.00	3.660	–
Tbiv (F)	2	35.00	100.00	7.00	6.996	3.660	0.900	1.00	3.660	–

Calculation SCOP, SCOP_{on}, SCOP_{net}

- Low temperature application (reference water temperature 35 °C)
- Reference heating season „W” – warmer


Bin	Outdoor temp (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistive heat elbu (Tj)	Annual resistive heat	COPbin (Tj)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating	
j	Tj	hj		P _{N(Tj)}			elbu _(Tj)	h _j × elbu _(Tj)	COP bin (Tj)	h _j × P _{N(Tj)}		h _j × (P _{N(Tj)} - elbu _(Tj))		
[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]	
B, TOL (E), Tbiv (F)	33	2	3	100.00	7.00	7.00	7.00	0.00	0.00	3.66	21	6	21	6
	34	3	22	92.86	6.50	7.38	6.50	0.00	0.00	3.66	143	37	143	37
	35	4	63	85.71	6.00	7.76	6.00	0.00	0.00	4.10	378	92	378	92
	36	5	63	76.57	5.50	8.14	5.50	0.00	0.00	4.32	346	80	346	80
	37	6	175	71.43	5.00	8.52	5.00	0.00	0.00	4.53	875	193	875	193
C	38	7	162	64.29	4.50	8.90	4.50	0.00	0.00	4.75	729	153	729	153
	39	8	259	57.14	4.00	9.22	4.00	0.00	0.00	4.91	1035	211	1035	211
	40	9	360	50.00	3.50	9.54	3.50	0.00	0.00	5.06	1259	249	1259	249

	41	10	428	42.86	3.00	9.86	3.00	0.00	0.00	5.21	1283	246	1283	246
	42	11	430	35.71	2.50	10.18	2.50	0.00	0.00	5.36	1074	200	1074	200
D	43	12	503	28.57	2.00	10.50	2.00	0.00	0.00	5.51	1005	182	1005	182
	44	13	444	21.43	1.50	10.82	1.50	0.00	0.00	5.66	666	118	666	118
	45	14	384	14.29	1.00	11.14	1.00	0.00	0.00	5.82	384	66	384	66
	46	15	294	7.14	0.50	11.46	0.50	0.00	0.00	5.97	147	25	147	25
	Σ		3690							Σ	9345	1858	9345	1858

SCOPon	5.03	SCOPnet	5.03
		SCOP	5.00

Part load performance diagram

- Low temperature application (reference water temperature 35 °C)
- Reference heating season „W” – warmer



Data for SCOP calculation

- Low temperature application (reference water temperature 35 °C)
- Reference heating season „C“ – colder

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (Tj)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]								
A	-7	31.87	60.53	3.42	6.800	3.150	0.993	0.50	3.129	0.0147
B	2	29.66	36.84	2.08	6.900	4.050	0.991	0.30	3.971	0.0147
C	7	29.39	23.68	1.34	9.300	5.190	0.992	0.14	4.948	0.0147
D	12	29.51	10.53	0.59	10.580	5.840	0.992	0.06	5.139	0.0147
TOL (E)	-22	35.00	100.00	5.65	3.686	2.031	0.900	1.53	2.031	–
Tbiv (F)	-15	32.00	81.58	4.61	4.606	2.573	0.900	1.00	2.573	–
G	-15	32.00	81.58	4.61	4.606	2.573	0.900	1.00	2.573	–

Calculation SCOP, SCOP_{on}, SCOP_{net}

- Low temperature application (reference water temperature 35 °C)
- Reference heating season „C“ – colder


Bin	Outdoor temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistive heat elbu (Tj)	Annual resistive heat	COPbin (Tj)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating
j	Tj	hj		Ph(Tj)			elbu(Tj)	hj x elbu(Tj)	COP bin (Tj)	hj x P _{H(Tj)}		hj x (P _{H(Tj)} - elbu(Tj))	
[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]
TOL (E)	9	-22	1	100.00	5.65	3.69	3.69	1.96	1.96	2.03	6	4	4
	10	-21	6	97.37	5.50	3.82	3.82	1.68	10.08	2.11	33	21	23
	11	-20	13	94.74	5.35	3.95	3.95	1.40	18.20	2.19	70	42	51
	12	-19	17	92.11	5.20	4.08	4.08	1.12	19.04	2.26	88	50	69
	13	-18	19	89.47	5.05	4.21	4.21	0.84	15.96	2.34	96	50	80
	14	-17	26	86.64	4.80	4.34	4.34	0.56	14.56	2.42	127	61	113
	15	-16	39	84.21	4.75	4.47	4.47	0.28	10.92	2.50	185	81	175
G, Tbiv (F)	16	-15	41	81.58	4.61	4.61	0.00	0.00	2.57	189	73	189	73
	17	-14	35	78.95	4.46	4.88	4.46	0.00	0.00	2.64	156	59	156
	18	-13	52	76.32	4.31	5.15	4.31	0.00	0.00	2.71	224	83	224
	19	-12	37	73.68	4.16	5.43	4.16	0.00	0.00	2.78	154	55	154
	20	-11	41	71.05	4.01	5.70	4.01	0.00	0.00	2.85	184	58	184

	21	-10	43	66.42	3.86	5.98	3.86	0.00	0.00	2.92	166	57	166	57
	22	-9	54	65.79	3.71	6.25	3.71	0.00	0.00	2.99	201	67	201	67
	23	-8	90	63.16	3.57	6.53	3.57	0.00	0.00	3.06	321	105	321	105
A	24	-7	125	60.53	3.42	6.80	3.42	0.00	0.00	3.13	427	137	427	137
	25	-6	169	57.89	3.27	6.81	3.27	0.00	0.00	3.22	552	171	552	171
	26	-5	195	55.26	3.12	6.82	3.12	0.00	0.00	3.32	608	183	608	183
	27	-4	278	52.83	2.97	6.83	2.97	0.00	0.00	3.41	826	242	826	242
	28	-3	306	50.00	2.82	6.84	2.82	0.00	0.00	3.50	864	247	864	247
	29	-2	454	47.37	2.67	6.86	2.67	0.00	0.00	3.60	1214	338	1214	338
	30	-1	385	44.74	2.53	6.87	2.53	0.00	0.00	3.69	972	264	972	264
	31	0	490	42.11	2.38	6.88	2.38	0.00	0.00	3.78	1165	308	1165	308
	32	1	533	39.47	2.23	6.89	2.23	0.00	0.00	3.88	1188	306	1188	306
B	33	2	380	36.84	2.08	6.90	2.08	0.00	0.00	3.97	790	199	790	199
	34	3	228	34.21	1.93	7.36	1.93	0.00	0.00	4.17	440	106	440	106
	35	4	261	31.58	1.78	7.86	1.78	0.00	0.00	4.36	465	107	465	107
	36	5	279	28.95	1.63	8.34	1.63	0.00	0.00	4.56	456	100	456	100
	37	6	229	26.32	1.49	8.82	1.49	0.00	0.00	4.75	340	72	340	72
C	38	7	269	23.68	1.34	9.30	1.34	0.00	0.00	4.95	360	73	360	73
	39	8	233	21.05	1.19	9.56	1.19	0.00	0.00	4.99	277	56	277	56
	40	9	230	18.42	1.04	9.81	1.04	0.00	0.00	5.02	239	48	239	48
	41	10	243	15.79	0.89	10.07	0.89	0.00	0.00	5.06	217	43	217	43
	42	11	191	13.16	0.74	10.32	0.74	0.00	0.00	5.10	142	28	142	28
D	43	12	146	10.53	0.59	10.58	0.59	0.00	0.00	5.14	87	17	87	17
	44	13	150	7.89	0.45	10.84	0.45	0.00	0.00	5.18	67	13	67	13
	45	14	97	5.26	0.30	11.09	0.30	0.00	0.00	5.22	29	6	29	6
	46	15	61	2.63	0.15	11.35	0.15	0.00	0.00	5.25	9	2	9	2
	Σ		6446							Σ	13916	3928	13825	3837

SCOPon	3.54	SCOPnet	3.60
		SCOP	3.54

Part load performance diagram

- Low temperature application (reference water temperature 35 °C)
- Reference heating season „C“ – colder



Data for SCOP calculation

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season „W” – warmer

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (Tj)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]								
A	–	–	–	–	–	–	–	–	–	–
B	2	55.00	100.00	6.52	6.521	2.500	0.900	1.00	2.500	–
C	7	49.90	64.29	4.19	8.300	3.500	0.994	0.51	3.479	0.0147
D	12	42.20	28.57	1.86	10.500	5.160	0.993	0.18	4.993	0.0147
TOL (E)	2	55.00	100.00	6.52	6.521	2.500	0.900	1.00	2.500	–
Tbiv (F)	2	55.00	100.00	6.52	6.521	2.500	0.900	1.00	2.500	–

 Calculation SCOP, SCOP_{on}, SCOP_{net}

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season „W” – warmer


	Bin	Outdoor temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistive heat elbu (Tj)	Annual resistive heat	COPbin (Tj)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating
	j	Tj	hj	Pn(Tj)	Pn(Tj)	elbu(Tj)	hj x elbu(Tj)	hj x elbu(Tj)	COP bin (Tj)	hj x Pn(Tj)	hj x Pn(Tj)	hj x (Pn(Tj) - elbu(Tj))	hj x (Pn(Tj) - elbu(Tj))	
	[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]
B, TOL (E), Tbiv (F)	33	2	3	100.00	6.52	6.52	6.52	0.00	0.00	2.50	20	8	20	8
	34	3	22	92.86	6.06	6.88	6.06	0.00	0.00	2.70	133	49	133	49
	35	4	63	85.71	5.59	7.23	5.59	0.00	0.00	2.89	352	122	352	122
	36	5	63	78.57	5.12	7.59	5.12	0.00	0.00	3.09	323	105	323	105
	37	6	175	71.43	4.66	7.94	4.66	0.00	0.00	3.28	815	248	815	248
	C	38	7	162	64.29	4.19	8.30	4.19	0.00	0.00	3.48	679	195	679
	39	8	259	57.14	3.73	8.74	3.73	0.00	0.00	3.78	965	255	965	255
	40	9	360	50.00	3.26	9.18	3.26	0.00	0.00	4.08	1174	287	1174	287
	41	10	428	42.86	2.79	9.62	2.79	0.00	0.00	4.39	1196	273	1196	273
	42	11	430	35.71	2.33	10.06	2.33	0.00	0.00	4.69	1001	214	1001	214
D	43	12	503	28.57	1.86	10.50	1.86	0.00	0.00	4.99	937	188	937	188
	44	13	444	21.43	1.40	10.94	1.40	0.00	0.00	5.30	620	117	620	117
	45	14	384	14.29	0.93	11.38	0.93	0.00	0.00	5.60	358	64	358	64

	46	15	294	7.14	0.47	11.82	0.47	0.00	0.00	5.90	137	23	137	23
	Σ		3590							Σ	8711	2148	8711	2148

SCOPon	4.06	SCOPnet	4.06
SCOP		4.03	

Part load performance diagram

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season „W” – warmer



Data for SCOP calculation

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season „C“ – colder

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COP _d at declared capacity	C _{dh} degradation coefficient	CR	COP _{bin} (T _j)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]								
A	-7	47.23	60.53	3.20	6.600	2.400	0.995	0.48	2.386	0.0147
B	2	41.70	36.84	1.95	6.900	3.300	0.993	0.28	3.242	0.0147
C	7	39.07	23.68	1.25	8.700	4.610	0.992	0.14	4.406	0.0147
D	12	37.40	10.53	0.56	10.461	5.394	0.992	0.05	4.753	0.0147
TOL (E)	-19	52.43	92.11	4.87	3.600	1.670	0.900	1.35	1.670	–
T_{biv} (F)	-15	49.00	81.58	4.31	4.314	1.921	0.900	1.00	1.921	–
G	-15	49.00	81.58	4.31	4.314	1.921	0.900	1.00	1.921	–

Calculation SCOP, SCOP_{on}, SCOP_{net}

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season „C“ – colder


Bin	Outdoor temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistive heat elbu (T _j)	Annual resistive heat	COP _{bin} (T _j)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating
j	T _j	h _j	P _{h(T_j)}	P _{h(T_j)}	[kW]	[kW]	elbu _(T_j)	h _j × elbu _(T_j)	COP _{bin} (T _j)	h _j × P _{h(T_j)}	[kWh]	h _j × (P _{h(T_j)} - elbu _(T_j))	[kWh]
[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]
9	-22	1	100.00	5.29	0.00	0.00	5.29	5.29	1.00	5	5	0	0
10	-21	6	97.37	5.15	0.00	0.00	5.15	30.89	1.00	31	31	0	0
11	-20	13	94.74	5.01	0.00	0.00	5.01	65.13	1.00	65	65	0	0
12	-19	17	92.11	4.87	3.60	3.60	1.27	21.60	1.67	83	58	61	37
13	-18	19	89.47	4.73	3.78	3.78	0.95	18.11	1.73	90	60	72	41
14	-17	26	86.84	4.59	3.96	3.96	0.64	16.52	1.80	119	74	103	57
15	-16	39	84.21	4.45	4.14	4.14	0.32	12.39	1.86	174	99	161	87
G	16	-15	41	81.58	4.31	4.31	0.00	0.00	1.92	177	92	177	92
17	-14	35	78.95	4.17	4.60	4.17	0.00	0.00	1.98	146	74	146	74
18	-13	52	76.32	4.04	4.89	4.04	0.00	0.00	2.04	210	103	210	103
19	-12	37	73.68	3.90	5.17	3.90	0.00	0.00	2.10	144	69	144	69
20	-11	41	71.05	3.76	5.46	3.76	0.00	0.00	2.15	154	72	154	72
21	-10	43	68.42	3.62	5.74	3.62	0.00	0.00	2.21	156	70	156	70

	22	-9	54	65.79	3.48	6.03	3.48	0.00	0.00	2.27	188	83	188	83
	23	-8	90	63.16	3.34	6.31	3.34	0.00	0.00	2.33	301	129	301	129
A	24	-7	125	60.53	3.20	6.60	3.20	0.00	0.00	2.39	400	168	400	168
	25	-6	169	57.89	3.06	6.63	3.06	0.00	0.00	2.48	517	209	517	209
	26	-5	195	55.26	2.92	6.67	2.92	0.00	0.00	2.58	570	221	570	221
	27	-4	278	52.63	2.78	6.70	2.78	0.00	0.00	2.67	774	290	774	290
	28	-3	306	50.00	2.64	6.73	2.64	0.00	0.00	2.77	809	292	809	292
	29	-2	454	47.37	2.50	6.77	2.50	0.00	0.00	2.86	1137	397	1137	397
	30	-1	985	44.74	2.37	6.80	2.37	0.00	0.00	2.96	911	308	911	308
	31	0	490	42.11	2.23	6.83	2.23	0.00	0.00	3.05	1091	357	1091	357
	32	1	533	39.47	2.09	6.87	2.09	0.00	0.00	3.15	1113	354	1113	354
B	33	2	380	36.84	1.95	6.90	1.95	0.00	0.00	3.24	740	228	740	228
	34	3	228	34.21	1.81	7.26	1.81	0.00	0.00	3.47	412	119	412	119
	35	4	261	31.58	1.67	7.62	1.67	0.00	0.00	3.71	436	118	436	118
	36	5	279	28.95	1.53	7.98	1.53	0.00	0.00	3.94	427	108	427	108
	37	6	229	26.32	1.39	8.34	1.39	0.00	0.00	4.17	319	76	319	76
C	38	7	269	23.68	1.25	8.70	1.25	0.00	0.00	4.41	337	76	337	76
	39	8	233	21.05	1.11	9.05	1.11	0.00	0.00	4.48	259	58	259	58
	40	9	230	18.42	0.97	9.40	0.97	0.00	0.00	4.54	224	49	224	49
	41	10	243	15.79	0.83	9.76	0.83	0.00	0.00	4.61	203	44	203	44
	42	11	191	13.16	0.70	10.11	0.70	0.00	0.00	4.68	133	28	133	28
D	43	12	146	10.53	0.56	10.46	0.56	0.00	0.00	4.75	81	17	81	17
	44	13	150	7.89	0.42	10.81	0.42	0.00	0.00	4.82	63	13	63	13
	45	14	97	5.26	0.28	11.17	0.28	0.00	0.00	4.89	27	6	27	6
	46	15	61	2.63	0.14	11.52	0.14	0.00	0.00	4.96	8	2	8	2
	Σ		6446							Σ	13034	4622	12864	4452

SCOPon	2.82	SCOPnet	2.89
		SCOP	2.82

Part load performance diagram

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season „C“ – colder



Tested by: Ing. Michal Faltýnek

Date: 2022-09-16

Signed: 

Reviewed and approved by: Ing. Mario Jankola



Date: 2022-09-16

Signed: 



V. Graphs

1. Rating conditions

A7/W35





A7/W55





2. Seasonal performance tests and SCOP calculation – Low temperature application



A2/W32.06





A7/W30.9





A12/W29.33





A-10/W35





A-7/W34





A2/W35



A-22/W35





A-15/W32





3. Seasonal performance tests and SCOP calculation – Medium temperature application



A2/W45.3





A7/W42.34





A12/W38.95





A-10/W55





A-7/W52





A2/W55



A12/W37.4



A-15/W49



VI. A list of referenced documents

- Order of 2022-06-29 (Order reg. no. B-76791, received on 2022-06-29)
- Contract B-76791/39
- ČSN EN 14511-2:2019 - Air conditioners, liquid chilling packages and heat pumps for space heating and cooling and process chillers, with electrically driven compressors - Part 2: Test conditions
- ČSN EN 14511-3:2019 - Air conditioners, liquid chilling packages and heat pumps for space heating and cooling a process chillers with electrically driven compressors - Part 3: Test methods
- ČSN EN 14511-4:2019 - Air conditioners, liquid chilling packages and heat pumps for space heating and cooling and process chillers, with electrically driven compressors - Part 4: Requirements
- ČSN EN 14825:2020 - Air conditioners, liquid chilling packages and heat pumps, with electrically driven compressors, for space heating and cooling - Testing and rating at part load conditions and calculation of seasonal performance
- EHPA Testing regulation – Testing of Air/Water Heat Pumps – Additional requirements for granting the international quality label for heat pumps – Version 2.4a

Test Report compiled by: Ing. Michal Faltýnek



Test Report approved by:  Milan Holomek
Head of Heat and Environment-Friendly Equipment Test Station

– End of Test Report –



Strojirenský zkušební ústav, s.p., Brno, Česká republika
Engineering Test Institute, Public Enterprise, Brno, Czech Republic

TEST CERTIFICATE

Number **O-B-01496-22 rev.1**

Customer **KOŁTON SPÓŁKA KOMANDYTOWA**
ul. Sosnowa 2
34-480 Jablonka
POLSKA

Product **Air/water heat pump – monobloc**

Type designation / Trade mark **Airkompakt p0916**

Test methods **ČSN EN 14511-3:2019, ČSN EN 14825:2020; ČSN EN 12102-1:2018, EHPA Testing regulation – Testing of Air/Water Heat Pumps, version 2.4a**

Basis of certificate **Test reports:
39-16511/T of 2022-09-16
39-16511/H of 2022-09-16
Technical documents of KOŁTON SPÓŁKA KOMANDYTOWA**

Reference heating season **„A“ = average
(Reference design temperature $T_{designh} = -10\text{ °C}$)**

Results:

LOW TEMPERATURE
(Reference water temperature 35 °C)

MEDIUM TEMPERATURE
(Reference water temperature 55 °C)

6.20	$P_{designh}$ [kW] ... Full load heating				6.28
4.00	SCOP [-] ... Seasonal coefficient of performance				3.25
Outdoor temperature T_j [°C]	Heating declared capacity P_{dh} [kW]	Coefficient of performance at the declared capacity COP_d [-]	Outdoor temperature T_j [°C]	Heating declared capacity P_{dh} [kW]	Coefficient of performance at the declared capacity COP_d [-]
$T_j = -7$	5.482	2.902	$T_j = -7$	5.558	2.285
$T_j = +2$	7.066	3.878	$T_j = +2$	6.865	3.125
$T_j = +7$	9.209	5.130	$T_j = +7$	8.854	4.189
$T_j = +12$	10.611	6.025	$T_j = +12$	10.398	5.230
$T_j = TOL = -10$	5.260	2.765	$T_j = TOL = -10$	5.127	2.003
$T_j = T_{bivalent} = -7$	5.482	2.902	$T_j = T_{bivalent} = -7$	5.558	2.285



LOW TEMPERATURE

(Reference water temperature 35 °C)

**MEDIUM TEMPERATURE**

(Reference water temperature 55 °C)

Power consumption in modes other than „active mode“:

14.8	Off mode	P _{OFF}	[W]	14.8
14.7	Thermostat off mode	P _{TO}	[W]	14.7
14.8	Standby mode	P _{SB}	[W]	14.8
0.0	Crankcase heater mode	P _{CK}	[W]	0.0

Annual electricity consumption for heating according to:

3197	ČSN EN 14825:2020	Q _{HE}	[kWh]	3995
------	-------------------	-----------------	-------	------

Seasonal Space heating energy efficiency

157.2	ČSN EN 14825:2020	η _s	[%]	127.0
-------	-------------------	----------------	-----	-------

Liquid flow rate in outdoor heating exchanger:

-	Source liquid	Min/Max	[m ³ /h]	-
---	---------------	---------	---------------------	---

Liquid flow rate in indoor heating exchanger:

0.9142/1.5814	Heating water	Min/Max	[m ³ /h]	0.9142/1.5814
---------------	---------------	---------	---------------------	---------------

Sound power level at condition A7W55* :**Airkompakt p0916**

LWA	62.9 ± 1.5	dB(A)
-----	------------	-------

Accuracy class 2 (Engineering)

(*) Comment to abbreviated marking:

„A“ air, „7“ inlet temperature (dry-bulb temperature) in °C, „W“ water, „35“ outlet temperature in °C.

(*) The technical data were declared by the manufacturer or calculated of data declared by the manufacturer and were not tested by the Testing Laboratory.

Specification of conditions:

Compressor speed control	Fixed	Heating water volume flow rate (indoor heat exchanger)	Fixed
Outlet water temperature (indoor heat exchanger)	Variable	Source liquid volume flow rate (outdoor heat exchanger)	-
Function	Reversible		

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2022-09-30

Milan Holomek

Head of Heat and Environment-Friendly Equipment Test Station

- END OF TEST CERTIFICATE -





Strojirenský zkušební ústav, s.p., Brno, Česká republika
Engineering Test Institute, Public Enterprise, Brno, Czech Republic

TEST CERTIFICATE

Number **O-B-01497-22 rev.1**

Customer KOŁTON SPÓŁKA KOMANDYTOWA
ul. Sosnowa 2
34-480 Jablonka
POLSKA

Product Air/water heat pump – monobloc

Type designation / Trade mark **Airkompakt p0916**

Test methods ČSN EN 14511-3:2019, ČSN EN 14825:2020; ČSN EN 12102-1:2018, EHPA Testing regulation – Testing of Air/Water Heat Pumps, version 2.4a

Basis of certificate Test reports:
39-16511/T of 2022-09-16
39-16511/H of 2022-09-16
Technical documents of KOŁTON SPÓŁKA KOMANDYTOWA

Reference heating season „W” = warmer
(Reference design temperature $T_{designh} = +2\text{ °C}$)

Results:

LOW TEMPERATURE (Reference water temperature 35 °C)

MEDIUM TEMPERATURE (Reference water temperature 55 °C)

7.00		$P_{designh}$ [kW] ... Full load heating		6.52	
5.00 ^(a)		SCOP [-] ... Seasonal coefficient of performance		4.03 ^(a)	
Outdoor temperature T_j [°C]	Heating declared capacity P_{dh} [kW]	Coefficient of performance at the declared capacity COP_d [-]	Outdoor temperature T_j [°C]	Heating declared capacity P_{dh} [kW]	Coefficient of performance at the declared capacity COP_d [-]
$T_j = -7$	—	—	$T_j = -7$	—	—
$T_j = +2$	6.996	3.660	$T_j = +2$	6.521	2.500
$T_j = +7$ ^(a)	8.900	4.790	$T_j = +7$ ^(a)	8.300	3.500
$T_j = +12$ ^(a)	10.500	5.700	$T_j = +12$ ^(a)	10.500	5.160
$T_j = TOL = +2$	6.996	3.660	$T_j = TOL = +2$	6.521	2.500
$T_j = T_{bivalent} = +2$	6.996	3.660	$T_j = T_{bivalent} = +2$	6.521	2.500



LOW TEMPERATURE

(Reference water temperature 35 °C)

**MEDIUM TEMPERATURE**

(Reference water temperature 55 °C)

Power consumption in modes other than „active mode“:

14.8	Off mode	P _{OFF}	[W]	14.8
14.7	Thermostat off mode	P _{TO}	[W]	14.7
14.8	Standby mode	P _{SB}	[W]	14.8
0.0	Crankcase heater mode	P _{CK}	[W]	0.0

Annual electricity consumption for heating according to:

1870 ^(a)	ČSN EN 14825:2020	Q _{HE}	[kWh]	2159 ^(a)
---------------------	-------------------	-----------------	-------	---------------------

Seasonal Space heating energy efficiency

196.9 ^(a)	ČSN EN 14825:2020	η _s	[%]	158.4 ^(a)
----------------------	-------------------	----------------	-----	----------------------

Liquid flow rate in outdoor heating exchanger:

–	Source liquid	Min/Max	[m ³ /h]	–
---	---------------	---------	---------------------	---

Liquid flow rate in indoor heating exchanger:

0.9142/1.5814	Heating water	Min/Max	[m ³ /h]	0.9142/1.5814
---------------	---------------	---------	---------------------	---------------

Sound power level at condition A7W55***Airkompakt p0916**

L _{WA}	62.9 ± 1.5	dB(A)
-----------------	------------	-------

Accuracy class 2 (Engineering)

(*) Comment to abbreviated marking:

„A“ air, „7“ inlet temperature (dry-bulb temperature) in °C, „W“ water, „35“ outlet temperature in °C.

(^a) The technical data were declared by the manufacturer or calculated of data declared by the manufacturer and were not tested by the Testing Laboratory.

Specification of conditions:

Compressor speed control	Fixed	Heating water volume flow rate (indoor heat exchanger)	Fixed
Outlet water temperature (indoor heat exchanger)	Variable	Source liquid volume flow rate (outdoor heat exchanger)	–
Function	Reversible		

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2022-09-30



Milan Holomek

Head of Heat and Environment-Friendly Equipment Test Station

– END OF TEST CERTIFICATE –





Strojirenský zkušební ústav, s.p., Brno, Česká republika
Engineering Test Institute, Public Enterprise, Brno, Czech Republic

TEST CERTIFICATE

Number **O-B-01498-22 rev.1**

Customer KOŁTON SPÓŁKA KOMANDYTOWA
ul. Sosnowa 2
34-480 Jablonka
POLSKA

Product Air/water heat pump – monobloc

Type designation / Trade mark **Airkompakt p0916**

Test methods ČSN EN 14511-3:2019, ČSN EN 14825:2020; ČSN EN 12102-1:2018, EHPA Testing regulation – Testing of Air/Water Heat Pumps, version 2.4a

Basis of certificate Test reports:
39-16511/T of 2022-09-16
39-16511/H of 2022-09-16
Technical documents of KOŁTON SPÓŁKA KOMANDYTOWA

Reference heating season „C” = colder
(Reference design temperature $T_{designh} = -22\text{ °C}$)

Results:

LOW TEMPERATURE
(Reference water temperature 35 °C)

MEDIUM TEMPERATURE
(Reference water temperature 55 °C)

5.65			5.29		
$P_{designh}$ [kW] ... Full load heating			$P_{designh}$ [kW] ... Full load heating		
3.54 ^(a)			2.82 ^(a)		
SCOP [-] ... Seasonal coefficient of performance			SCOP [-] ... Seasonal coefficient of performance		
Outdoor temperature	Heating declared capacity	Coefficient of performance at the declared capacity	Outdoor temperature	Heating declared capacity	Coefficient of performance at the declared capacity
T_j [°C]	P_{dh} [kW]	COP_d [-]	T_j [°C]	P_{dh} [kW]	COP_d [-]
$T_j = -7$ ^(a)	6.800	3.150	$T_j = -7$ ^(a)	6.600	2.400
$T_j = +2$ ^(a)	6.900	4.050	$T_j = +2$ ^(a)	6.900	3.300
$T_j = +7$ ^(a)	9.300	5.190	$T_j = +7$ ^(a)	8.700	4.610
$T_j = +12$ ^(a)	10.580	5.840	$T_j = +12$	10.461	5.394
$T_j = TOL = -22$	3.686	2.031	$T_j = TOL = -19$ ^(a)	3.600	1.670
$T_j = T_{bivalent} = -15$	4.606	2.573	$T_j = T_{bivalent} = -15$	4.314	1.921
$T_j = -15$	4.606	2.573	$T_j = -15$	4.314	1.921



LOW TEMPERATURE
(Reference water temperature 35 °C)



MEDIUM TEMPERATURE
(Reference water temperature 55 °C)

Power consumption in modes other than „active mode“:

14.8	Off mode	P _{OFF}	[W]	14.8
14.7	Thermostat off mode	P _{TO}	[W]	14.7
14.8	Standby mode	P _{SB}	[W]	14.8
0.0	Crankcase heater mode	P _{CK}	[W]	0.0

Annual electricity consumption for heating according to:

3930 ^(a)	ČSN EN 14825:2020	Q _{HE}	[kWh]	4624 ^(a)
---------------------	-------------------	-----------------	-------	---------------------

Seasonal Space heating energy efficiency

138.7 ^(a)	ČSN EN 14825:2020	η _s	[%]	109.8 ^(a)
----------------------	-------------------	----------------	-----	----------------------

Liquid flow rate in outdoor heating exchanger:

-	Source liquid	Min/Max	[m ³ /h]	-
---	---------------	---------	---------------------	---

Liquid flow rate in indoor heating exchanger:

0.9142/1.5814	Heating water	Min/Max	[m ³ /h]	0.9142/1.5814
---------------	---------------	---------	---------------------	---------------

Sound power level at condition A7W55*

Airkompakt p0916

L _{WA}	62.9 ± 1.5	dB(A)
-----------------	------------	-------

Accuracy class 2 (Engineering)

(*) Comment to abbreviated marking:

„A“ air, „7“ inlet temperature (dry-bulb temperature) in °C, „W“ water, „35“ outlet temperature in °C.

^(a) The technical data were declared by the manufacturer or calculated of data declared by the manufacturer and were not tested by the Testing Laboratory.

Specification of conditions:

Compressor speed control	Fixed	Heating water volume flow rate (indoor heat exchanger)	Fixed
Outlet water temperature (indoor heat exchanger)	Variable	Source liquid volume flow rate (outdoor heat exchanger)	-
Function	Reversible		

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2022-09-30

Milan Holomek

Head of Heat and Environment-Friendly Equipment Test Station

- END OF TEST CERTIFICATE -





Strojirenský zkušební ústav, s.p., Brno, Česká republika
Engineering Test Institute, Public Enterprise, Brno, Czech Republic

TEST CERTIFICATE

Number **O-B-01499-22 rev.1**

Customer **KOŁTON SPÓŁKA KOMANDYTOWA**
ul. Sosnowa 2
34-480 Jabłonka
POLSKA

Product **Air/water heat pump – monobloc**

Type designation / Trade mark **Airkompakt p0916**

Test methods **ČSN EN 14511-2:2019, ČSN EN 14511-3:2019,
ČSN EN 14511-4:2019, ČSN EN 12102-1:2018, EHPA Testing
regulation – Testing of Air/Water Heat Pumps, version 2.4a**

Basis of certificate **Test reports:
39-16511/T of 2022-09-16
39-16511/H of 2022-09-16
Technical documents of KOŁTON SPÓŁKA KOMANDYTOWA**

Temperature application **LOW TEMPERATURE,**
(Reference water temperature 35 °C)
MEDIUM TEMPERATURE
(Reference water temperature 55 °C)

Results:

Temperature conditions*	A7/W35	A7/W55
Corrected heat capacity [kW]	9.062	8.428
Effective electric power input [kW]	1.950	2.678
Coefficient of performance [-]	4.647	3.148
Compressor settings [-]	—	—

(*) Comment to abbreviated marking: e.g. A7/W35

A (air), 7 (input air – dry bulb temperature in °C) / W (water), 35 (output heating (cooling) water temperature in °C).



O-B-01499-22, page 1 (2)

Strojirenský zkušební ústav, s.p., Hudcova 424/56b, 621 00 Brno, Česká republika
Engineering Test Institute, public enterprise, Hudcova 424/56b, 621 00 Brno, Czech Republic

www.szutest.cz





Sound power level at temperature condition A7/W55^{*}:

Air/Water Heat Pump – monobloc

Airkompakt p0916

Sound power level

L_{WA} 62.9 ± 1.5 dB(A)


Accuracy class

Engineering (grade 2)

(*) Comment to abbreviated marking: e.g. A7/W55

A (air), 7 (input air – dry bulb temperature in °C) / W (water), 55 (output heating (cooling) water temperature in °C).

Temperature operating range:



Liquid flow rate in:

outdoor heating exchanger

Minimum – m³/h

Maximum – m³/h

indoor heating exchanger

Minimum 0.9142 m³/h

Maximum 1.5814 m³/h

Complies with ČSN EN 14511-4:2019, articles:

4.2.1.2, 4.2.1.3, 4.5

Specification of conditions:

Compressor speed control	Fixed	Heating water volume flow rate (indoor heat exchanger)	Fixed
Outlet water temperature (indoor heat exchanger)	Variable	Source liquid volume flow rate (outdoor heat exchanger)	–
Function	Reversible		

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2022-09-30

Milan Holomek

Head of Heat and Environment-Friendly Equipment Test Station

– END OF TEST CERTIFICATE –





Strojirenský zkušební ústav, s.p., Brno, Česká republika
Engineering Test Institute, Public Enterprise, Brno, Czech Republic

TEST CERTIFICATE

Number **O-B-01500-22 rev.1**

Customer **KOŁTON SPÓŁKA KOMANDYTOWA**
ul. Sosnowa 2
34-480 Jablonka
POLSKA

Product **Air/water heat pump – monobloc**

Type designation / Trade mark **Airkompakt p0916**
Airkompakt p1118
Airkompakt p1522
Airkompakt p1926

Test methods **ČSN EN 14511-3:2019, ČSN EN 14825:2020; EHPA Testing regulation – Testing of Air/Water Heat Pumps, version 2.4a**

Basis of certificate **Test reports:**
39-16511/T of 2022-09-16
39-16511/H of 2022-09-16
Technical documents of KOŁTON SPÓŁKA KOMANDYTOWA

Temperature application **LOW TEMPERATURE**
(Reference water temperature 35 °C)

Reference heating season **„A“ = average / „W“ = warmer / „C“ = colder**
(Reference design conditions for heating $T_{design} = -10\text{ °C} / +2\text{ °C} / -22\text{ °C}$)

Specification of conditions:

Compressor speed control	Fixed	Heating water volume flow rate (indoor heat exchanger)	Fixed
Outlet water temperature (indoor heat exchanger)	Variable	Source liquid volume flow rate (outdoor heat exchanger)	–
Function	Reversible		



O-B-01500-22, page 1 (2)

Strojirenský zkušební ústav, s.p., Hudcova 424/56b, 621 00 Brno, Česká republika
Engineering Test Institute, public enterprise, Hudcova 424/56b, 621 00 Brno, Czech Republic

www.szutest.cz



**Results:****Low temperature application**

(Reference water temperature 35 °C)

Model names		Airkompakt p0916 (Tested)	Airkompakt p1118 (Not tested)	Airkompakt p1522 (Not tested)	Airkompakt p1926 (Not tested)	
Full load heating	P_{designh} [kW]	A	6.20	8.59	12.10	14.58
		W	7.00	9.40	13.50	14.40
		C	5.65	7.97	9.68	12.38
Bivalent temperature	T_{bivalent} [°C]	A	-7	-7	-7	-7
		W	2	2	2	2
		C	-15	-15	-15	-15
Seasonal coefficient of performance	SCOP [-]	A	4.00	4.05	4.08	4.08
		W	5.00 (Not tested)	5.16	4.96	5.13
		C	3.54 (Not tested)	3.61	3.55	3.53
Seasonal Space heating energy efficiency	η_s [%]	A	157.2	159.1	160.1	160.2
		W	196.9 (Not tested)	203.3	195.3	202.3
		C	138.7 (Not tested)	141.2	139.1	138.3

(Tested) This test sample was tested at the Testing Laboratory.

(Not tested) The technical data were declared by the Manufacturer according to the model range specifications and were not tested by the Testing Laboratory.

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2022-09-30


Milan Holomek

Head of Heat and Environment-Friendly Equipment Test Station

- END OF TEST CERTIFICATE -





Strojirenský zkušební ústav, s.p., Brno, Česká republika
Engineering Test Institute, Public Enterprise, Brno, Czech Republic

TEST CERTIFICATE

Number **O-B-01501-22 rev.1**

Customer **KOLTON SPÓŁKA KOMANDYTOWA**
ul. Sosnowa 2
34-480 Jabłonka
POLSKA

Product **Air/water heat pump – monobloc**

Type designation / Trade mark
Airkompakt p0916
Airkompakt p1118
Airkompakt p1522
Airkompakt p1926

Test methods **ČSN EN 14511-3:2019, ČSN EN 14825:2020; EHPA Testing regulation – Testing of Air/Water Heat Pumps, version 2.4a**

Basis of certificate
Test reports:
39-16511/T of 2022-09-16
39-16511/H of 2022-09-16
Technical documents of **KOLTON SPÓŁKA KOMANDYTOWA**

Temperature application
MEDIUM TEMPERATURE
(Reference water temperature 55 °C)

Reference heating season
„A“ = average / „W“ = warmer / „C“ = colder
(Reference design conditions for heating $T_{design} = -10\text{ °C} / +2\text{ °C} / -22\text{ °C}$)

Specification of conditions:

Compressor speed control	Fixed	Heating water volume flow rate (indoor heat exchanger)	Fixed
Outlet water temperature (indoor heat exchanger)	Variable	Source liquid volume flow rate (outdoor heat exchanger)	-
Function	Reversible		



O-B-01501-22, page 1 (2)

Strojirenský zkušební ústav, s.p., Hudcova 424/56b, 621 00 Brno, Česká republika
Engineering Test Institute, public enterprise, Hudcova 424/56b, 621 00 Brno, Czech Republic

www.szutest.cz



**Results:****Medium temperature application**

(Reference water temperature 55 °C)

Model names		Airkompakt p0916 (Tested)	Airkompakt p1118 (Not tested)	Airkompakt p1522 (Not tested)	Airkompakt p1926 (Not tested)	
Full load heating	P_{designh} [kW]	A	6.28	8.59	11.42	13.90
		W	6.52	8.90	11.60	14.40
		C	5.29	7.72	9.68	12.38
Bivalent temperature	T_{bivalent} [°C]	A	-7	-7	-7	-7
		W	2	2	2	2
		C	-15	-15	-15	-15
Seasonal coefficient of performance	SCOP [-]	A	3.25	3.39	3.20	3.35
		W	4.03 (Not tested)	4.07	4.13	4.10
		C	2.82 (Not tested)	2.97	2.93	2.94
Seasonal Space heating energy efficiency	η_s [%]	A	127.0	132.8	125.0	131.2
		W	158.4 (Not tested)	159.8	162.4	161.1
		C	109.8 (Not tested)	116.0	114.2	114.5

*(Tested) This test sample was tested at the Testing Laboratory.**(Not tested) The technical data were declared by the Manufacturer according to the model range specifications and were not tested by the Testing Laboratory.*

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2022-09-30

Milan Holomek

Head of Heat and Environment-Friendly Equipment Test Station

- END OF TEST CERTIFICATE -





Strojirenský zkušební ústav, s.p., Brno, Česká republika
Engineering Test Institute, Public Enterprise, Brno, Czech Republic

TEST CERTIFICATE

Number **O-B-01502-22 rev.1**

Customer **KOLTON SPÓŁKA KOMANDYTOWA**
ul. Sosnowa 2
34-480 Jablonka
POLSKA

Product **Air/water heat pump – monobloc**

Type designation / Trade mark
Airkompakt p0916
Airkompakt p1118
Airkompakt p1522
Airkompakt p1926

Test methods **ČSN EN 14511-2:2019, ČSN EN 14511-3:2019,
ČSN EN 14511-4:2019, ČSN EN 12102-1:2018, EHPA Testing
regulation – Testing of Air/Water Heat Pumps, version 2.4a**

Basis of certificate
Test reports:
39-16511/T of 2022-09-16
39-16511/H of 2022-09-16
Technical documents of KOLTON SPÓŁKA KOMANDYTOWA

Temperature application
LOW TEMPERATURE,
(Reference water temperature 35 °C)

MEDIUM TEMPERATURE
(Reference water temperature 55 °C)

Specification of conditions:

Compressor speed control	Fixed	Heating water volume flow rate (indoor heat exchanger)	Fixed
Outlet water temperature (indoor heat exchanger)	Variable	Source liquid volume flow rate (outdoor heat exch.)	-
Function	Reversible		



O-B-01502-22, page 1 (2)

Strojirenský zkušební ústav, s.p., Hudcova 424/56b, 621 00 Brno, Česká republika
Engineering Test Institute, public enterprise, Hudcova 424/56b, 621 00 Brno, Czech Republic

www.szutest.cz



**Results:**

Model names		Airkompakt p0916 (Tested)	Airkompakt p1118 (Not tested)	Airkompakt p1522 (Not tested)	Airkompakt p1928 (Not tested)
Temperature condition*					
A7/W35	Corrected heat capacity [kW]	9.062	11.200	15.180	19.650
	Effective power input [kW]	1.950	2.599	3.667	4.226
	Coefficient of performance [-]	4.647	4.310	4.140	4.650
	Control settings [-]	-	-	-	-
A7/W55	Corrected heat capacity [kW]	8.428	11.200	12.890	17.400
	Effective power input [kW]	2.678	3.478	4.901	5.918
	Coefficient of performance [-]	3.148	3.220	2.630	2.940
	Control settings [-]	-	-	-	-
A2/W35	Corrected heat capacity [kW]	6.996	9.400	13.500	14.400
	Effective power input [kW]	1.911	2.473	3.562	3.891
	Coefficient of performance [-]	3.660	3.800	3.790	3.700
	Control settings [-]	-	-	-	-

Sound power level at condition A7/W55*:

LWA	[dB(A)]	62.9 ± 1.5	66.0 ± 1.5	68.0 ± 1.5	69.0 ± 1.5
------------	---------	------------	------------	------------	------------

Accuracy class

Engineering (2)

(*) Comment to abbreviated marking e.g. A7W35 B0/W35:

„A“ air, „7“ inlet temperature (dry-bulb temperature) in °C, „W“ water, „35“ outlet temperature in °C.

(Tested) This test sample was tested at the Testing Laboratory.

(Not tested) The technical data were declared by the Manufacturer according to the model range specifications and were not tested by the Testing Laboratory.

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2022-09-30



Milan Holomek

Head of Heat and Environment-Friendly Equipment Test Station



- END OF TEST CERTIFICATE -

Tłumaczenie przysięgłe z jęz. angielskiego na jęz. polski

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, Brno, Republika Czeska

CERTYFIKAT TESTÓW
Numer: O-B-01496-22 rev.1

Klient KOŁTON SPÓŁKA KOMANDYTOWA
ul. Sosnowa 2
34-480 Jabłonka
POLSKA

Produkt Pompa ciepła typu powietrze/woda – monoblok

Oznaczenie typu/
znak towarowy **Airkompakt p0916**

Metody testowe ČSN EN 14511-3:2019, ČSN EN 14825:2020; ČSN EN 12102-1:2018,
Przepisy dotyczące badań EHPA – Badanie pomp ciepła typu powietrze/woda, wersja 2.4a

Podstawa certyfikatu Raporty z testów:
39-16511/T z 2022-09-16
39-16511/H z 2022-09-16
Dokumentacja techniczna KOŁTON SPÓŁKA KOMANDYTOWA

Referencyjny sezon grzewczy „A” = umiarkowany
(Referencyjna temperatura projektowa $T_{designh} = -10^{\circ}\text{C}$)

Wyniki:

NISKA TEMPERATURA

(Referencyjna temperatura wody 35°C)

ŚREDNIA TEMPERATURA

(Referencyjna temperatura wody 55°C)

6,20		$P_{designh}$ [kW] ... Znamionowa moc cieplna		6,28	
4,00		SCOP [-] ... Sezonowy współczynnik efektywności		3,25	
Temperatura zewnętrzna	Deklarowana wydajność grzewcza	Współczynnik efektywności przy deklarowanej wydajności	Temperatura zewnętrzna	Deklarowana wydajność grzewcza	Współczynnik efektywności przy deklarowanej wydajności
T_j [$^{\circ}\text{C}$]	P_{dh} [kW]	COP_d [-]	T_j [$^{\circ}\text{C}$]	P_{dh} [kW]	COP_d [-]
$T_j = -7$	5,482	2,902	$T_j = -7$	5,558	2,285
$T_j = +2$	7,066	3,878	$T_j = +2$	6,865	3,125
$T_j = +7$	9,209	5,130	$T_j = +7$	8,854	4,189
$T_j = +12$	10,611	6,025	$T_j = +12$	10,398	5,230
$T_j = \text{TOL} = -10$	5,260	2,765	$T_j = \text{TOL} = -10$	5,127	2,003
$T_j = T_{bivalent} = -7$	5,482	2,902	$T_j = T_{bivalent} = -7$	5,558	2,285

[okrągła pieczęć]

O-B-01496-22, strona 1 (2)

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,
Hudcova 424/56b, 621 00 Brno, Republika Czeska
www.szutest.cz

[Hologram]



NISKA TEMPERATURA
(Referencyjna temperatura wody 35°C)

ŚREDNIA TEMPERATURA
(Referencyjna temperatura wody 55°C)

Pobór mocy w trybach innych niż „tryb aktywny”

14,8	Tryb wyłączony P _{OFF} [W]	14,8
14,7	Tryb wyłączonego termostatu P _{TO} [W]	14,7
14,8	Tryb czuwania P _{SB} [W]	14,8
0,00	Tryb grzałki karteru P _{CK} [W]	0,00

Roczne zużycie energii elektrycznej na ogrzewanie według:

3197	ČSN EN 14825:2020 Q _{HE} [kWh]	3995
------	-----------------------------------------	------

Sezonowa efektywność energetyczna ogrzewania pomieszczeń η_s

157,2	ČSN EN 14825:2020 η _s [%]	127,0
-------	--------------------------------------	-------

Natężenie przepływu cieczy w zewnętrznym wymienniku ciepła:

-	Źródło cieczy	Min./Maks. [m ³ /h]	-
---	---------------	--------------------------------	---

Natężenie przepływu cieczy w wewnętrznym wymienniku ciepła:

0,9142/1,5814	Woda grzewcza	Min./Maks. [m ³ /h]	0,9142/1,5814
---------------	---------------	--------------------------------	---------------

Poziom mocy akustycznej w warunku A7W55*:

Airkompakt p0916 L_{WA} 62,9±1,5 dB(A) Klasa dokładności 2 (inżynieria)

(*) *Komentarz do skróconego oznaczenia:*

„A” = powietrze, „7” = temperatura na wlocie (temperatura termometru suchego) w °C, „W” = woda, „35” = temperatura na wylocie w °C.

(a) *Dane techniczne zostały zadeklarowane przez producenta lub obliczone na podstawie danych zadeklarowanych przez producenta i nie były badane przez Laboratorium Badawcze.*

Specyfikacja warunków:

Sterowanie prędkością sprężarki	Stałe	Przepływ objętościowy wody grzewczej (wewnętrzny wymiennik ciepła)	Stały
Temperatura wody na wylocie (wewnętrzny wymiennik ciepła)	Zmienna	Objętość przepływu cieczy źródłowej (zewnętrzny wymiennik ciepła)	-
Funkcja	Odwracalna		

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, potwierdza niniejszym Certyfikatem Testów, że badanie danego produktu zostało przeprowadzone z wynikami podanymi powyżej. Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, jest akredytowanym Laboratorium Badawczym 1045.1.

Brno, 30.09.2022 r.

[nieczytelny podpis]

Milan Holomek

Kierownik Stacji Badań Urządzeń Ciepłych i Przyjaznych Środowisku
- KONIEC CERTYFIKATU TESTÓW -

[okrągła pieczęć]

O-B-01496-22, strona 2 (2)

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,
Hudcova 424/56b, 621 00 Brno, Republika Czeska
www.szutest.cz

Nr rep. 572/24

Stwierdzam zgodność powyższego przekładu z oryginałem
Tytułem wynagrodzenia pobrano -
Augustów, dnia: 20.03.2024 r.

Tłumacz przysięgły języka angielskiego – mgr Piotr Szlaużys (nr TP/4453/05)



Tłumaczenie przysięgłe z jęz. angielskiego na jęz. polski

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, Brno, Republika Czeska

CERTYFIKAT TESTÓW

Numer: O-B-01497-22 rev.1

Klient	KOŁTON SPÓŁKA KOMANDYTOWA ul. Sosnowa 2 34-480 Jabłonka POLSKA
Produkt	Pompa ciepła typu powietrze/woda – monoblok
Oznaczenie typu/ znak towarowy	Airkompakt p0916
Metody testowe	ČSN EN 14511-3:2019, ČSN EN 14825:2020; ČSN EN 12102-1:2018, Przepisy dotyczące badań EHPA – Badanie pomp ciepła typu powietrze/woda, wersja 2.4a Raporty z testów:
Podstawa certyfikatu	39-16511/T z 2022-09-16 39-16511/H z 2022-09-16 Dokumentacja techniczna KOŁTON SPÓŁKA KOMANDYTOWA
Referencyjny sezon grzewczy	„W” = ciepły (Referencyjna temperatura projektowa $T_{designh} = +2\text{ °C}$)
Wyniki:	

NISKA TEMPERATURA

(Referencyjna temperatura wody 35°C)

ŚREDNIA TEMPERATURA

(Referencyjna temperatura wody 55°C)

7,00	$P_{designh}$ [kW] ... Znamionowa moc cieplna				6,52
5,00^(a)	SCOP [-] ... Sezonowy współczynnik efektywności				4,03^(a)
Temperatura zewnętrzna	Deklarowana wydajność grzewcza	Współczynnik efektywności przy deklarowanej wydajności	Temperatura zewnętrzna	Deklarowana wydajność grzewcza	Współczynnik efektywności przy deklarowanej wydajności
T_j [°C]	P_{dh} [kW]	COP_d [-]	T_j [°C]	P_{dh} [kW]	COP_d [-]
$T_j = -7$	-	-	$T_j = -7$	-	-
$T_j = +2$	6,996	3,660	$T_j = +2$	6,521	2,500
$T_j = +7^{(a)}$	8,900	4,790	$T_j = +7^{(a)}$	8,300	3,500
$T_j = +12^{(a)}$	10,500	5,700	$T_j = +12^{(a)}$	10,500	5,160
$T_j = TOL = +2$	6,996	3,660	$T_j = TOL = +2$	6,521	2,500
$T_j = T_{bivalent} = +2$	6,996	3,660*	$T_j = T_{bivalent} = +2$	6,521	2,500

[okrągła pieczęć]

O-B-01497-22, strona 1 (2)

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,
Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz

[Hologram]



NISKA TEMPERATURA
(Referencyjna temperatura wody 35°C)

ŚREDNIA TEMPERATURA
(Referencyjna temperatura wody 55°C)

Pobór mocy w trybach innych niż „tryb aktywny”

14,8	Tryb wyłączony P _{OFF} [W]	14,8
14,7	Tryb wyłączonego termostatu P _{TO} [W]	14,7
14,8	Tryb czuwania P _{SB} [W]	14,8
0,00	Tryb grzałki karteru P _{CK} [W]	0,00

Roczne zużycie energii elektrycznej na ogrzewanie według:

1870 ^(a)	ČSN EN 14825:2020 Q _{HE} [kWh]	2159 ^(a)
---------------------	-----------------------------------------	---------------------

Sezonowa efektywność energetyczna ogrzewania pomieszczeń

196,9 ^(a)	ČSN EN 14825:2020 η _s [%]	158,4 ^(a)
----------------------	--------------------------------------	----------------------

Natężenie przepływu cieczy w zewnętrznym wymienniku ciepła:

-	Źródło cieczy	Min./Maks. [m ³ /h]	-
---	---------------	--------------------------------	---

Natężenie przepływu cieczy w wewnętrznym wymienniku ciepła:

0,9142/1,5814	Woda grzewcza	Min./Maks. [m ³ /h]	0,9142/1,5814
---------------	---------------	--------------------------------	---------------

Poziom mocy akustycznej w warunku A7W55*

Airkompakt p0916 L_{WA} 62,9±1,5 dB(A) Klasa dokładności 2 (inżynieria)

(*) *Komentarz do skróconego oznaczenia:*

„A” powietrze, „7” = temperatura na wlocie (temperatura termometru suchego) w °C, „W” woda, „35” temperatura na wylocie w °C.

^(a) Dane techniczne zostały zadeklarowane przez producenta lub obliczone na podstawie danych zadeklarowanych przez producenta i nie były badane przez Laboratorium Badawcze.

Specyfikacja warunków:

Sterowanie prędkością sprężarki	Stałe	Przepływ objętościowy wody grzewczej (wewnętrzny wymiennik ciepła)	Stały
Temperatura wody na wylocie (wewnętrzny wymiennik ciepła)	Zmienna	Objętość przepływu cieczy źródłowej (zewnętrzny wymiennik ciepła)	-
Funkcja	Odwracalna		

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, potwierdza niniejszym Certyfikatem Testów, że badanie danego produktu zostało przeprowadzone z wynikami podanymi powyżej. Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, jest akredytowanym Laboratorium Badawczym 1045.1.

Brno, 30.09.2022 r.

[nieczytelny podpis]

Milan Holomek

Kierownik Stacji Badań Urządzeń Ciepłych i Przyjaznych Środowisku

- KONIEC CERTYFIKATU TESTÓW -

[okrągła pieczęć]

O-B-01497-22, strona 2 (2)

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,
Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz

Nr rep. 573/24

Stwierdzam zgodność powyższego przekładu z oryginałem

Tytułem wynagrodzenia pobrano -

Augustów, dnia: 20.03.2024 r.

Tłumacz przysięgły języka angielskiego – mgr Piotr Szlauzys (nr TP/4453/05)



Tłumaczenie przysięgłe z jęz. angielskiego na jęz. polski

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, Brno, Republika Czeska

CERTYFIKAT TESTÓW

Numer: O-B-01498-22 rev.1

Klient **KOŁTON SPÓŁKA KOMANDYTOWA**
ul. Sosnowa 2
34-480 Jabłonka
POLSKA

Produkt **Pompa ciepła typu powietrze/woda – monoblok**

Oznaczenie typu/
znak towarowy **Airkompakt p0916**

Metody testowe **ČSN EN 14511-3:2019, ČSN EN 14825:2020; ČSN EN 12102-1:2018,**
Przepisy dotyczące badań EHPA – Badanie pomp ciepła typu powietrze/woda, wersja 2.4a
Raporty z testów:

Podstawa certyfikatu **39-16511/T z 2022-09-16**
39-16511/H z 2022-09-16
Dokumentacja techniczna KOŁTON SPÓŁKA KOMANDYTOWA

Referencyjny sezon
grzewczy

„C” = chłodny

(Referencyjna temperatura projektowa $T_{designh} = -22\text{ °C}$)

Wyniki:

NISKA TEMPERATURA

ŚREDNIA TEMPERATURA

(Referencyjna temperatura wody 35 °C)

(Referencyjna temperatura wody 55 °C)

5,65		$P_{designh}$ [kW] ... Znamionowa moc cieplna		5,29	
3,54^(a)		SCOP [-] ... Sezonowy współczynnik efektywności		2,82^(a)	
Temperatura zewnętrzna	Deklarowana wydajność grzewcza	Współczynnik efektywności przy deklarowanej wydajności	Temperatura zewnętrzna	Deklarowana wydajność grzewcza	Współczynnik efektywności przy deklarowanej wydajności
T_j [°C]	P_{dh} [kW]	COP_d [-]	T_j [°C]	P_{dh} [kW]	COP_d [-]
$T_j = -7^{(a)}$	6,800	3,150	$T_j = -7^{(a)}$	6,600	2,400
$T_j = +2^{(a)}$	6,900	4,050	$T_j = +2^{(a)}$	6,900	3,300
$T_j = +7^{(a)}$	9,300	5,190	$T_j = +7^{(a)}$	8,700	4,610
$T_j = +12^{(a)}$	10,580	5,840	$T_j = +12$	10,461	5,394
$T_j = TOL = -22$	3,686	2,031	$T_j = TOL = -19^{(a)}$	3,600	1,670
$T_j = T_{bivalent} = -15$	4,606	2,573	$T_j = T_{bivalent} = -15$	4,314	1,921
$T_j = -15$	4,606	2,573	$T_j = -15$	4,314	1,921

[okrągła pieczęć]

O-B-01498-22, strona 1 (2)

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,

Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz

[Hologram]



NISKA TEMPERATURA

(Referencyjna temperatura wody 35°C)

ŚREDNIA TEMPERATURA

(Referencyjna temperatura wody 55°C)

Pobór mocy w trybach innych niż „tryb aktywny”

14,8	Tryb wyłączony P _{OFF} [W]	14,8
14,7	Tryb wyłączonego termostatu P _{TO} [W]	14,7
14,8	Tryb czuwania P _{SB} [W]	14,8
0,00	Tryb grzałki karteru P _{CK} [W]	0,00

Roczne zużycie energii elektrycznej na ogrzewanie według:

3930 ^(a)	ČSN EN 14825:2020 Q _{HE} [kWh]	4624 ^(a)
---------------------	-----------------------------------------	---------------------

Sezonowa efektywność energetyczna ogrzewania pomieszczeń

138,7 ^(a)	ČSN EN 14825:2020 η _s [%]	109,8 ^(a)
----------------------	--------------------------------------	----------------------

Nateżenie przepływu cieczy w zewnętrznym wymienniku ciepła:

-	Źródło cieczy	Min./Maks. [m ³ /h]	-
---	---------------	--------------------------------	---

Nateżenie przepływu cieczy w wewnętrznym wymienniku ciepła:

0,9142/1,5814	Woda grzewcza	Min./Maks. [m ³ /h]	0,9142/1,5814
---------------	---------------	--------------------------------	---------------

Poziom mocy akustycznej w warunku A7W55***Airkompakt p0916**L_{WA} 62,9±1,5 dB(A)

Klasa dokładności 2 (inżynieria)

(*) *Komentarz do skróconego oznaczenia:*

„A” powietrze, „7” = temperatura na wlocie (temperatura termometru suchego) w °C, „W” woda, „35” temperatura na wylocie w °C.

^(a) Dane techniczne zostały zadeklarowane przez producenta lub obliczone na podstawie danych zadeklarowanych przez producenta i nie były badane przez Laboratorium Badawcze.**Specyfikacja warunków:**

Sterowanie prędkością sprężarki	Stałe	Przepływ objętościowy wody grzewczej (wewnętrzny wymiennik ciepła)	Stały
Temperatura wody na wylocie (wewnętrzny wymiennik ciepła)	Zmienna	Objętość przepływu cieczy źródłowej (zewnętrzny wymiennik ciepła)	-
Funkcja	Odwracalna		

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, potwierdza niniejszym Certyfikatem Testów, że badanie danego produktu zostało przeprowadzone z wynikami podanymi powyżej. Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, jest akredytowanym Laboratorium Badawczym 1045.1.

Brno, 30.09.2022 r.

[nieczytelny podpis]

Milan Holomek

Kierownik Stacji Badań Urządzeń Ciepłych i Przyjaznych Środowisku

- KONIEC CERTYFIKATU TESTÓW -

[okrągła pieczęć]

O-B-01498-22, strona 2 (2)

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,

Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz

Nr rep. 574/24

Stwierdzam zgodność powyższego przekładu z oryginałem

Tytułem wynagrodzenia pobrano -

Augustów, dnia: 20.03.2024 r.

Tłumacz przysięgły języka angielskiego – mgr Piotr Szlauzys (nr TP/4453/05)



Tłumaczenie przysięgłe z jęz. angielskiego na jęz. polski

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, Brno, Republika Czeska

CERTYFIKAT TESTÓW

Numer: O-B-01499-22 rev.1

Klient KOŁTON SPÓŁKA KOMANDYTOWA
ul. Sosnowa 2
34-480 Jablonka
POLSKA

Produkt Pompa ciepła typu powietrze/woda – monoblok

Oznaczenie typu/
znak towarowy **Airkompakt p0916**

Metody testowe ČSN EN 14511-2:2019, ČSN EN 14511-3:2019;
ČSN EN 14511:4:2019, ČSN EN 12102-1:2018, Przepisy dotyczące badań
EHPA – Badanie pomp ciepła typu powietrze/woda, wersja 2.4a
Raporty z testów:

Podstawa certyfikatu 39-16511/T z 2022-09-16
39-16511/H z 2022-09-16
Dokumentacja techniczna KOŁTON SPÓŁKA KOMANDYTOWA

Zastosowana temp. **NISKA TEMPERATURA**
(Referencyjna temperatura wody 35°C)
ŚREDNIA TEMPERATURA
(Referencyjna temperatura wody 55°C)

Wyniki:

Warunki temperaturowe*	A7/W35	A7/W55
Skorygowana wydajność grzewcza [kW]	9,062	8,428
Efektywny pobór mocy elektrycznej [kW]	1,950	2,678
Współczynnik efektywności [-]	4,647	3,148
Ustawienia sprężarki [-]	-	-

(*) Komentarz do skróconego oznaczenia: np. A7/W35
A (powietrze), 7 (powietrze wejściowe - temperatura termometru suchego w °C) / W (woda),
35 (wyjściowa temperatura wody grzewczej (chłodzącej) w °C)
[okrągła pieczęć]

O-B-01499-22, strona 1 (2)

[Hologram]
Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,
Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz



Poziom mocy akustycznej w warunkach temperaturowych A7/W55*:

Pompa ciepła typu powietrze/woda – monoblok

Airkompakt p0916

Poziom mocy akustycznej

$L_{WA} 62,9 \pm 1,5 \text{ dB(A)}$

Klasa dokładności


Inżynieria (klasa 2)

(*) *Komentarz do skróconego oznaczenia: np. A7/W55*

A (powietrze), 7 (powietrze wejściowe - temperatura termometru suchego w °C) / W (woda),

55 (wyjściowa temperatura wody grzewczej (chłodzącej) w °C)

Zakres temperatur pracy:



Natężenie przepływu cieczy:

w zewnętrznym wymienniku ciepła

Minimalne – m³/h

Maksymalne – m³/h

w wewnętrznym wymienniku ciepła

Minimalne 0,9142 m³/h

Maksymalne 1,5814 m³/h

Zgodne z

ČSN EN 14511-4:2019, artykuły: 4.2.1.2, 4.2.1.3, 4.5

Specyfikacja warunków:

Sterowanie prędkością sprężarki	Stałe	Przepływ objętościowy wody grzewczej (wewnętrzny wymiennik ciepła)	Stały
Temperatura wody na wylocie (wewnętrzny wymiennik ciepła)	Zmienna	Objętość przepływu cieczy źródłowej (zewnętrzny wymiennik ciepła)	-
Funkcja	Odwracalna		

Institut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, potwierdza niniejszym Certyfikatem Testów, że badanie danego produktu zostało przeprowadzone z wynikami podanymi powyżej. Institut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, jest akredytowanym Laboratorium Badawczym 1045.1.

Brno, 30.09.2022 r.

[nieczytelny podpis]

Milan Holomek

Kierownik Stacji Badań Urządzeń Ciepłych i Przyjaznych Środowisku

- KONIEC CERTYFIKATU TESTÓW -

[okrągła pieczęć]

O-B-01499-22, strona 2 (2)

Institut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,

Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz

Nr rep. 576/24

Stwierdzam zgodność powyższego przekładu z oryginałem

Tytułem wynagrodzenia pobrano -

Augustów, dnia: 20.03.2024 r.

Tłumacz przysięgły języka angielskiego – mgr Piotr Szlauzys (nr TP/4453/05)



Tłumaczenie przysięgłe z jęz. angielskiego na jęz. polski

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, Brno, Republika Czeska

CERTYFIKAT TESTÓW

Numer: O-B-01500-22 rev.1

Klient	KOŁTON SPÓŁKA KOMANDYTOWA ul. Sosnowa 2 34-480 Jabłonka POLSKA
Produkt	Pompa ciepła typu powietrze/woda – monoblok
Oznaczenie typu/ znak towarowy	Airkompakt p0916 Airkompakt p1118 Airkompakt p1522 Airkompakt p1926
Metody testowe	ČSN EN 14511-3:2019, ČSN EN 14825:2020; Przepisy dotyczące badań EHPA – Badanie pomp ciepła typu powietrze/woda, wersja 2.4a Raporty z testów:
Podstawa certyfikatu	39-16511/T z 2022-09-16 39-16511/H z 2022-09-16 Dokumentacja techniczna KOŁTON SPÓŁKA KOMANDYTOWA
Zastosowana temp.	NISKA TEMPERATURA (Referencyjna temperatura wody 35°C)
Referencyjny sezon grzewczy „A” = umiarkowany / „W” = ciepły / „C” = chłodny	(referencyjny warunek projektowy dla ogrzewania $T_{designh} = -10\text{ °C}/+2\text{ °C}/-22\text{ °C}$)

Specyfikacja warunków:

Sterowanie prędkością sprężarki	Stałe	Przepływ objętościowy wody grzewczej (wewnętrzny wymiennik ciepła)	Stały
Temperatura wody na wylocie (wewnętrzny wymiennik ciepła)	Zmienna	Objętość przepływu cieczy źródłowej (zewewnętrzny wymiennik ciepła)	-
Funkcja	Odwracalna		

[okrągła pieczęć]

O-B-01500-22, strona 1 (2)

[Hologram]

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,
Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz



Wyniki:

Nazwy modeli		Zastosowanie niskotemperaturowe (Referencyjna temperatura wody 35°C)				
		Airkompakt p0916 (Testowany)	Airkompakt p1118 (Nietestowany)	Airkompakt p1522 (Nietestowany)	Airkompakt p1926 (Nietestowany)	
Znamionowa moc cieplna	$P_{designh}$ [kW]	A	6,20	8,59	12,10	14,58
		W	7,00	9,40	13,50	14,40
		C	5,65	7,97	9,68	12,38
Temperatura biwalentna	$T_{bivalent}$ [°C]	A	-7	-7	-7	-7
		W	2	2	2	2
		C	-15	-15	-15	-15
Sezonowy współczynnik efektywności	SCOP [-]	A	4,00	4,05	4,08	4,08
		W	5,00 (Nietestowany)	5,16	4,96	5,13
		C	3,54 (Nietestowany)	3,61	3,55	3,53
Sezonowa efektywność energetyczna ogrzewania pomieszczeń	n_s [%]	A	157,2	159,1	160,1	160,2
		W	196,9 (Nietestowany)	203,3	195,3	202,3
		C	138,7 (Nietestowany)	141,2	139,1	138,3

(Testowany) Ta próbka testowa została przetestowana w Laboratorium Badawczym.

(Nietestowany) Dane techniczne zostały zadeklarowane przez Producenta zgodnie ze specyfikacją typoszeręgu i nie były sprawdzane przez Laboratorium Badawcze.

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, potwierdza niniejszym Certyfikatem Testów, że badanie danego produktu zostało przeprowadzone z wynikami podanymi powyżej. Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, jest akredytowanym Laboratorium Badawczym 1045.1.

Brno, 30.09.2022 r.

[nieczytelny podpis]

Milan Holomek

Kierownik Stacji Badań Urządzeń Ciepłych i Przyjaznych Środowisku

- KONIEC CERTYFIKATU TESTÓW -

[okrągła pieczęć]

O-B-014500-22, strona 2 (2)

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,

Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz


Nr rep. 580/24

Stwierdzam zgodność powyższego przekładu z oryginałem

Tytułem wynagrodzenia pobrano -

Augustów, dnia: 20.03.2024 r.

Tłumacz przysięgły języka angielskiego – mgr Piotr Szlaużys (nr TP/4453/05)



Tłumaczenie przysięgłe z jęz. angielskiego na jęz. polski

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, Brno, Republika Czeska

CERTYFIKAT TESTÓW Numer: O-B-01501-22 rev.1

Klient KOŁTON SPÓŁKA KOMANDYTOWA
ul. Sosnowa 2
34-480 Jablonka
POLSKA

Produkt Pompa ciepła typu powietrze/woda – monoblok

Oznaczenie typu/
znak towarowy **Airkompakt p0916**
Airkompakt p1118
Airkompakt p1522
Airkompakt p1926

Metody testowe ČSN EN 14511-3:2019, ČSN EN 14825:2020;
Przepisy dotyczące badań EHPA – Badanie pomp ciepła typu powietrze/woda,
wersja 2.4a
Raporty z testów:

Podstawa certyfikatu 39-16511/T z 2022-09-16
39-16511/H z 2022-09-16
Dokumentacja techniczna KOŁTON SPÓŁKA KOMANDYTOWA

Zastosowana temp. **ŚREDNIA TEMPERATURA**
(Referencyjna temperatura wody 55°C)

Referencyjny sezon grzewczy „A” = **umiarkowany** / „W” = **ciepły** / „C” = **chłodny**
(Referencyjny warunek projektowy dla ogrzewania $T_{designh} = -10\text{ °C}/+2\text{ °C}/-22\text{ °C}$)

Specyfikacja warunków:

Sterowanie prędkością sprężarki	Stałe	Przepływ objętościowy wody grzewczej (wewnętrzny wymiennik ciepła)	Stały
Temperatura wody na wylocie (wewnętrzny wymiennik ciepła)	Zmienna	Objętość przepływu cieczy źródłowej (zewnętrzny wymiennik ciepła)	-
Funkcja	Odwracalna		

[okrągła pieczęć]

O-B-01501-22, strona 1 (2)

[Hologram]

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,
Hudcova 424/56b, 621 00 Brno, Republika Czeska
www.szutest.cz



Wyniki:

Nazwy modeli		Zastosowanie średnitemperaturowe (Referencyjna temperatura wody 55°C)				
		Airkompakt p0916 (Testowany)	Airkompakt p1118 (Nietestowany)	Airkompakt p1522 (Nietestowany)	Airkompakt p1926 (Nietestowany)	
Znamionowa moc cieplna	$P_{designh}$ [kW]	A	6,28	8,59	11,42	13,90
		W	6,52	8,90	11,60	14,40
		C	5,29	7,72	9,68	12,38
Temperatura biwalentna	$T_{bivalent}$ [°C]	A	-7	-7	-7	-7
		W	2	2	2	2
		C	-15	-15	-15	-15
Sezonowy współczynnik efektywności	SCOP [-]	A	3,25	3,39	3,20	3,35
		W	4,03 (Nietestowany)	4,07	4,13	4,10
		C	2,82 (Nietestowany)	2,97	2,93	2,94
Sezonowa efektywność energetyczna ogrzewania pomieszczeń	n_s [%]	A	127,0	132,8	125,0	131,2
		W	158,4 (Nietestowany)	159,8	162,4	161,1
		C	109,8 (Nietestowany)	116,0	114,2	114,5

(Testowany) Ta próbka testowa została przetestowana w Laboratorium Badawczym.

(Nietestowany) Dane techniczne zostały zadeklarowane przez Producenta zgodnie ze specyfikacją typoszeręgu i nie były sprawdzane przez Laboratorium Badawcze.

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, potwierdza niniejszym Certyfikatem Testów, że badanie danego produktu zostało przeprowadzone z wynikami podanymi powyżej. Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, jest akredytowanym Laboratorium Badawczym 1045.1.

Brno, 30.09.2022 r.

[nieczytelny podpis]

Milan Holomek

Kierownik Stacji Badań Urządzeń Ciepłych i Przyjaznych Środowisku

- KONIEC CERTYFIKATU TESTÓW -

[okrągła pieczęć]

O-B-014501-22, strona 2 (2)

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,
Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz


Nr rep. 575/24

Stwierdzam zgodność powyższego przekładu z oryginałem

Tytułem wynagrodzenia pobrano -

Augustów, dnia: 20.03.2024 r.

Tłumacz przysięgły języka angielskiego – mgr Piotr Szlauzys (nr TP/4453/05)



Tłumaczenie przysięgłe z jęz. angielskiego na jęz. polski

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, Brno, Republika Czeska

CERTYFIKAT TESTÓW

Numer: O-B-01502-22 rev.1

Klient	KOŁTON SPÓŁKA KOMANDYTOWA ul. Sosnowa 2 34-480 Jabłonka POLSKA
Produkt	Pompa ciepła typu powietrze/woda – monoblok
Oznaczenie typu/ znak towarowy	Airkompakt p0916 Airkompakt p1118 Airkompakt p1522 Airkompakt p1926
Metody testowe	ČSN EN 14511-2:2019, ČSN EN 14511-3:2019, ČSN EN 14511-4:2019, ČSN EN 12102-1:2018, Przepisy dotyczące badań EHPA – Badanie pomp ciepła typu powietrze/woda, wersja 2.4a
Podstawa certyfikatu	Raporty z testów: 39-16511/T z 2022-09-16 39-16511/H z 2022-09-16 Dokumentacja techniczna KOŁTON SPÓŁKA KOMANDYTOWA NISKA TEMPERATURA (Referencyjna temperatura wody 35°C)
Zastosowana temp.	ŚREDNIA TEMPERATURA (Referencyjna temperatura wody 55°C)

Specyfikacja warunków:

Sterowanie prędkością sprężarki	Stałe	Przepływ objętościowy wody grzewczej (wewnętrzny wymiennik ciepła)	Stały
Temperatura wody na wylocie (wewnętrzny wymiennik ciepła)	Zmienna	Objętość przepływu cieczy źródłowej (zewnętrzny wymiennik ciepła)	-
Funkcja	Odwracalna		

[okrągła pieczęć]


O-B-01502-22, strona 1 (2)

[Hologram]

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,

Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz



Wyniki:

Nazwy modeli		Airkompakt p0916 (Testowany)	Airkompakt p1118 (Nietestowany)	Airkompakt P1522 (Nietestowany)	Airkompakt p1926 (Nietestowany)
Warunki temperaturowe					
A7/W35	Skorygowana wydajność grzewcza [kW]	9,062	11,200	15,180	19,650
	Efektywny pobór mocy [kW]	1,950	2,599	3,667	4,226
	Współczynnik efektywności [-]	4,647	4,310	4,140	4,650
	Ustawienia sterowania [-]	-	-	-	-
A7/W55	Skorygowana wydajność grzewcza [kW]	8,428	11,200	12,890	17,400
	Efektywny pobór mocy [kW]	2,678	3,478	4,901	5,918
	Współczynnik efektywności [-]	3,148	3,220	2,630	2,940
	Ustawienia sterowania [-]	-	-	-	-
A2/W35	Skorygowana wydajność grzewcza [kW]	6,996	9,400	13,500	14,400
	Efektywny pobór mocy [kW]	1,911	2,473	3,562	3,891
	Współczynnik efektywności [-]	3,660	3,800	3,790	3,700
	Ustawienia sterowania [-]	-	-	-	-

Poziom mocy akustycznej w warunku A7/W55*:

L _{WA}	[dB(A)]	62,9 ± 1,5	66,0 ± 1,5	68,0 ± 1,5	69,0 ± 1,5
-----------------	---------	------------	------------	------------	------------

Klasa dokładności

Inżynieria (2)

(*) Komentarz do skróconego oznaczenia, np. A7W35 B0/W35:

„A” powietrze, „7” temperatura na wlocie (temperatura termometru suchego) w °C, „W” woda, „35” temperatura na wylocie w °C.

(Testowany) Ta próbka testowa została przetestowana w Laboratorium Badawczym.

(Nietestowany) Dane techniczne zostały zadeklarowane przez Producenta zgodnie ze specyfikacją typoszeregu i nie były sprawdzane przez Laboratorium Badawcze.

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne potwierdza niniejszym Certyfikatem Testów, że badanie danego produktu zostało przeprowadzone z wynikami podanymi powyżej. Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne, jest akredytowanym Laboratorium Badawczym 1045.1.

Brno, 30.09.2022 r.

[nieczytelny podpis]

Milan Holomek

Kierownik Stacji Badań Urządzeń Ciepłych i Przyjaznych Środowisku

- KONIEC CERTYFIKATU TESTÓW -

[okrągła pieczęć]

O-B-01502-22, strona 2 (2)

Instytut Testów Inżynieryjnych, Przedsiębiorstwo Publiczne,

Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz

Nr rep. 581/24

Stwierdzam zgodność powyższego przekładu z oryginałem

Tytułem wynagrodzenia pobrano -

Augustów, dnia: 20.03.2024 r.

Tłumacz przysięgły języka angielskiego – mgr Piotr Szlauzys (nr TP/4453/05)



OŚWIADCZENIE

Producent KOŁTON SPÓŁKA KOMANDYTOWA oświadcza, iż pompy ciepła

- 1) AIRKOMPAKT P0714
Oznaczenie/typ/identyfikator modelu
- 2) AIRKOMPAKT P0916
Oznaczenie/typ/identyfikator modelu
- 3) AIRKOMPAKT P1118
Oznaczenie/typ/identyfikator modelu
- 4)
Oznaczenie/typ/identyfikator modelu
- 5)
Oznaczenie/typ/identyfikator modelu

Należą do jednego podtypu w danym typoszeregu i spełniają łącznie następujące warunki:

- identyczna konstrukcja obiegu chłodniczego, ten sam czynnik chłodniczy/roboczy;
- ten sam producent, typ i liczba sprężarek;
- ten sam typ elementu rozprężnego;
- ten sam typ skraplacza;
- ten sam typ parownika;
- ten sam typ procesu odszraniania;
- ten sam sterownik i zasada sterowania wydajnością;
- ten sam producent, typ i liczba wentylatorów parownika (w przypadku powietrznych pomp ciepła) i zasada sterowania wydajnością (stała, zmienna lub stopniowana regulacja prędkości obrotowej);
- urządzenia z i bez zaworu czterodrogowego nie mogą być zaliczone do tego samego typoszeregu.

Jabłonka, dn. 10.04.2024 r.
Miejscowość, data

 **KOŁTON**

KOŁTON spółka komandytowa
ul. Sosnowa 2, 34-480 Jabłonka

NIP 735 274 90 54 REGON 120755317 KRS 000098729


Podpis osoby upoważnionej

