



**Testing Laboratory 1045.1**  
Accredited by the Czech Accreditation Institute pursuant to  
ČSN EN ISO/IEC 17025:2005  
**Strojírenský zkušební ústav, s.p. Testing Laboratory, Hudcova 424/56b, 621 00 Brno**  
Workplace Brno, Hudcova 424/56b, 621 00 Brno, Czech Republic

Page 1 of 57



## TEST REPORT 39-11227/T

**Product:** Air/Water Heat Pump – monobloc

**Type designation** Airmax<sup>2</sup> 21GT

**Customer:** “Galmet Sp. z o.o.” Sp. K.  
ul. Raciborska 36  
48-100 Głubczyce  
Poland

**Manufacturer:** “Galmet Sp. z o.o.” Sp. K.  
ul. Raciborska 36  
48-100 Głubczyce  
Poland

**Responsible employee:** Ing. Mario Jankola

**Report date issue:** 2018-01-05

**Distribution list:** 1 copy to the Engineering Test Institute  
1 copy to the Customer

This report may be copied in its entirety without written consent of the Engineering Test Institute.  
The results of tests and verifications only apply to the products tested.



The tests were conducted on the basis:

- Order B-59756 of 2017-06-27 (Order reg. no. B-59756 delivered on 2017-06-28)
- Contract B-59756/39
- Amendment No. 1 to Contract B-59756/39

## **I. Description of tested product**

The Heat pump **Airmax<sup>2</sup> 21GT** from the company "**Galmet Sp. z o.o.**" **Sp. K.** is structurally adapted to operate in air/water system. Device is designed as monobloc. Refrigerant R-410A is used with charge 5.50 kg. Power supply is three-phase. Heat pump is able to work in heating/cooling mode.

Main components of the unit **Airmax<sup>2</sup> 21GT**:


- Cuboid shape with dimensions 1470 × 700 × 1400 mm (W × D × H)
- Frame and casing made of varnished steel
- Cuboid evaporator (4-row), dimensions 960 × 84 × 1090 mm (L × D × H), spacing 2.1 mm, with surface treatment
- Electric expansion valve Carel E2V35
- Thermostatic expansion valve (for EVI) Alco controls TX3-Z35
- Solenoid valve (for EVI) Sanhua China MQ-AO3226
- Axial fan with motor Ziehl-Abegg FN080-ZII.DG.V5P4, ø800
- Refrigerant R-410A (charge: 5.50 kg)
- Filterdehydrator Sanhua, view glass Sanhua
- Plate condenser with heat insulation, dimensions 120 × 190 × 560 mm (W × D × H)
- EVI with heat insulation, dimensions 90 × 50 × 320 mm (W × D × H)
- Water pump Grundfoss UPML GEO 25-105
- 4-way reversing valve Sanhua SHF-35B-67-02-E
- 2× Pressure transducer Carel
- 2× Pressure switch Emerson
- Temperature sensors on refrigerant pipe, outside on casing and others for external devices
- Electric backup heater 7 kW
- Compressor Emerson Copeland Scroll ZHI18K1P-TFM-526




Photos:




Heat pump Airmax<sup>2</sup> 21GT  
– unit with cover –



Heat pump Airmax<sup>2</sup> 21GT  
– unit without cover (detail) –



Heat pump Airmax<sup>2</sup> 21GT  
– unit label –

		
www.galmef.com.pl		
pompyciepla@galmef.com.pl Tel. 77 403 45 00		
<b>TYP: Airmax<sup>2</sup> 21GT</b>		
Pompa ciepła powietrze-woda		
Nr kat.: 09-262100		CE
Moc grzewcza A7/W35:	20.98	kW
Pobór mocy el. A7/W35:	4.58	kW
COP A7/W35	4.57	
Napięcie znam.:	400V	
Prąd znamionowy:	9.7	A
Czynnik chłodniczy:	R410a / 5.5	kg
Maks ciśnienie układu chłodn.:	4.2	MPa
Moc el. grzałki	7	kW
Stopień ochrony:	IP22	
Przepływ powietrza:	7000	m <sup>3</sup> /h
Wymiary:	1500x1405x700	mm
Waga:	230	kg
Data produkcji:	2017-11	
Nr. fabryczny:	17P001407	



5801224792892(21)17P001407

**Nr kat.: 09-262100**

Data prod.: 2017-11 Nr. fabr.: 17P001407

Heat pump Airmax<sup>2</sup> 21GT  
– compressor label –



## II. Sample tested

- Number of samples: 1
- Name of samples: Heat pump **Airmax<sup>2</sup> 21GT**
- Date of submission or collection: 2017-12-07 (2017-11-20)
- Reg. number: 0213.17.17724.000 (0213.17.17692.000)
- Serial number: 17P001407

The visual inspection, testing and verification were carried out by Ing. Tomáš Fiala at the test station of SZU.

## III. Measuring and testing equipment

The testing was conducted using measurement and testing equipment with valid calibration.

No.	Name:	Inventory number:	Calibration is valid to:	Accuracy see Calibration Sheet number:
1.	Electrical energy meter	022370/1	07/2022	082/12/E
2.	Flow meter Krohne Optiflux	022370/4	03/2020	6015-KL-P0163-16
3.	Barometer	022370/7	04/2019	3373/2014
4.	Differential pressure gauge	022370/8	08/2018	160137
5.	Temperature-humidity meter HC2-IC305	022370/10	07/2019	6036-KL-V0248-14
6.	Temperature-humidity meter HC2-IC305	022370/11	07/2019	6036-KL-V0247-14
7.	Thermometers	022370/13	04/2020	170052

## IV. Test results

Accredited test number: **T 037\*** Test title: **Tests of leakage, pressure resistance, thermal and technical parameters, combustion efficiency, safety functions**

Testing method: **ČSN EN 14511-2+4:2014**  
**ČSN EN 14825:2016**  
**EHPA Testing regulation – Testing of Air/Water Heat Pumps, ver. 2.3**

Sample tested: **Heat pump Airmax<sup>2</sup> 21GT**

Measuring equipment used: **See chapter III.**

Place of testing:	at the Engineering Test Institute	<input checked="" type="checkbox"/>	at the Manufacturer's premises	<input type="checkbox"/>	at the Customer's premises	<input type="checkbox"/>	other:
-------------------	-----------------------------------	-------------------------------------	--------------------------------	--------------------------	----------------------------	--------------------------	--------



a) **Rating conditions:**

**Measurement results:**

Test number		1	2	3
Assessment condition		Rating condition		
Specification of the assessment condition <sup>(*)</sup>		A7/W35	A2/W35	A7/W55
Date of testing		2017-11-21	2017-11-22	2017-11-22
Transient test procedure	YES / NO	NO	YES	NO
Average defrost time of 1 cycle	[min]	-	4.3	-
Average time of 1 cycle	[min]	-	45.1	-
Calculation time	[min]	70.0	135.4	70.0
Output heating water – temperature calculation	[°C]	35.00	33.88	55.01
Input heating water – temperature calculation	[°C]	29.98	30.28	46.90
Output heating water temperature	[°C]	35.00	35.06	55.01
Input heating water temperature	[°C]	29.98	30.73	46.90
Air temperature - dry bulb temperature	[°C]	7.01	1.96	7.01
Air temperature - wet bulb temperature	[°C]	6.02	0.98	6.02
Relative humidity	[%]	87.04	84.09	86.99
Barometric pressure	[kPa]	98.132	98.165	98.163
Ambient temperature	[°C]	7.01	1.96	7.01
Secondary circuit pressure difference	[kPa]	1.180	1.368	5.414
Efficiency of the secondary liquid pump	[-]	0.076	0.080	0.107
Volume flow rate of heating water	[m <sup>3</sup> ·h <sup>-1</sup> ]	3.6253	3.6165	2.2905
Density of heating water	[kg·m <sup>-3</sup> ]	994.0	994.3	985.8
Specific heat capacity of heating water	[kJ·kg <sup>-1</sup> ·K <sup>-1</sup> ]	4.180	4.180	4.180
Voltage	[V]	400.08	399.45	399.51
Total current	[A]	29.17	28.28	36.59
Overall power input	[kW]	4.601	4.360	6.791
Partial power input of secondary liquid pump	[W]	15.57	17.18	32.23
Heating capacity - heating water	[kW]	20.997	15.048	21.248
<b>Corrected heating capacity - heating water</b>	<b>[kW]</b>	<b>20.981</b>	<b>15.031</b>	<b>21.216</b>
Uncertainty of corrected heating capacity	[kW]	± 0.299	± 0.297	± 0.189
<b>Effective electric power input</b>	<b>[kW]</b>	<b>4.586</b>	<b>4.342</b>	<b>6.759</b>
<b>COP</b>	<b>[-]</b>	<b>4.575</b>	<b>3.461</b>	<b>3.139</b>
Uncertainty of COP	[-]	± 0.065	± 0.069	± 0.028
<b>Control settings</b>	<b>[ ]</b>	<b>-</b>	<b>-</b>	<b>-</b>
Circulation pump settings – heating water	[%]	55	55	40

<sup>(\*)</sup> Comment to abbreviated marking: e.g. A7/W35

A (air) 7 (input air, dry-bulb temperature in °C) / W (water), 35 (output heating water temperature in °C)



**b) Seasonal performance tests and SCOP calculation – Low temperature application for reference heating seasons:**

**„A“ = average** (reference water temperature 35 °C, reference design conditions for heating T<sub>designh</sub> = -10 °C)

**„W“ = warmer** (reference water temperature 35 °C, reference design conditions for heating T<sub>designh</sub> = +2 °C)

**„C“ = colder** (reference water temperature 35 °C, reference design conditions for heating T<sub>designh</sub> = -22 °C)

Model		Heat pump <b>Airmax<sup>2</sup> 21GT</b>			
Design		Air / Water – monobloc			
Conditions specification according to ČSN EN 14825:2016	Temperature application			<b>Low</b> (reference water temperature 35 °C)	
	Reference heating season			<b>A, W, C</b>	
	Outlet water temperature - indoor heat exchanger			Variable	
	Compressor speed control			Fixed	
	Water flow rate – primary circuit			-	
Water flow rate – secondary circuit			Variable		
Seasonal space heating energy efficiency	Heating	Average	$\eta_s / A$	<b>154.2</b>	%
		Warmer	$\eta_s / W$	194.5 (not tested)	%
		Colder	$\eta_s / C$	130.1 (not tested)	%
Seasonal efficiency according to ČSN EN 14825:2016	Heating	Average	<b>SCOP / A</b>	<b>3.93</b>	-
		Warmer	SCOP / W	4.94 (not tested)	-
		Colder	SCOP / C	3.33 (not tested)	-
Function	Cooling				Yes
	Heating	Yes	Reference heating season	Average	Yes
				Warmer (if designated)	Yes
				Colder (if designated)	Yes
Full heating load	Cooling		P <sub>designc</sub>	-	kW
	Heating	Average	P <sub>designh</sub>	<b>14.12</b>	kW
		Warmer	P <sub>designh</sub>	<b>14.27</b>	kW
		Colder	P <sub>designh</sub>	<b>15.58</b>	kW
Bivalent temperatures	Heating	Average	T <sub>bivalent</sub>	-7	°C
		Warmer	T <sub>bivalent</sub>	2	°C
		Colder	T <sub>bivalent</sub>	-10	°C
Operation limit temperatures	Heating	Average	TOL	-20	°C
		Warmer	TOL	-20	°C
		Colder	TOL	-20	°C
Seasonal power consumption according to ČSN EN 14825:2016	Cooling		Q <sub>CE</sub>	-	kWh
	Heating	Average	Q <sub>HE/A</sub>	7421	kWh
		Warmer	Q <sub>HE/W</sub>	3863 (not tested)	kWh
		Colder	Q <sub>HE/C</sub>	11539 (not tested)	kWh
Modes other than „active mode“	Off mode		P <sub>OFF</sub>	9.8	W
	Thermostat off mode		P <sub>TO</sub>	10.0	W
	Standby mode		P <sub>SB</sub>	9.8	W
	Crankcase heater mode		P <sub>CK</sub>	0.0	W

(Not tested): The technical data were declared by the Manufacturer and were not tested by the Testing Laboratory.



### Calculation of SCOP according to ČSN EN 14825:2016:

Number of hours used for calculation of reference SCOP (Annex B – Table B.2, B.3)

- For reversible heat pumps and reference heating season „A“ = average

H <sub>HE</sub>	2066	[h]
H <sub>TO</sub>	178	[h]
H <sub>SB</sub>	0	[h]
H <sub>CK</sub>	178	[h]
H <sub>OFF</sub>	0	[h]

Measured data:

P <sub>TO</sub>	0.0100	[kW]
P <sub>SB</sub>	0.0098	[kW]
P <sub>CK</sub>	0.0000	[kW]
P <sub>OFF</sub>	0.0098	[kW]
P <sub>designh</sub>	14.12	[kW]
SCOP <sub>ON</sub>	3.93	[-]

Coefficient and correction:

F(1)	3	[%]
F(2)	0	[%]
CC	2.5	[-]

#### Calculation of SCOP:

7.3 Calculation of the reference annual heating demand (Q<sub>H</sub>)

$$Q_H = P_{\text{designh}} \cdot H_{\text{HE}} \quad [\text{kWh}]$$

$$Q_H = 14.12 \cdot 2066 = 29170 \quad [\text{kWh}]$$

7.4 Calculation of the annual electricity consumption (Q<sub>HE</sub>)

$$Q_{\text{HE}} = Q_H / \text{SCOP}_{\text{on}} + H_{\text{TO}} \cdot P_{\text{TO}} + H_{\text{SB}} \cdot P_{\text{SB}} + H_{\text{CK}} \cdot P_{\text{CK}} + H_{\text{OFF}} \cdot P_{\text{OFF}} \quad [\text{kWh}]$$

$$Q_{\text{HE}} = 29170 / 3.93 + 178 \cdot 0.01 + 0 \cdot 0.0098 + 178 \cdot 0 + 0 \cdot 0.0098 = 7421 \quad [\text{kWh}]$$

7.2 General formula for calculation of reference SCOP

$$\text{SCOP} = Q_H / Q_{\text{HE}} \quad [-]$$

$$\text{SCOP} = 29170 / 7421 = 3.93 \quad [-]$$

7.1 Calculation of the seasonal space heating efficiency  $\eta_s$

$$\Sigma F(i) = F(1) + F(2) \quad [-]$$

$$\Sigma F = 0.03 + 0 = 0.03 \quad [-]$$

$$\eta_s = 1 / \text{CC} \cdot \text{SCOP} - \Sigma F(i) \quad [-]$$

$$\eta_s (A) = (1 / 2.5) \cdot 3.93 - 0.03 = \underline{\underline{1.542}} \quad [-]$$





Data for SCOP calculation (Heat pump **Airmax<sup>2</sup> 21GT**)

- Low temperature application (reference water temperature 35 °C)
- Reference heating season "A" – average

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (Tj)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]								
<b>A</b>	-7	34.00	88.46	12.49	12.490	2.944	0.900	1.00	2.944	-
<b>B</b>	2	32.47	53.85	7.60	15.016	3.734	0.998	0.51	3.725	0.0100
<b>C</b>	7	30.80	34.62	4.89	20.357	4.949	0.998	0.24	4.911	0.0100
<b>D</b>	12	28.51	15.38	2.17	22.322	5.828	0.997	0.10	5.690	0.0100
<b>TOL (E)</b>	-10	35.00	100.00	14.12	10.789	2.524	0.900	1.31	2.524	-
<b>Tbiv (F)</b>	-7	34.00	88.46	12.49	12.490	2.944	0.900	1.00	2.944	-

**Adaption of water temperature – according to ČSN EN 14825:2016, Annex D**

- Low temperature application (reference water temperature 35 °C)
- Reference season "A" – average
- Condition D
- Variable water flow rate - secondary circuit

$$\begin{aligned}
 t_{\text{outlet, average}} &= t_{\text{inlet, capacity test}} + (t_{\text{outlet, capacity test}} - t_{\text{inlet, capacity test}}) \cdot CR && [^{\circ}\text{C}] \\
 t_{\text{outlet, average}} &= t_{\text{inlet, capacity test}} + (\Delta t) \cdot CR && [^{\circ}\text{C}] \\
 t_{\text{outlet, average}} &= t_{\text{outlet, capacity test}} - \Delta t + \Delta t \cdot CR && [^{\circ}\text{C}] \\
 t_{\text{outlet, capacity test}} &= t_{\text{outlet, average}} + \Delta t - \Delta t \cdot CR && [^{\circ}\text{C}]
 \end{aligned}$$

For variable flow:

$$\Delta t = 5$$

$$CR \cdot \Delta t = \text{Part load} / \text{Declared capacity} \cdot 5$$

$$t_{\text{outlet, capacity test, variable flow}} = t_{\text{outlet, average}} + 5 - \text{Part load} / \text{Declared capacity} \cdot 5$$

Measured data:

$t_{\text{outlet, average}}$	24.00	[°C]
Declared capacity	22.322	[kW]
Declared capacity <small>standard rating condition A7/W35</small>	-	[kW]
Part load	2.17	[kW]

Calculation of water temperature

$$t_{\text{outlet, capacity test, variable flow}} = 24 + 5 - 2.17 / 22.32 \cdot 5 = \mathbf{28.51} \quad [^{\circ}\text{C}]$$





Calculation SCOP, SCOP<sub>on</sub>, SCOP<sub>net</sub> (Heat pump Airmax<sup>2</sup> 21GT)

- Low temperature application (reference water temperature 35 °C)
- Reference heating season "A" – average


Bin	Outdoor temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistive heat elbu (Tj)	Annual resistive heat	COP <sub>bin</sub> (Tj)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating
j	T <sub>j</sub>	h <sub>j</sub>		P <sub>h(Tj)</sub>			elbu <sub>(Tj)</sub>	h <sub>j</sub> × elbu <sub>(Tj)</sub>		h <sub>j</sub> × P <sub>h(Tj)</sub>		h <sub>j</sub> × (P <sub>h(Tj)</sub> - elbu <sub>(Tj)</sub> )	
[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]
<b>TOL(E)</b>	<b>21</b>	<b>-10</b>	<b>1</b>	<b>100.00</b>	<b>10.79</b>	<b>10.79</b>	<b>3.33</b>	<b>3.33</b>	<b>2.52</b>	<b>14</b>	<b>8</b>	<b>11</b>	<b>4</b>
	22	-9	25	96.15	11.36	11.36	2.22	55.51	2.66	339	162	284	107
	23	-8	23	92.31	11.92	11.92	1.11	25.53	2.80	300	123	274	98
<b>A, Tbiv(F)</b>	<b>24</b>	<b>-7</b>	<b>24</b>	<b>88.46</b>	<b>12.49</b>	<b>12.49</b>	<b>0.00</b>	<b>0.00</b>	<b>2.94</b>	<b>300</b>	<b>102</b>	<b>300</b>	<b>102</b>
	25	-6	27	84.62	12.77	11.95	0.00	0.00	3.03	323	106	323	106
	26	-5	68	80.77	13.05	11.40	0.00	0.00	3.12	775	249	775	249
	27	-4	91	76.92	13.33	10.86	0.00	0.00	3.20	988	308	988	308
	28	-3	89	73.08	13.61	10.32	0.00	0.00	3.29	918	279	918	279
	29	-2	165	69.23	13.89	9.77	0.00	0.00	3.38	1613	477	1613	477
	30	-1	173	65.38	14.17	9.23	0.00	0.00	3.46	1597	461	1597	461
	31	0	240	61.54	14.45	8.69	0.00	0.00	3.55	2085	587	2085	587
	32	1	280	57.69	14.74	8.15	0.00	0.00	3.64	2281	627	2281	627
<b>B</b>	<b>33</b>	<b>2</b>	<b>320</b>	<b>53.85</b>	<b>15.02</b>	<b>7.60</b>	<b>0.00</b>	<b>0.00</b>	<b>3.72</b>	<b>2433</b>	<b>653</b>	<b>2433</b>	<b>653</b>
	34	3	357	50.00	16.08	7.06	0.00	0.00	3.96	2520	636	2520	636
	35	4	356	46.15	17.15	6.52	0.00	0.00	4.20	2320	552	2320	552
	36	5	303	42.31	18.22	5.97	0.00	0.00	4.44	1810	408	1810	408
	37	6	330	38.46	19.29	5.43	0.00	0.00	4.67	1792	383	1792	383
<b>C</b>	<b>38</b>	<b>7</b>	<b>326</b>	<b>34.62</b>	<b>20.36</b>	<b>4.89</b>	<b>0.00</b>	<b>0.00</b>	<b>4.91</b>	<b>1593</b>	<b>324</b>	<b>1593</b>	<b>324</b>
	39	8	348	30.77	20.75	4.34	0.00	0.00	5.07	1512	298	1512	298
	40	9	335	26.92	21.14	3.80	0.00	0.00	5.22	1273	244	1273	244
	41	10	315	23.08	21.54	3.26	0.00	0.00	5.38	1026	191	1026	191
	42	11	215	19.23	21.93	2.72	0.00	0.00	5.53	584	105	584	105
<b>D</b>	<b>43</b>	<b>12</b>	<b>169</b>	<b>15.38</b>	<b>22.32</b>	<b>2.17</b>	<b>0.00</b>	<b>0.00</b>	<b>5.69</b>	<b>367</b>	<b>65</b>	<b>367</b>	<b>65</b>
	44	13	151	11.54	22.71	1.63	0.00	0.00	5.85	246	42	246	42
	45	14	105	7.69	23.11	1.09	0.00	0.00	6.00	114	19	114	19
	46	15	74	3.85	23.50	0.54	0.00	0.00	6.16	40	7	40	7
	Σ		4910						Σ	29165	7418	29080	7334

SCOP <sub>on</sub>	3.93	SCOP <sub>net</sub>	3.97
<b>SCOP</b>		<b>3.93</b>	



Power diagram - Heat pump **Airmax<sup>2</sup> 21GT**

- Low temperature application (reference water temperature 35 °C)
- Reference heating season "A" – average





Test results for single part load conditions (Heat pump **Airmax<sup>2</sup> 21GT**)

**Measurement results:**

Test number		4	5	6
Temperature level		Low temperature application (reference water temperature 35 °C)		
Reference heating season		"A" = average (T <sub>designh</sub> = -10 °C)		
Assessment condition		A, T <sub>biv</sub> (F)	B	C
Specification of the assessment condition <sup>(*)</sup>		A-7/W34	A2/W32.47	A7/W30.8
Date of testing		2017-11-23	2017-11-24	2017-12-07
Transient test procedure	YES / NO	YES	YES	NO
Average defrost time of 1 cycle	[min]	4.7	4.4	-
Average time of 1 cycle	[min]	79.7	44.6	-
Calculation time	[min]	79.7	133.9	70.0
Output heating water – temperature calculation	[°C]	33.30	31.30	30.84
Input heating water – temperature calculation	[°C]	28.87	27.14	25.80
Output heating water temperature	[°C]	34.05	32.49	30.84
Input heating water temperature	[°C]	29.07	27.53	25.80
Air temperature - dry bulb temperature	[°C]	-7.03	1.96	7.01
Air temperature - wet bulb temperature	[°C]	-8.03	0.97	6.02
Relative humidity	[%]	74.96	84.03	87.05
Barometric pressure	[kPa]	98.437	98.620	98.766
Ambient temperature	[°C]	-7.03	1.96	7.01
Secondary circuit pressure difference	[kPa]	3.424	2.895	2.157
Efficiency of the secondary liquid pump	[-]	0.094	0.097	0.091
Volume flow rate of heating water	[m <sup>3</sup> ·h <sup>-1</sup> ]	2.4492	3.1244	3.5017
Density of heating water	[kg·m <sup>-3</sup> ]	994.5	995.1	995.3
Specific heat capacity of heating water	[kJ·kg <sup>-1</sup> ·K <sup>-1</sup> ]	4.180	4.180	4.180
Voltage	[V]	398.70	399.81	399.58
Total current	[A]	27.95	27.31	27.73
Overall power input	[kW]	4.267	4.048	4.137
Partial power input of secondary liquid pump	[W]	24.68	25.98	22.97
Heating capacity - heating water	[kW]	12.515	15.042	20.380
<b>Corrected heating capacity - heating water</b>	<b>[kW]</b>	<b>12.490</b>	<b>15.016</b>	<b>20.357</b>
Uncertainty of corrected heating capacity	[kW]	± 0.202	± 0.257	± 0.289
<b>Effective electric power input</b>	<b>[kW]</b>	<b>4.242</b>	<b>4.022</b>	<b>4.114</b>
<b>COP</b>	<b>[-]</b>	<b>2.944</b>	<b>3.734</b>	<b>4.949</b>
Uncertainty of COP	[-]	± 0.048	± 0.064	± 0.071
<b>Control settings</b>	<b>[ ]</b>	<b>-</b>	<b>-</b>	<b>-</b>
Circulation pump settings – heating water	[%]	42	50	55

<sup>(\*)</sup> Comment to abbreviated marking: e.g. A7/W35

A (air) 7 (input air, dry-bulb temperature in °C) / W (water), 35 (output heating water temperature in °C)



Test results for single part load conditions (Heat pump **Airmax<sup>2</sup> 21GT**)

**Measurement results:**

Test number		7	8
Temperature level		Low temperature application (reference water temperature 35 °C)	
Reference heating season		"A" = average ( $T_{\text{designh}} = -10 \text{ °C}$ )	
Assessment condition		D	TOL (E)
Specification of the assessment condition <sup>(*)</sup>		A12/W28.51	A-10/W35
Date of testing		2017-12-11	2017-12-08
Transient test procedure	YES / NO	NO	YES
Average defrost time of 1 cycle	[min]	-	4.5
Average time of 1 cycle	[min]	-	102.6
Calculation time	[min]	70.0	102.6
Output heating water – temperature calculation	[°C]	28.54	34.25
Input heating water – temperature calculation	[°C]	23.50	29.72
Output heating water temperature	[°C]	28.54	34.97
Input heating water temperature	[°C]	23.50	29.95
Air temperature - dry bulb temperature	[°C]	12.04	-10.01
Air temperature - wet bulb temperature	[°C]	10.70	-11.04
Relative humidity	[%]	85.47	69.00
Barometric pressure	[kPa]	96.100	97.945
Ambient temperature	[°C]	12.04	-10.01
Secondary circuit pressure difference	[kPa]	0.849	2.670
Efficiency of the secondary liquid pump	[-]	0.070	0.082
Volume flow rate of heating water	[m <sup>3</sup> ·h <sup>-1</sup> ]	3.8294	2.0393
Density of heating water	[kg·m <sup>-3</sup> ]	995.9	994.2
Specific heat capacity of heating water	[kJ·kg <sup>-1</sup> ·K <sup>-1</sup> ]	4.180	4.180
Voltage	[V]	400.38	399.69
Total current	[A]	26.98	28.23
Overall power input	[kW]	3.843	4.292
Partial power input of secondary liquid pump	[W]	12.94	17.71
Heating capacity - heating water	[kW]	22.335	10.806
<b>Corrected heating capacity - heating water</b>	<b>[kW]</b>	<b>22.322</b>	<b>10.789</b>
Uncertainty of corrected heating capacity	[kW]	± 0.316	± 0.168
<b>Effective electric power input</b>	<b>[kW]</b>	<b>3.830</b>	<b>4.274</b>
<b>COP</b>	<b>[-]</b>	<b>5.828</b>	<b>2.524</b>
Uncertainty of COP	[-]	± 0.083	± 0.039
<b>Control settings</b>	<b>[ ]</b>	-	-
Circulation pump settings – heating water	[%]	58	35

<sup>(\*)</sup> Comment to abbreviated marking: e.g. A7/W35

A (air) 7 (input air, dry-bulb temperature in °C) / W (water), 35 (output heating water temperature in °C)



Test results for single part load conditions (Heat pump Airmax<sup>2</sup> 21GT)

**Measurement results:**

Test number		9	10	11
Temperature level		Low temperature application (reference water temperature 35 °C)		
Reference heating season		"W" = warmer (T <sub>designh</sub> = +2 °C)	"C" = colder (T <sub>designh</sub> = -22 °C)	
Assessment condition		<b>B, TOL (E), Tbiv (F)</b>	<b>C</b>	<b>Tbiv (F)</b>
Specification of the assessment condition <sup>(*)</sup>		<b>A2/W35</b>	<b>A7/W29.08</b>	<b>A-10/W30.75</b>
Date of testing		<b>2017-12-14</b>	<b>2017-12-13</b>	<b>2017-12-13</b>
Transient test procedure	YES / NO	YES	NO	YES
Average defrost time of 1 cycle	[min]	4.5	-	4.3
Average time of 1 cycle	[min]	45.5	-	77.3
Calculation time	[min]	136.5	70.0	154.7
Output heating water – temperature calculation	[°C]	33.72	29.07	29.81
Input heating water – temperature calculation	[°C]	29.48	24.09	25.45
Output heating water temperature	[°C]	35.11	29.07	30.68
Input heating water temperature	[°C]	30.00	24.09	25.72
Air temperature - dry bulb temperature	[°C]	1.98	7.02	-10.01
Air temperature - wet bulb temperature	[°C]	0.98	6.02	-11.01
Relative humidity	[%]	84.05	86.99	69.79
Barometric pressure	[kPa]	96.872	97.447	98.695
Ambient temperature	[°C]	1.98	7.02	-10.01
Secondary circuit pressure difference	[kPa]	0.719	6.442	5.696
Efficiency of the secondary liquid pump	[-]	0.061	0.129	0.106
Volume flow rate of heating water	[m <sup>3</sup> ·h <sup>-1</sup> ]	2.9029	3.4930	2.0980
Density of heating water	[kg·m <sup>-3</sup> ]	994.3	995.8	995.5
Specific heat capacity of heating water	[kJ·kg <sup>-1</sup> ·K <sup>-1</sup> ]	4.180	4.180	4.180
Voltage	[V]	399.83	400.39	399.95
Total current	[A]	27.86	27.24	27.15
Overall power input	[kW]	4.206	3.923	3.933
Partial power input of secondary liquid pump	[W]	7.84	48.38	30.89
Heating capacity - heating water	[kW]	14.282	20.077	10.689
<b>Corrected heating capacity - heating water</b>	<b>[kW]</b>	<b>14.275</b>	<b>20.029</b>	<b>10.658</b>
Uncertainty of corrected heating capacity	[kW]	± 0.239	± 0.288	± 0.173
<b>Effective electric power input</b>	<b>[kW]</b>	<b>4.198</b>	<b>3.875</b>	<b>3.902</b>
<b>COP</b>	<b>[-]</b>	<b>3.400</b>	<b>5.169</b>	<b>2.732</b>
Uncertainty of COP	[-]	± 0.057	± 0.075	± 0.044
<b>Control settings</b>	<b>[ ]</b>	<b>-</b>	<b>-</b>	<b>-</b>
Circulation pump settings – heating water	[%]	45	57	40

<sup>(\*)</sup> Comment to abbreviated marking: e.g. A7/W35

A (air) 7 (input air, dry-bulb temperature in °C) / W (water), 35 (output heating water temperature in °C)



**c) Seasonal performance tests and SCOP calculation - Medium temperature application for reference heating seasons**

„A“ = average (reference water temperature 55 °C, reference design conditions for heating T<sub>designh</sub> = -10 °C)  
 „W“ = warmer (reference water temperature 55 °C, reference design conditions for heating T<sub>designh</sub> = +2 °C)  
 „C“ = colder (reference water temperature 55 °C, reference design conditions for heating T<sub>designh</sub> = -22 °C)

Model		Heat pump <b>Airmax<sup>2</sup> 21GT</b>			
Design		Air / Water – monobloc			
Conditions specification according to ČSN EN 14825:2016	Temperature application			<b>Medium</b> (reference water temperature 55 °C)	
	Reference heating season			<b>A, W, C</b>	
	Outlet water temperature - indoor heat exchanger			Variable	
	Compressor speed control			Fixed	
	Water flow rate – primary circuit			-	
	Water flow rate – secondary circuit			Variable	
Seasonal space heating energy efficiency	Heating	Average	$\eta_s / A$	<b>118.8</b>	%
		Warmer	$\eta_s / W$	139.3 (not tested)	%
		Colder	$\eta_s / C$	97.6 (not tested)	%
Seasonal efficiency according to ČSN EN 14825:2016	Heating	Average	<b>SCOP / A</b>	<b>3.04</b>	-
		Warmer	SCOP / W	3.56 (not tested)	-
		Colder	SCOP / C	2.52 (not tested)	-
Function	Cooling				Yes
	Heating	Yes	Reference heating season	Average	Yes
				Warmer (if designated)	Yes
				Colder (if designated)	Yes
Full heating load	Cooling		P <sub>designc</sub>	-	kW
	Heating	Average	P <sub>designh</sub>	<b>14.49</b>	kW
		Warmer	P <sub>designh</sub>	<b>14.63</b>	kW
		Colder	P <sub>designh</sub>	<b>15.13</b>	kW
Bivalent temperatures	Heating	Average	T <sub>bivalent</sub>	-7	°C
		Warmer	T <sub>bivalent</sub>	2	°C
		Colder	T <sub>bivalent</sub>	-10	°C
Operation limit temperatures	Heating	Average	TOL	-20	°C
		Warmer	TOL	-20	°C
		Colder	TOL	-16	°C
Seasonal power consumption according to ČSN EN 14825:2016	Cooling		Q <sub>CE</sub>	-	kWh
	Heating	Average	Q <sub>HE/A</sub>	9834	kWh
		Warmer	Q <sub>HE/W</sub>	5495 (not tested)	kWh
		Colder	Q <sub>HE/C</sub>	14829 (not tested)	kWh
Modes other than „active mode“	Off mode		P <sub>OFF</sub>	9.8	W
	Thermostat off mode		P <sub>TO</sub>	9.7	W
	Standby mode		P <sub>SB</sub>	9.8	W
	Crankcase heater mode		P <sub>CK</sub>	0.0	W

(Not tested): The technical data were declared by the Manufacturer and were not tested by the Testing Laboratory.



### Calculation of SCOP according to ČSN EN 14825:2016:

Number of hours used for calculation of reference SCOP (Annex B – Table B.2, B.3)

- For reversible heat pumps and reference heating season „A“ = average

H <sub>HE</sub>	2066	[h]
H <sub>TO</sub>	178	[h]
H <sub>SB</sub>	0	[h]
H <sub>CK</sub>	178	[h]
H <sub>OFF</sub>	0	[h]

Measured data:

P <sub>TO</sub>	0.0097	[kW]
P <sub>SB</sub>	0.0098	[kW]
P <sub>CK</sub>	0.0000	[kW]
P <sub>OFF</sub>	0.0098	[kW]
P <sub>designh</sub>	14.49	[kW]
SCOP <sub>ON</sub>	3.04	[-]

Coefficient and correction:

F(1)	3	[%]
F(2)	0	[%]
CC	2.5	[-]

#### Calculation of SCOP:

7.3 Calculation of the reference annual heating demand (Q<sub>H</sub>)

$$Q_H = P_{designh} \cdot H_{HE} \quad [kWh]$$

$$Q_H = 14.49 \cdot 2066 = 29938 \quad [kWh]$$

7.4 Calculation of the annual electricity consumption (Q<sub>HE</sub>)

$$Q_{HE} = Q_H / SCOP_{on} + H_{TO} \cdot P_{TO} + H_{SB} \cdot P_{SB} + H_{CK} \cdot P_{CK} + H_{OFF} \cdot P_{OFF} \quad [kWh]$$

$$Q_{HE} = 29938 / 3.04 + 178 \cdot 0.0097 + 0 \cdot 0.0098 + 178 \cdot 0 + 0 \cdot 0.0098 = 9834 \quad [kWh]$$

7.2 General formula for calculation of reference SCOP

$$SCOP = Q_H / Q_{HE} \quad [-]$$

$$SCOP = 29938 / 9834 = 3.04 \quad [-]$$

7.1 Calculation of the seasonal space heating efficiency  $\eta_s$

$$\Sigma F(i) = F(1) + F(2) \quad [-]$$

$$\Sigma F = 0.03 + 0 = 0.03 \quad [-]$$

$$\eta_s = 1 / CC \cdot SCOP - \Sigma F(i) \quad [-]$$

$$\eta_s (A) = (1 / 2.5) \cdot 3.04 - 0.03 = \underline{\underline{1.188}} \quad [-]$$





Data for SCOP calculation (Heat pump **Airmax<sup>2</sup> 21GT**)

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season "A" – average

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (Tj)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]								
<b>A</b>	-7	52.00	88.46	12.82	12.819	2.171	0.900	1.00	2.171	-
<b>B</b>	2	45.69	53.85	7.80	14.468	2.806	0.998	0.54	2.802	0.0097
<b>C</b>	7	42.04	34.62	5.02	20.496	4.060	0.998	0.24	4.036	0.0097
<b>D</b>	12	37.18	15.38	2.23	21.856	5.046	0.998	0.10	4.949	0.0097
<b>TOL (E)</b>	-10	55.00	100.00	14.49	10.932	1.793	0.900	1.33	1.793	-
<b>Tbiv (F)</b>	-7	52.00	88.46	12.82	12.819	2.171	0.900	1.00	2.171	-

**Adaption of water temperature – according to ČSN EN 14825:2016. Annex D**

- Medium temperature application (reference water temperature 55 °C)
- Reference season "A" – average
- Condition D
- Variable water flow rate - secondary circuit

$$t_{\text{outlet, average}} = t_{\text{inlet, capacity test}} + (t_{\text{outlet, capacity test}} - t_{\text{inlet, capacity test}}) \cdot CR_u \quad [^{\circ}\text{C}]$$

$$t_{\text{outlet, average}} = t_{\text{inlet, capacity test}} + (\Delta t) \cdot CR_u \quad [^{\circ}\text{C}]$$

$$t_{\text{outlet, average}} = t_{\text{outlet, capacity test}} - \Delta t + \Delta t \cdot CR_u \quad [^{\circ}\text{C}]$$

$$t_{\text{outlet, capacity test}} = t_{\text{outlet, average}} + \Delta t - \Delta t \cdot CR_u \quad [^{\circ}\text{C}]$$

**For variable flow:**

$$\Delta t = 8$$

$$CR \cdot \Delta t = \text{Part load} / \text{Declared capacity} \cdot 8$$

$$t_{\text{outlet, capacity test, variable flow}} = t_{\text{outlet, average}} + 8 - \text{Part load} / \text{Declared capacity} \cdot 8$$

**Measured data:**

$t_{\text{outlet, average}}$	30.00	[°C]
Declared capacity	21.856	[kW]
Declared capacity standard rating condition A7/W55	-	[kW]
Part load	2.23	[kW]

**Calculation of water temperature:**

$$t_{\text{outlet, capacity test, variable flow}} = 30 + 8 - 2.23 / 21.85 \cdot 8 = \mathbf{37.18} \quad [^{\circ}\text{C}]$$



Calculation SCOP, SCOP<sub>on</sub>, SCOP<sub>net</sub> (Heat pump Airmax<sup>2</sup> 21GT)

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season "A" – average


	Bin	Outdoor temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistive heat elbu(Tj)	Annual resistive heat	COPbin (Tj)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating
	j	T <sub>j</sub>	h <sub>j</sub>		P <sub>h(Tj)</sub>			elbu <sub>(Tj)</sub>	h <sub>j</sub> × elbu <sub>(Tj)</sub>		h <sub>j</sub> × P <sub>h(Tj)</sub>		h <sub>j</sub> × (P <sub>h(Tj)</sub> - elbu <sub>(Tj)</sub> )	
	[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]
<b>TOL(E)</b>	<b>21</b>	<b>-10</b>	<b>1</b>	<b>100.00</b>	<b>14.49</b>	<b>10.93</b>	<b>10.93</b>	<b>3.56</b>	<b>3.56</b>	<b>1.79</b>	<b>14</b>	<b>10</b>	<b>11</b>	<b>6</b>
	22	-9	25	96.15	13.93	11.56	11.56	2.37	59.31	1.92	348	210	289	151
	23	-8	23	92.31	13.38	12.19	12.19	1.19	27.28	2.05	308	164	280	137
<b>A, T<sub>biv(F)</sub></b>	<b>24</b>	<b>-7</b>	<b>24</b>	<b>88.46</b>	<b>12.82</b>	<b>12.82</b>	<b>12.82</b>	<b>0.00</b>	<b>0.00</b>	<b>2.17</b>	<b>308</b>	<b>142</b>	<b>308</b>	<b>142</b>
	25	-6	27	84.62	12.26	13.00	12.26	0.00	0.00	2.24	331	148	331	148
	26	-5	68	80.77	11.70	13.19	11.70	0.00	0.00	2.31	796	344	796	344
	27	-4	91	76.92	11.15	13.37	11.15	0.00	0.00	2.38	1014	426	1014	426
	28	-3	89	73.08	10.59	13.55	10.59	0.00	0.00	2.45	942	384	942	384
	29	-2	165	69.23	10.03	13.74	10.03	0.00	0.00	2.52	1655	656	1655	656
	30	-1	173	65.38	9.47	13.92	9.47	0.00	0.00	2.59	1639	633	1639	633
	31	0	240	61.54	8.92	14.10	8.92	0.00	0.00	2.66	2140	804	2140	804
	32	1	280	57.69	8.36	14.28	8.36	0.00	0.00	2.73	2341	857	2341	857
<b>B</b>	<b>33</b>	<b>2</b>	<b>320</b>	<b>53.85</b>	<b>7.80</b>	<b>14.47</b>	<b>7.80</b>	<b>0.00</b>	<b>0.00</b>	<b>2.80</b>	<b>2497</b>	<b>891</b>	<b>2497</b>	<b>891</b>
	34	3	357	50.00	7.25	15.67	7.25	0.00	0.00	3.05	2587	849	2587	849
	35	4	356	46.15	6.69	16.88	6.69	0.00	0.00	3.30	2381	723	2381	723
	36	5	303	42.31	6.13	18.08	6.13	0.00	0.00	3.54	1858	524	1858	524
	37	6	330	38.46	5.57	19.29	5.57	0.00	0.00	3.79	1839	485	1839	485
<b>C</b>	<b>38</b>	<b>7</b>	<b>326</b>	<b>34.62</b>	<b>5.02</b>	<b>20.50</b>	<b>5.02</b>	<b>0.00</b>	<b>0.00</b>	<b>4.04</b>	<b>1635</b>	<b>405</b>	<b>1635</b>	<b>405</b>
	39	8	348	30.77	4.46	20.77	4.46	0.00	0.00	4.22	1552	368	1552	368
	40	9	335	26.92	3.90	21.04	3.90	0.00	0.00	4.40	1307	297	1307	297
	41	10	315	23.08	3.34	21.31	3.34	0.00	0.00	4.58	1053	230	1053	230
	42	11	215	19.23	2.79	21.58	2.79	0.00	0.00	4.77	599	126	599	126
<b>D</b>	<b>43</b>	<b>12</b>	<b>169</b>	<b>15.38</b>	<b>2.23</b>	<b>21.86</b>	<b>2.23</b>	<b>0.00</b>	<b>0.00</b>	<b>4.95</b>	<b>377</b>	<b>76</b>	<b>377</b>	<b>76</b>
	44	13	151	11.54	1.67	22.13	1.67	0.00	0.00	5.13	252	49	252	49
	45	14	105	7.69	1.11	22.40	1.11	0.00	0.00	5.31	117	22	117	22
	46	15	74	3.85	0.56	22.67	0.56	0.00	0.00	5.50	41	8	41	8
	Σ		4910							Σ	29933	9831	29842	9740

SCOP <sub>on</sub>	3.04	SCOP <sub>net</sub>	3.06
<b>SCOP</b>		<b>3.04</b>	



Power diagram - Heat pump **Airmax<sup>2</sup> 21GT**

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season "A" – average





Test results for single part load conditions (Heat pump **Airmax<sup>2</sup> 21GT**)

**Measurement results:**

Test number		12	13	14
Temperature level		Medium temperature application (reference water temperature 55 °C)		
Reference heating season		"A" = average ( $T_{\text{designh}} = -10$ °C)		
Assessment condition		<b>A, T<sub>biv</sub> (F)**</b>	<b>B**</b>	<b>C</b>
Specification of the assessment condition <sup>(*)</sup>		<b>A-7/W52</b>	<b>A2/W45.69</b>	<b>A7/W42.04</b>
Date of testing		<b>2017-11-27</b>	<b>2017-12-12</b>	<b>2017-12-13</b>
Transient test procedure	YES / NO	YES	YES	NO
Average defrost time of 1 cycle	[min]	4.7	4.4	-
Average time of 1 cycle	[min]	98.4	47.2	-
Calculation time	[min]	98.4	141.7	70.0
Output heating water – temperature calculation	[°C]	50.86	43.99	41.97
Input heating water – temperature calculation	[°C]	43.87	37.44	33.98
Output heating water temperature	[°C]	51.83	45.59	41.97
Input heating water temperature	[°C]	43.98	37.67	33.98
Air temperature - dry bulb temperature	[°C]	-7.01	1.98	7.01
Air temperature - wet bulb temperature	[°C]	-8.01	1.00	6.02
Relative humidity	[%]	75.00	84.24	87.03
Barometric pressure	[kPa]	98.968	97.468	97.877
Ambient temperature	[°C]	-7.01	1.98	7.01
Secondary circuit pressure difference	[kPa]	3.233	3.991	5.591
Efficiency of the secondary liquid pump	[-]	0.080	0.091	0.107
Volume flow rate of heating water	[m <sup>3</sup> ·h <sup>-1</sup> ]	1.5679	1.8727	2.2354
Density of heating water	[kg·m <sup>-3</sup> ]	987.6	990.6	991.4
Specific heat capacity of heating water	[kJ·kg <sup>-1</sup> ·K <sup>-1</sup> ]	4.180	4.180	4.173
Voltage	[V]	398.37	398.82	399.70
Total current	[A]	33.58	30.92	30.63
Overall power input	[kW]	5.921	5.178	5.081
Partial power input of secondary liquid pump	[W]	17.14	22.45	32.40
Heating capacity - heating water	[kW]	12.836	14.490	20.528
<b>Corrected heating capacity - heating water</b>	<b>[kW]</b>	<b>12.819</b>	<b>14.468</b>	<b>20.496</b>
Uncertainty of corrected heating capacity	[kW]	± 0.129	± 0.154	± 0.185
<b>Effective electric power input</b>	<b>[kW]</b>	<b>5.904</b>	<b>5.156</b>	<b>5.048</b>
<b>COP</b>	<b>[-]</b>	<b>2.171</b>	<b>2.806</b>	<b>4.060</b>
Uncertainty of COP	[-]	± 0.022	± 0.030	± 0.037
<b>Control settings</b>	<b>[ ]</b>	-	-	-
Circulation pump settings – heating water	[%]	30	33	42

<sup>(\*)</sup> Comment to abbreviated marking: e.g. A7/W35

A (air) 7 (input air, dry-bulb temperature in °C) / W (water), 35 (output heating water temperature in °C)

<sup>(\*\*)</sup> Because of high capacity decreases actual values are not in tolerances given by standard.



Test results for single part load conditions (Heat pump Airmax<sup>2</sup> 21GT)

**Measurement results:**

Test number		15	16
Temperature level		Medium temperature application (reference water temperature 55 °C)	
Reference heating season		"A" = average ( $T_{\text{designh}} = -10$ °C)	
Assessment condition		D	TOL (E)**
Specification of the assessment condition <sup>(*)</sup>		A12/W37.18	A-10/W55
Date of testing		2017-12-11	2017-12-08
Transient test procedure	YES / NO	NO	YES
Average defrost time of 1 cycle	[min]	-	4.9
Average time of 1 cycle	[min]	-	-
Calculation time	[min]	70.0	180.0
Output heating water – temperature calculation	[°C]	36.91	54.49
Input heating water – temperature calculation	[°C]	29.00	46.92
Output heating water temperature	[°C]	36.91	55.01
Input heating water temperature	[°C]	29.00	46.99
Air temperature - dry bulb temperature	[°C]	12.00	-10.00
Air temperature - wet bulb temperature	[°C]	10.67	-11.04
Relative humidity	[%]	85.54	69.00
Barometric pressure	[kPa]	96.146	97.798
Ambient temperature	[°C]	12.00	-10.00
Secondary circuit pressure difference	[kPa]	6.099	2.456
Efficiency of the secondary liquid pump	[-]	0.113	0.069
Volume flow rate of heating water	[m <sup>3</sup> ·h <sup>-1</sup> ]	2.4019	1.2548
Density of heating water	[kg·m <sup>-3</sup> ]	993.3	986.0
Specific heat capacity of heating water	[kJ·kg <sup>-1</sup> ·K <sup>-1</sup> ]	4.180	4.180
Voltage	[V]	399.67	398.89
Total current	[A]	28.36	34.25
Overall power input	[kW]	4.367	6.108
Partial power input of secondary liquid pump	[W]	36.10	12.28
Heating capacity - heating water	[kW]	21.892	10.945
<b>Corrected heating capacity - heating water</b>	<b>[kW]</b>	<b>21.856</b>	<b>10.932</b>
Uncertainty of corrected heating capacity	[kW]	± 0.199	± 0.103
<b>Effective electric power input</b>	<b>[kW]</b>	<b>4.331</b>	<b>6.096</b>
<b>COP</b>	<b>[-]</b>	<b>5.046</b>	<b>1.793</b>
Uncertainty of COP	[-]	± 0.046	± 0.017
<b>Control settings</b>	<b>[ ]</b>	-	-
Circulation pump settings – heating water	[%]	43	25

<sup>(\*)</sup> Comment to abbreviated marking: e.g. A7/W35

A (air) 7 (input air, dry-bulb temperature in °C) / W (water), 35 (output heating water temperature in °C)

<sup>(\*\*)</sup> Because of high capacity decreases actual values are not in tolerances given by standard.



Test results for single part load conditions (Heat pump Airmax<sup>2</sup> 21GT)

**Measurement results:**

Test number		17	18	19
Temperature level		Medium temperature application (reference water temperature 55 °C)		
Reference heating season		"W" = warmer (T <sub>designh</sub> = +2 °C)	"C" = colder (T <sub>designh</sub> = -22 °C)	
Assessment condition		B, TOL (E), Tbiv (F)**	C	Tbiv (F)**
Specification of the assessment condition <sup>(*)</sup>		A2/W55	A7/W38.61	A-10/W45.88
Date of testing		2017-12-12	2017-12-15	2017-12-13
Transient test procedure	YES / NO	YES	NO	ANO
Average defrost time of 1 cycle	[min]	5.0	-	3.9
Average time of 1 cycle	[min]	62.2	-	48.0
Calculation time	[min]	124.4	70.0	144.0
Output heating water – temperature calculation	[°C]	53.52	38.56	44.14
Input heating water – temperature calculation	[°C]	46.73	30.58	37.39
Output heating water temperature	[°C]	55.03	38.56	45.85
Input heating water temperature	[°C]	46.98	30.58	37.81
Air temperature - dry bulb temperature	[°C]	2.00	7.00	-10.01
Air temperature - wet bulb temperature	[°C]	1.02	6.01	-11.01
Relative humidity	[%]	84.24	87.12	69.87
Barometric pressure	[kPa]	97.952	96.634	98.287
Ambient temperature	[°C]	2.00	7.00	-10.01
Secondary circuit pressure difference	[kPa]	4.557	5.070	1.901
Efficiency of the secondary liquid pump	[-]	0.094	0.104	0.064
Volume flow rate of heating water	[m <sup>3</sup> ·h <sup>-1</sup> ]	1.8279	2.2401	1.3320
Density of heating water	[kg·m <sup>-3</sup> ]	986.4	992.7	990.5
Specific heat capacity of heating water	[kJ·kg <sup>-1</sup> ·K <sup>-1</sup> ]	4.180	4.180	4.180
Voltage	[V]	398.80	399.79	399.79
Total current	[A]	34.82	29.52	30.35
Overall power input	[kW]	6.272	4.731	4.988
Partial power input of secondary liquid pump	[W]	24.07	30.36	10.90
Heating capacity - heating water	[kW]	14.658	20.595	10.364
<b>Corrected heating capacity - heating water</b>	<b>[kW]</b>	<b>14.634</b>	<b>20.565</b>	<b>10.354</b>
Uncertainty of corrected heating capacity	[kW]	± 0.150	± 0.186	± 0.110
<b>Effective electric power input</b>	<b>[kW]</b>	<b>6.248</b>	<b>4.701</b>	<b>4.977</b>
<b>COP</b>	<b>[-]</b>	<b>2.342</b>	<b>4.374</b>	<b>2.080</b>
Uncertainty of COP	[-]	± 0.024	± 0.040	± 0.022
<b>Control settings</b>	<b>[ ]</b>	-	-	-
Circulation pump settings – heating water	[%]	33	40	25

<sup>(\*)</sup> Comment to abbreviated marking: e.g. A7/W35

A (air) 7 (input air, dry-bulb temperature in °C) / W (water), 35 (output heating water temperature in °C)

<sup>(\*\*)</sup> Because of high capacity decreases actual values are not in tolerances given by standard.



Accredited test number: **T 037\*** Test title: **Tests of leakage, pressure resistance, thermal and technical parameters, combustion efficiency, safety functions**


Testing method: **ČSN EN 14511-4:2014 Art. 4.2, 4.3, 4.4, 4.5, 4.6, 4.7; EHPA Testing regulation – Testing of Air/Water Heat Pumps, ver. 2.3**

Sample tested: **Heat pump Airmax<sup>2</sup> 21GT**

Measuring equipment used: **See chapter III.**

Place of testing:	at the Engineering Test Institute <input checked="" type="checkbox"/>	at the Manufacturer's premises <input type="checkbox"/>	at the Customer's premises <input type="checkbox"/>	other: <input type="checkbox"/>
-------------------	---	---	---	---------------------------------

### 1) Temperature operating range



Heat pump air/water, heating	Input air dry bulb temperature [°C]		Output heating water temperature [°C]		Water flow rate in condenser [m <sup>3</sup> /h]	Note
1.	A	35	W	60	Maximum	Minimum water flow rate: <b>1.255 m<sup>3</sup>·h<sup>-1</sup></b> Maximum water flow rate: <b>4.500 m<sup>3</sup>·h<sup>-1</sup></b>
2.	A	-20	W	25	Minimum	
3.	A	-20	W	50	Maximum	

Heat pump **Airmax<sup>2</sup> 21GT** is fully operational in the temperature operating range.





### Starting test

Test according to Article 4.2.1 of ČSN EN 14511-4:2014

Operational requirements conditions					
Type	Inlet temperature at outdoor heat exchanger (°C)	Outlet temperature at indoor heat exchanger (°C)	Water flow rate or brine-to-water and water-to-water units	Voltage (V)	Test result
All types	Upper limit of use	Upper limit of use	maximum	Rated voltage	+
All types	Lower limit of use	Lower limit of use	minimum	Rated voltage	+

Evaluation: +... The unit has started and has been operating for at least 30 min (the lower limit of use) and has been operating for at least 60 min (the upper limit of use), without breaking off by protective devices.  
 -... The unit did not fulfill test requirements.  
 0... The requirement does not apply to the product concerned.  
 x... Test was not required.

### 2) Test at maximum operating conditions (cooling mode)

Test according to Article 4.2.2 of ČSN EN 14511-4:2014

Maximum operating conditions				
Type	Inlet temperature at outdoor heat exchanger (°C)	Outlet temperature at indoor heat exchanger (°C)	Voltage (V)	Test result
Control cabinet air conditioner	Upper limit of use	35	Rated voltage	0
All other types	Upper limit of use	Upper limit of use	Rated voltage	x

Evaluation: +... The unit has not been damaged; the motor operates without interruption for the first hour without tripping of the motor overload protective devices; after the shut-down period of 5 min. the unit shall restart automatically no more than 5 min. after restarting of the compressor; the unit motor shall operate again continuously for the rest of the second hour without tripping of the motor overload protective devices.  
 -... The unit did not fulfill test requirements.  
 0... The requirement does not apply to the product concerned.  
 x... Test was not required.

### 3) Freeze-up test

#### Air-cooled unit

Required operating conditions	Test result	Note
Test according to Article 4.2.3.1 ČSN EN 14511-4:2014	0	

Evaluation: +... After the unit has been operated for 6 hours and after the last freeze up cycle has been completed. the following requirements shall be fulfilled:  
 - no ice shall have accumulated on the evaporator;  
 - no ice shall drip from the unit;  
 - no water shall drip or be blown off the unit into the room.  
 -... The unit did not fulfill test requirements.  
 0... The requirement does not apply to the product concerned.  
 x... Test was not required.



#### Water-cooled units

Required operating conditions	Test result	Note
Test according to Article 4.2.3.2 ČSN EN 14511-4:2014	x	

Evaluation: +... After the unit has been operated for 6 hours, the following requirements shall be fulfilled:  
 - air flow through the unit shall not have dropped by more than 5 %;  
 - the water temperature difference through the unit shall not have dropped by more than 30 %;  
 - the saturated temperature corresponding to the pressure measured at the suction of the compressor shall not have decreased by more than 2 K.  
 -... The unit did not fulfill test requirements.  
 0... The requirement does not apply to the product concerned.  
 x... Test was not required.

#### 4) Outside the operating range

Requirements for outside the operating range	Requirement specification	Test result	Note
If operating outside the temperature range can cause damage to the unit, it shall be provided with safety devices which ensure that the unit suffers no damage when the operating limits of use indicated by the manufacturer are exceeded and remains capable of operating when coming back within these limits. A safety device that does not automatically reset may trip provided that a warning device is fitted. The manufacturer shall indicate any safety devices provided and their operating conditions according to 7.2.3.	ČSN EN 14511-4:2014 Art. 4.3	+	Pressure safety contact device

#### 5) Shutting off the heat transfer medium flows

Required operating conditions	Test result	Note
Test for section a) Art. 4.4 ČSN EN 14511-4:2014	+	Frequent defrosting
Test for section b) Art. 4.4 ČSN EN 14511-4:2014	+	Flow switch
Test for section c) Art. 4.4 ČSN EN 14511-4:2014	0	
Test according to the table 4 Art. 4.4. ČSN EN 14511-4:2014	+	Flow switch

Evaluation: +... The unit shall suffer no damage and shall remain capable of operating after restoration of the flow rates.  
 -... The unit did not fulfill test requirements.  
 0... The requirement does not apply to the product concerned.  
 x... Test was not required.

#### 6) Complete power supply failure

Required operating conditions	Test result	Note
Test according to Article 4.5 of ČSN EN 14511-4:2014	+	

Evaluation: +... The unit has to restart automatically within 30 min. When manufacturer states that the unit does not automatically restart, fault detection is necessary. The unit is checked for any damage sustained during the test and if any safety devices have operated during the test.  
 -... The unit did not fulfill test requirements.  
 0... The requirement does not apply to the product concerned.  
 x... Test was not required.



### 7) Condensate draining and enclosure sweat test

Required operating conditions	Test result	Note
Test according to Article 4.6 of ČSN EN 14511-4:2014	+	Bottom free drain
Evaluation: +...	During the test of 4 hours no condensed water shall drip, run or blow off the unit except through the drain. For indoor units, drain holes shall be provided with suitable pipe connection, the minimum diameter of which shall be 12 mm.	
-...	The unit did not fulfill test requirements.	
0...	The requirement does not apply to the product concerned.	
x...	Test was not required.	

### 8) Defrosting

Required operating conditions	Test result	Note
Test according to Article 4.7 of ČSN EN 14511-4:2014	+	
Evaluation: +...	At least three successive frosting/defrosting cycles shall be repeated without running in progressively deteriorating average performances. There shall not be growth of ice in and around the drip tray.	
-...	The unit did not fulfill test requirements.	
0...	The requirement does not apply to the product concerned.	
x...	Test was not required.	



## V. Test results – Out of accredited tests

### SCOP calculations – based on values provided by the customer

Testing method: **ČSN EN 14511-2+4:2014;**  
**ČSN EN 14825:2016;**  
**EHPA Testing regulation** – Testing of Air/Water Heat Pumps,  
version 2.3.

Sample tested: **Heat pump Airmax<sup>2</sup> 21GT**

- a) **SCOP calculation** – Low temperature application (reference water temperature 35 °C)  
– Reference heating season “W” – warmer

Data for SCOP calculation (Heat pump Airmax<sup>2</sup> 21GT)

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (Tj)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]								
<b>A</b>	-	-	-	-	-	-	-	-	-	-
<b>B</b>	2	35.00	100.00	14.27	14.275	3.400	0.900	1.00	3.400	-
<b>C</b>	7	33.82	64.29	9.18	21.000	4.790	0.998	0.42	4.775	0.0100
<b>D</b>	12	30.09	28.57	4.08	22.410	5.430	0.998	0.18	5.372	0.0100
<b>TOL (E)</b>	2	35.00	100.00	14.27	14.275	3.400	0.900	1.00	3.400	-
<b>Tbiv (F)</b>	2	35.00	100.00	14.27	14.275	3.400	0.900	1.00	3.400	-



Calculation SCOP, SCOP<sub>on</sub>, SCOP<sub>net</sub> (Heat pump **Airmax<sup>2</sup> 21GT**)

- Low temperature application (reference water temperature 35 °C)
- Reference heating season "W" – warmer


Bin	Outdoor temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistive heat elbu (Tj)	Annual resistive heat	COPbin (Tj)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating
j	T <sub>j</sub>	h <sub>j</sub>		P <sub>h(Tj)</sub>			elbu <sub>(Tj)</sub>	h <sub>j</sub> × elbu <sub>(Tj)</sub>		h <sub>j</sub> × P <sub>h(Tj)</sub>		h <sub>j</sub> × (P <sub>h(Tj)</sub> - elbu <sub>(Tj)</sub> )	
[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]
<b>B, TOL (E), Tbiv (F)</b>	<b>33</b>	<b>2</b>	<b>3</b>	<b>100.00</b>	<b>14.27</b>	<b>14.27</b>	<b>14.27</b>	<b>0.00</b>	<b>0.00</b>	<b>3.40</b>	<b>43</b>	<b>13</b>	<b>13</b>
	34	3	22	92.86	13.26	15.62	13.26	0.00	0.00	3.68	292	79	292
	35	4	63	85.71	12.24	16.96	12.24	0.00	0.00	3.95	771	195	771
	36	5	63	78.57	11.22	18.31	11.22	0.00	0.00	4.23	707	167	707
	37	6	175	71.43	10.20	19.65	10.20	0.00	0.00	4.50	1784	396	1784
<b>C</b>	<b>38</b>	<b>7</b>	<b>162</b>	<b>64.29</b>	<b>9.18</b>	<b>21.00</b>	<b>9.18</b>	<b>0.00</b>	<b>0.00</b>	<b>4.78</b>	<b>1487</b>	<b>311</b>	<b>1487</b>
	39	8	259	57.14	8.16	21.28	8.16	0.00	0.00	4.90	2113	432	2113
	40	9	360	50.00	7.14	21.56	7.14	0.00	0.00	5.01	2569	512	2569
	41	10	428	42.86	6.12	21.85	6.12	0.00	0.00	5.13	2618	510	2618
	42	11	430	35.71	5.10	22.13	5.10	0.00	0.00	5.25	2192	417	2192
<b>D</b>	<b>43</b>	<b>12</b>	<b>503</b>	<b>28.57</b>	<b>4.08</b>	<b>22.41</b>	<b>4.08</b>	<b>0.00</b>	<b>0.00</b>	<b>5.37</b>	<b>2051</b>	<b>382</b>	<b>2051</b>
	44	13	444	21.43	3.06	22.69	3.06	0.00	0.00	5.49	1358	247	1358
	45	14	384	14.29	2.04	22.97	2.04	0.00	0.00	5.61	783	140	783
	46	15	294	7.14	1.02	23.26	1.02	0.00	0.00	5.73	300	52	300
	Σ	3590								Σ	19068	3855	19068

SCOP <sub>on</sub>	4.95	SCOP <sub>net</sub>	4.95
		<b>SCOP</b>	<b>4.94</b>



Power diagram - Heat pump Airmax<sup>2</sup> 21GT

- Low temperature application (reference water temperature 35 °C)
- Reference heating season "W" – warmer





- b) **SCOP calculation** – Low temperature application (reference water temperature 35 °C)  
– Reference heating season “C” – colder

Data for SCOP calculation (Heat pump **Airmax<sup>2</sup> 21GT**)

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (T)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]								
<b>A</b>	-7	31.20	60.53	9.43	12.400	3.010	0.998	0.76	3.008	0.0100
<b>B</b>	2	30.09	36.84	5.74	15.050	3.810	0.997	0.38	3.794	0.0100
<b>C</b>	7	29.08	23.68	3.69	20.029	5.169	0.997	0.18	5.110	0.0100
<b>D</b>	12	28.63	10.53	1.64	22.320	5.820	0.997	0.07	5.635	0.0100
<b>TOL (E)</b>	-20	34.14	94.74	14.76	10.500	1.950	0.900	1.41	1.950	-
<b>Tbiv (F)</b>	-10	30.75	68.42	10.66	10.658	2.732	0.900	1.00	2.732	-
<b>G</b>	-15	32.00	81.58	12.71	10.579	2.341	0.900	1.20	2.341	-





Calculation SCOP, SCOP<sub>on</sub>, SCOP<sub>net</sub> (Heat pump Airmax<sup>2</sup> 21GT)  
 - Low temperature application (reference water temperature 35 °C)  
 - Reference heating season "C" – colder

Bin	Outdo or temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistiv e heat elbu(Tj)	Annual resistive heat	COPbin( Tj)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating	
j	T <sub>j</sub>	h <sub>j</sub>		P <sub>h(Tj)</sub>			elbu(Tj)	h <sub>j</sub> × elbu(Tj)		h <sub>j</sub> × P <sub>h(Tj)</sub>		h <sub>j</sub> × (P <sub>h(Tj)</sub> - elbu(Tj))		
[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]	
	9	-22	1	100.00	15.58	0.00	0.00	15.58	15.58	1.00	16	16	0	0
	10	-21	6	97.37	15.17	0.00	0.00	15.17	91.01	1.00	91	91	0	0
<b>TOL (E)</b>	<b>11</b>	<b>-20</b>	<b>13</b>	<b>94.74</b>	<b>14.76</b>	<b>10.50</b>	<b>10.50</b>	<b>4.26</b>	<b>55.35</b>	<b>1.95</b>	<b>192</b>	<b>125</b>	<b>137</b>	<b>70</b>
	12	-19	17	92.11	14.35	10.52	10.52	3.83	65.14	2.03	244	153	179	88
	13	-18	19	89.47	13.94	10.53	10.53	3.41	64.72	2.11	265	160	200	95
	14	-17	26	86.84	13.53	10.55	10.55	2.98	77.49	2.18	352	203	274	126
	15	-16	39	84.21	13.12	10.56	10.56	2.55	99.63	2.26	512	282	412	182
<b>G</b>	<b>16</b>	<b>-15</b>	<b>41</b>	<b>81.58</b>	<b>12.71</b>	<b>10.58</b>	<b>10.58</b>	<b>2.13</b>	<b>87.29</b>	<b>2.34</b>	<b>521</b>	<b>273</b>	<b>434</b>	<b>185</b>
	17	-14	35	78.95	12.30	10.60	10.60	1.70	59.61	2.42	430	213	371	153
	18	-13	52	76.32	11.89	10.61	10.61	1.28	66.42	2.50	618	287	552	221
	19	-12	37	73.68	11.48	10.63	10.63	0.85	31.51	2.58	425	184	393	153
	20	-11	41	71.05	11.07	10.64	10.64	0.43	17.46	2.65	454	182	436	164
<b>Tbiv(F)</b>	<b>21</b>	<b>-10</b>	<b>43</b>	<b>68.42</b>	<b>10.66</b>	<b>10.66</b>	<b>10.66</b>	<b>0.00</b>	<b>0.00</b>	<b>2.73</b>	<b>458</b>	<b>168</b>	<b>458</b>	<b>168</b>
	22	-9	54	65.79	10.25	11.24	10.25	0.00	0.00	2.82	553	196	553	196
	23	-8	90	63.16	9.84	11.82	9.84	0.00	0.00	2.92	885	304	885	304
<b>A</b>	<b>24</b>	<b>-7</b>	<b>125</b>	<b>60.53</b>	<b>9.43</b>	<b>12.40</b>	<b>9.43</b>	<b>0.00</b>	<b>0.00</b>	<b>3.01</b>	<b>1179</b>	<b>392</b>	<b>1179</b>	<b>392</b>
	25	-6	169	57.89	9.02	12.69	9.02	0.00	0.00	3.10	1524	492	1524	492
	26	-5	195	55.26	8.61	12.99	8.61	0.00	0.00	3.18	1679	527	1679	527
	27	-4	278	52.63	8.20	13.28	8.20	0.00	0.00	3.27	2279	697	2279	697
	28	-3	306	50.00	7.79	13.58	7.79	0.00	0.00	3.36	2383	710	2383	710
	29	-2	454	47.37	7.38	13.87	7.38	0.00	0.00	3.44	3350	972	3350	972
	30	-1	385	44.74	6.97	14.17	6.97	0.00	0.00	3.53	2683	760	2683	760
	31	0	490	42.11	6.56	14.46	6.56	0.00	0.00	3.62	3214	888	3214	888
	32	1	533	39.47	6.15	14.76	6.15	0.00	0.00	3.71	3277	884	3277	884
<b>B</b>	<b>33</b>	<b>2</b>	<b>380</b>	<b>36.84</b>	<b>5.74</b>	<b>15.05</b>	<b>5.74</b>	<b>0.00</b>	<b>0.00</b>	<b>3.79</b>	<b>2181</b>	<b>575</b>	<b>2181</b>	<b>575</b>
	34	3	228	34.21	5.33	16.05	5.33	0.00	0.00	4.06	1215	299	1215	299
	35	4	261	31.58	4.92	17.04	4.92	0.00	0.00	4.32	1284	297	1284	297
	36	5	279	28.95	4.51	18.04	4.51	0.00	0.00	4.58	1258	274	1258	274
	37	6	229	26.32	4.10	19.03	4.10	0.00	0.00	4.85	939	194	939	194
<b>C</b>	<b>38</b>	<b>7</b>	<b>269</b>	<b>23.68</b>	<b>3.69</b>	<b>20.03</b>	<b>3.69</b>	<b>0.00</b>	<b>0.00</b>	<b>5.11</b>	<b>992</b>	<b>194</b>	<b>992</b>	<b>194</b>
	39	8	233	21.05	3.28	20.49	3.28	0.00	0.00	5.22	764	147	764	147
	40	9	230	18.42	2.87	20.95	2.87	0.00	0.00	5.32	660	124	660	124
	41	10	243	15.79	2.46	21.40	2.46	0.00	0.00	5.43	598	110	598	110




	42	11	191	13.16	2.05	21.86	2.05	0.00	0.00	5.53	391	71	391	71
D	43	12	146	10.53	1.64	22.32	1.64	0.00	0.00	5.63	239	42	239	42
	44	13	150	7.89	1.23	22.78	1.23	0.00	0.00	5.74	184	32	184	32
	45	14	97	5.26	0.82	23.24	0.82	0.00	0.00	5.84	80	14	80	14
	46	15	61	2.63	0.41	23.69	0.41	0.00	0.00	5.95	25	4	25	4
	Σ		6446							Σ	38395	11537	37664	10805

SCOPon	3.33	SCOPnet	3.49
<b>SCOP</b>		<b>3.33</b>	

Power diagram - Heat pump **Airmax<sup>2</sup> 21GT**

- Low temperature application (reference water temperature 35 °C)
- Reference heating season "C" – colder





- c) **SCOP calculation** – Medium temperature application (reference water temperature 55 °C)  
– Reference heating season “W” – warmer

Data for SCOP calculation (Heat pump **Airmax<sup>2</sup> 21GT**)

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (Tj)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]								
<b>A</b>	-	-	-	-	-	-	-	-	-	-
<b>B</b>	2	55.00	100.00	14.63	14.634	2.342	0.900	1.00	2.342	-
<b>C</b>	7	50.47	64.29	9.41	21.300	3.100	0.999	0.44	3.094	0.0097
<b>D</b>	12	40.51	28.57	4.18	22.500	4.320	0.998	0.19	4.285	0.0097
<b>TOL (E)</b>	2	55.00	100.00	14.63	14.634	2.342	0.900	1.00	2.342	-
<b>Tbiv (F)</b>	2	55.00	100.00	14.63	14.634	2.342	0.900	1.00	2.342	-



Calculation SCOP, SCOP<sub>on</sub>, SCOP<sub>net</sub> (Heat pump Airmax<sup>2</sup> 21GT)

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season "W" – warmer


	Bin	Outdo or temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistiv e heat elbu(T <sub>j</sub> )	Annual resistive heat	COPbin( T <sub>j</sub> )	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating
	j	T <sub>j</sub>	h <sub>j</sub>		P <sub>h(T<sub>j</sub>)</sub>			elbu(T <sub>j</sub> )	h <sub>j</sub> × elbu(T <sub>j</sub> )		h <sub>j</sub> × P <sub>h(T<sub>j</sub>)</sub>		h <sub>j</sub> × (P <sub>h(T<sub>j</sub>)</sub> - elbu(T <sub>j</sub> ))	
	[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]
<b>B, TOL (E), Tbiv (F)</b>	<b>33</b>	<b>2</b>	<b>3</b>	<b>100.00</b>	<b>14.63</b>	<b>14.63</b>	<b>14.63</b>	<b>0.00</b>	<b>0.00</b>	<b>2.34</b>	<b>44</b>	<b>19</b>	<b>44</b>	<b>19</b>
	34	3	22	92.86	13.59	15.97	13.59	0.00	0.00	2.49	299	120	299	120
	35	4	63	85.71	12.54	17.30	12.54	0.00	0.00	2.64	790	299	790	299
	36	5	63	78.57	11.50	18.63	11.50	0.00	0.00	2.79	724	259	724	259
	37	6	175	71.43	10.45	19.97	10.45	0.00	0.00	2.94	1829	621	1829	621
<b>C</b>	<b>38</b>	<b>7</b>	<b>162</b>	<b>64.29</b>	<b>9.41</b>	<b>21.30</b>	<b>9.41</b>	<b>0.00</b>	<b>0.00</b>	<b>3.09</b>	<b>1524</b>	<b>492</b>	<b>1524</b>	<b>492</b>
	39	8	259	57.14	8.36	21.54	8.36	0.00	0.00	3.33	2166	650	2166	650
	40	9	360	50.00	7.32	21.78	7.32	0.00	0.00	3.57	2634	738	2634	738
	41	10	428	42.86	6.27	22.02	6.27	0.00	0.00	3.81	2684	705	2684	705
	42	11	430	35.71	5.23	22.26	5.23	0.00	0.00	4.05	2247	555	2247	555
<b>D</b>	<b>43</b>	<b>12</b>	<b>503</b>	<b>28.57</b>	<b>4.18</b>	<b>22.50</b>	<b>4.18</b>	<b>0.00</b>	<b>0.00</b>	<b>4.29</b>	<b>2103</b>	<b>491</b>	<b>2103</b>	<b>491</b>
	44	13	444	21.43	3.14	22.74	3.14	0.00	0.00	4.52	1392	308	1392	308
	45	14	384	14.29	2.09	22.98	2.09	0.00	0.00	4.76	803	169	803	169
	46	15	294	7.14	1.05	23.22	1.05	0.00	0.00	5.00	307	61	307	61
	Σ		3590							Σ	19548	5487	19548	5487

SCOP <sub>on</sub>	3.56	SCOP <sub>net</sub>	3.56
		<b>SCOP</b>	<b>3.56</b>



Power diagram - Heat pump **Airmax<sup>2</sup> 21GT**

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season "W" – warmer





d) **SCOP calculation** – Medium temperature application (reference water temperature 55 °C)  
– Reference heating season “C” – colder

Data for SCOP calculation (Heat pump **Airmax<sup>2</sup> 21GT**)

	Outdoor heat exchanger	Indoor heat exchanger	Part load ratio	Part load	DC Declared capacity	COPd at declared capacity	Cdh degradation coefficient	CR	COPbin (Tj)	Eff. power input of compressor off state
	Outdoor air inlet	Outlet water temperature								
	[°C]	[°C]	[%]	[kW]	[kW]	[-]	[-]	[-]	[-]	[kW]
<b>A</b>	-7	46.33	60.53	9.16	12.920	2.190	0.998	0.71	2.189	0.0097
<b>B</b>	2	41.92	36.84	5.58	14.480	2.890	0.998	0.39	2.881	0.0097
<b>C</b>	7	38.61	23.68	3.58	20.565	4.374	0.998	0.17	4.332	0.0097
<b>D</b>	12	35.42	10.53	1.59	21.900	5.150	0.998	0.07	5.004	0.0097
<b>TOL (E)</b>	-16	49.86	84.21	12.74	11.500	1.500	0.900	1.11	1.500	-
<b>Tbiv (F)</b>	-10	45.88	68.42	10.35	10.354	2.080	0.900	1.00	2.080	-
<b>G</b>	-15	49.00	81.58	12.34	11.309	1.597	0.900	1.09	1.597	-



Calculation SCOP, SCOP<sub>on</sub>, SCOP<sub>net</sub> (Heat pump Airmax<sup>2</sup> 21GT)

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season "C" – colder

Bin	Outdo or temp. (dry bulb)	Hours	Part load ratio	Heat load	Capacity of HP	Heat load covered by heat pump	Resistiv e heat elbu(Tj)	Annual resistive heat	COPbin( Tj)	Annual heating demand	Annual power input including electric back up heating	Net annual heating capacity	Net annual power input without electric back up heating	
j	T <sub>j</sub>	h <sub>j</sub>		P <sub>h(Tj)</sub>			elbu(Tj)	h <sub>j</sub> × elbu(Tj)		h <sub>j</sub> × P <sub>h(Tj)</sub>		h <sub>j</sub> × (P <sub>h(Tj)</sub> - elbu(Tj))		
[-]	[°C]	[h]	[%]	[kW]	[kW]	[kW]	[kW]	[kWh]	[-]	[kWh]	[kWh]	[kWh]	[kWh]	
9	-22	1	100.00	15.13	0.00	0.00	15.13	15.13	1.00	15	15	0	0	
10	-21	6	97.37	14.73	0.00	0.00	14.73	88.40	1.00	88	88	0	0	
11	-20	13	94.74	14.34	0.00	0.00	14.34	186.36	1.00	186	186	0	0	
12	-19	17	92.11	13.94	0.00	0.00	13.94	236.94	1.00	237	237	0	0	
13	-18	19	89.47	13.54	0.00	0.00	13.54	257.25	1.00	257	257	0	0	
14	-17	26	86.84	13.14	0.00	0.00	13.14	341.67	1.00	342	342	0	0	
<b>TOL (E)</b>	<b>15</b>	<b>-16</b>	<b>39</b>	<b>84.21</b>	<b>12.74</b>	<b>11.50</b>	<b>11.50</b>	<b>1.24</b>	<b>48.47</b>	<b>1.50</b>	<b>497</b>	<b>347</b>	<b>449</b>	<b>299</b>
<b>G</b>	<b>16</b>	<b>-15</b>	<b>41</b>	<b>81.58</b>	<b>12.34</b>	<b>11.31</b>	<b>11.31</b>	<b>1.04</b>	<b>42.47</b>	<b>1.60</b>	<b>506</b>	<b>333</b>	<b>464</b>	<b>290</b>
	17	-14	35	78.95	11.95	11.12	11.12	0.83	29.00	1.69	418	259	389	230
	18	-13	52	76.32	11.55	10.93	10.93	0.62	32.32	1.79	601	350	568	317
	19	-12	37	73.68	11.15	10.74	10.74	0.41	15.33	1.89	413	226	397	211
	20	-11	41	71.05	10.75	10.54	10.54	0.21	8.49	1.98	441	226	432	218
<b>Tbiv(F)</b>	<b>21</b>	<b>-10</b>	<b>43</b>	<b>68.42</b>	<b>10.35</b>	<b>10.35</b>	<b>10.35</b>	<b>0.00</b>	<b>0.00</b>	<b>2.08</b>	<b>445</b>	<b>214</b>	<b>445</b>	<b>214</b>
	22	-9	54	65.79	9.96	11.21	9.96	0.00	0.00	2.12	538	254	538	254
	23	-8	90	63.16	9.56	12.06	9.56	0.00	0.00	2.15	860	400	860	400
<b>A</b>	<b>24</b>	<b>-7</b>	<b>125</b>	<b>60.53</b>	<b>9.16</b>	<b>12.92</b>	<b>9.16</b>	<b>0.00</b>	<b>0.00</b>	<b>2.19</b>	<b>1145</b>	<b>523</b>	<b>1145</b>	<b>523</b>
	25	-6	169	57.89	8.76	13.09	8.76	0.00	0.00	2.27	1481	654	1481	654
	26	-5	195	55.26	8.36	13.27	8.36	0.00	0.00	2.34	1631	696	1631	696
	27	-4	278	52.63	7.96	13.44	7.96	0.00	0.00	2.42	2214	915	2214	915
	28	-3	306	50.00	7.57	13.61	7.57	0.00	0.00	2.50	2315	927	2315	927
	29	-2	454	47.37	7.17	13.79	7.17	0.00	0.00	2.57	3254	1265	3254	1265
	30	-1	385	44.74	6.77	13.96	6.77	0.00	0.00	2.65	2606	983	2606	983
	31	0	490	42.11	6.37	14.13	6.37	0.00	0.00	2.73	3122	1145	3122	1145
	32	1	533	39.47	5.97	14.31	5.97	0.00	0.00	2.80	3184	1135	3184	1135
<b>B</b>	<b>33</b>	<b>2</b>	<b>380</b>	<b>36.84</b>	<b>5.58</b>	<b>14.48</b>	<b>5.58</b>	<b>0.00</b>	<b>0.00</b>	<b>2.88</b>	<b>2119</b>	<b>735</b>	<b>2119</b>	<b>735</b>
	34	3	228	34.21	5.18	15.70	5.18	0.00	0.00	3.17	1180	372	1180	372
	35	4	261	31.58	4.78	16.91	4.78	0.00	0.00	3.46	1247	360	1247	360
	36	5	279	28.95	4.38	18.13	4.38	0.00	0.00	3.75	1222	326	1222	326
	37	6	229	26.32	3.98	19.35	3.98	0.00	0.00	4.04	912	226	912	226
<b>C</b>	<b>38</b>	<b>7</b>	<b>289</b>	<b>23.68</b>	<b>3.58</b>	<b>20.56</b>	<b>3.58</b>	<b>0.00</b>	<b>0.00</b>	<b>4.33</b>	<b>964</b>	<b>223</b>	<b>964</b>	<b>223</b>
	39	8	233	21.05	3.19	20.83	3.19	0.00	0.00	4.47	742	166	742	166
	40	9	230	18.42	2.79	21.10	2.79	0.00	0.00	4.60	641	139	641	139
	41	10	243	15.79	2.39	21.37	2.39	0.00	0.00	4.74	581	123	581	123






	42	11	191	13.16	1.99	21.63	1.99	0.00	0.00	4.87	380	78	380	78
<b>D</b>	<b>43</b>	<b>12</b>	<b>146</b>	<b>10.53</b>	<b>1.59</b>	<b>21.90</b>	<b>1.59</b>	<b>0.00</b>	<b>0.00</b>	<b>5.00</b>	<b>233</b>	<b>46</b>	<b>233</b>	<b>46</b>
	44	13	150	7.89	1.19	22.17	1.19	0.00	0.00	5.14	179	35	179	35
	45	14	97	5.26	0.80	22.43	0.80	0.00	0.00	5.27	77	15	77	15
	46	15	61	2.63	0.40	22.70	0.40	0.00	0.00	5.41	24	4	24	4
	Σ		6446							Σ	37297	14827	35995	13525

SCOPon	2.52	SCOPnet	2.66
<b>SCOP</b>		<b>2.52</b>	

Power diagram - Heat pump **Airmax<sup>2</sup> 21GT**

- Medium temperature application (reference water temperature 55 °C)
- Reference heating season "C" – colder



Tested by: Ing. Tomáš Fiala

Date: 2017-01-05

Signed: Fiala

Reviewed by: Ing. Mario Jankola



Date: 2017-01-05

Signed: Jankola





## VI. Graphs

Heat pump Airmax<sup>2</sup> 21GT: A7/W35







Heat pump Airmax<sup>2</sup> 21GT: A2/W35







Heat pump Airmax<sup>2</sup> 21GT: A7/W55







Heat pump Airmax<sup>2</sup> 21GT: A-7/W34







Heat pump Airmax<sup>2</sup> 21GT: A2/W32.47







Heat pump **Airmax<sup>2</sup> 21GT: A7/W30.8**









Heat pump Airmax<sup>2</sup> 21GT: A12/W28.51









Heat pump Airmax<sup>2</sup> 21GT: A-10/W35







Heat pump Airmax<sup>2</sup> 21GT: A2/W35







Heat pump **Airmax<sup>2</sup> 21GT: A7/W29.08**







Heat pump Airmax<sup>2</sup> 21GT: A-10/W30.75







Heat pump Airmax<sup>2</sup> 21GT: A-7/W52







Heat pump Airmax<sup>2</sup> 21GT: A2/W45.69









Heat pump Airmax<sup>2</sup> 21GT: A7/W42.04







Heat pump Airmax<sup>2</sup> 21GT: A12/W37.18









Heat pump Airmax<sup>2</sup> 21GT: A-10/W55







Heat pump Airmax<sup>2</sup> 21GT: A2/W55







Heat pump Airmax<sup>2</sup> 21GT: A7/W38.61





Heat pump Airmax<sup>2</sup> 21GT: A-10/W45.88





## VII. List of additional documents used

- Order B-59756 of 2017-06-27 (Order reg. no. B-59756 delivered on 2017-06-28)
- Contract B-59756/39
- Amendment No. 1 to Contract B-59756/39
- ČSN EN 14511-1:2014 – Air conditioners, liquid chilling packages and heat pumps with electrically driven compressors for space heating and cooling - Part 1: Terms, definitions and classification
- ČSN EN 14511-2:2014 – Air conditioners, liquid chilling packages and heat pumps with electrically driven compressors for space heating and cooling - Part 2: Test conditions
- ČSN EN 14511-3:2014 – Air conditioners, liquid chilling packages and heat pumps with electrically driven compressors for space heating and cooling - Part 3: Test methods
- ČSN EN 14511-4:2014 – Air conditioners, liquid chilling packages and heat pumps with electrically driven compressors for space heating and cooling - Part 4: Operating requirements, marking and instructions
- ČSN EN 14825:2016 – Air conditioners, liquid chilling packages and heat pumps, with electrically driven compressors, for space heating and cooling - Testing and rating at part load conditions and calculation of seasonal performance
- EHPA Testing Regulation – Testing of Air/Water Heat Pumps – Additional requirements for granting the international quality label for heat pumps – Version 2.3
- Background 39-11227
- Record measurement file: Galmet\_12\_2017.zip

Test Report drafted by: Ing. Tomáš Fiala – Test Engineer

Person responsible for the Report:

**Milan Holomek**

Head of Heat and Environment-Friendly Equipment Test Station



- End of text -

[Uwagi tłumacza podane kursywą w nawiasach kwadratowych.]

[Tekst źródłowy dwustronicowy, w języku angielskim i języku trzecim, sporządzony na papierze firmowym Instytutu Badawczego Przemysłu Maszynowego w Brnie.]

[Logo Instytutu Badawczego Przemysłu Maszynowego]

[Tekst w języku trzecim]

Instytut Badawczy Przemysłu Maszynowego, Przedsiębiorstwo Państwowe, Brno,  
Republika Czeska

## Świadectwo badania

Numer **O-39-00006-18**

Klient Galmet Sp. z o.o. Sp. K.  
ul. Raciborska 36  
48-100 Głubczyce  
Polska

Produkt Pompa ciepła powietrze/woda – monoblokowa

Oznaczenie typu / znak towarowy **Airmax<sup>2</sup> 16GT**  
**Airmax<sup>2</sup> 21GT**  
**Airmax<sup>2</sup> 26GT**  
**Airmax<sup>2</sup> 30GT**

Metody badań ČSN EN 14511-2÷4:2014, ČSN EN 14825:2016, ČSN EN 12102:2014,  
Przepisy badań EHPA – Badanie pomp ciepła powietrze/woda, wersja 2.3

Podstawa wydania świadectwa Sprawozdania z badań:  
39-11227/T z 2017-01-05,  
39-11227/A/H z 2017-01-05,  
Dokumentacja techniczna Galmet sp. z o.o. sp. K.

Temperatura stosowania **NISKA**  
Referencyjna temperatura wody 35°C

Referencyjny sezon ogrzewczy **„A” = umiarkowany / „W” = ciepły / „C” = chłodny**  
Warunki obliczeniowe odniesienia dla ogrzewania:  $T_{designh} = -10^{\circ}\text{C} / + 2^{\circ}\text{C} / -22^{\circ}\text{C}$

### Specyfikacja warunków:

Regulacja prędkości sprężarki	<b>Stała</b>	Znamionowe natężenie przepływu cieczy (wewnętrzny wymiennik ciepła)	<b>Zmienne</b>
Temperatura wody na wylocie (wewnętrzny wymiennik ciepła)	<b>Zmienna</b>	Znamionowe natężenie przepływu cieczy (zewewnętrzny wymiennik ciepła)	---
Działanie	<b>Odwracalne</b>		

[Czerwona okrągła pieczęć z logo Instytutu Badawczego Przemysłu Maszynowego w polu pieczęci i tekstem w języku trzecim oraz numerem CZ 1 w otoku pieczęci]

Zarejestrowane Centrum Badawcze  
[Logo ehpa]

O-39-00006-18, strona 1 (2)

[Tekst w języku trzecim]

Instytut Badawczy Przemysłu Maszynowego, przedsiębiorstwo państwowe, Hudcova 424/56b, 621 00 Brno,  
Republika Czeska  
www.szutest.cz

[Element graficzny]

**Wyniki:**

Zastosowanie niskotemperaturowe Referencyjna temperatura wody 35°C		Nazwy modeli				
		Airmax <sup>2</sup> 16GT (niebadany)	Airmax <sup>2</sup> 21GT (badany)	Airmax <sup>2</sup> 26GT (niebadany)	Airmax <sup>2</sup> 30GT (niebadany)	
Ogrzewanie przy pełnym obciążeniu	<b>P<sub>designh</sub></b> [kW]	A	10,58	14,12	17,58	19,79
		W	10,70	14,27	17,80	20,30
		C	12,36	15,58	19,17	24,99
Temperatura dwuwartościowa	<b>T<sub>bivalent</sub></b> [°C]	A	-7	-7	-7	-7
		W	2	2	2	2
		C	-10	-10	-10	-10
Sezonowy współczynnik efektywności	<b>SCOP</b> [-]	A	4,07	3,93	3,99	4,01
		W	5,03	4,94	4,99	5,00
		C	3,44	3,33	3,38	3,42
Sezonowa efektywność energetyczna ogrzewania pomieszczeń	<b>η<sub>s</sub></b> [%]	A	159,8	154,2	156,7	157,5
		W	198,4	194,5	196,6	197,1
		C	134,8	130,1	132,2	133,8

(Badany) Ten egzemplarz testowy urządzenia został zbadany w Laboratorium Badawczym.

(Niebadany) Dane techniczne zostały zadeklarowane przez Producenta w oparciu o specyfikację gamy modeli i nie były badane przez Laboratorium Badawcze.

Instytut Badawczy Przemysłu Maszynowego, Przedsiębiorstwo Państwowe, potwierdza niniejszym Świadectwem Badania, że odnośny produkt został poddany badaniom, których wyniki są przedstawione powyżej. Instytut Badawczy Przemysłu Maszynowego, Przedsiębiorstwo Państwowe, jest akredytowanym Laboratorium Badawczym 1045.1.

Brno, 2018-01-05

[Niezczytelny podpis]

**Milan Holomek**

Kierownik Stacji Badawczej Urządzeń Ciepłych  
i Przyjaznych dla Środowiska

[Czerwona okrągła pieczęć, jak wyżej]

- KONIEC ŚWIADECTWA -

O-39-00006-18, strona 2 (2)

[Dane teleadresowe, jak na str. 1]

Niniejszym poświadczam zgodność powyższego tłumaczenia z okazanym mi odpisem dokumentu w formacie pdf sporządzonym w języku angielskim, którego kopia jest dołączona do niniejszego tłumaczenia.

Andrzej Saczek, tłumacz przysięgły języka angielskiego, wpisany na listę tłumaczy przysięgłych, prowadzoną przez ministra sprawiedliwości, pod numerem TP/28/17.

Numer w repertorium: 37/2024

Bojano, 05.06.2024 r.





Strojirenský zkušební ústav, s.p., Brno, Česká republika  
Engineering Test Institute, Public Enterprise, Brno, Czech Republic

## TEST CERTIFICATE

Number **O-39-00006-18**

Customer "Galmet Sp. z o.o." Sp. K.  
ul. Raciborska 36  
48-100 Głubczyce  
Poland

Product Air/Water Heat Pump – monobloc

Type designation / Trade mark **Airmax<sup>2</sup> 16GT**  
**Airmax<sup>2</sup> 21GT**  
**Airmax<sup>2</sup> 26GT**  
**Airmax<sup>2</sup> 30GT**

Test methods ČSN EN 14511-2+4:2014, ČSN EN 14825:2016, ČSN EN 12102:2014,  
EHPA Testing regulation – Testing of Air/Water Heat Pumps, version 2.3

Basis of certificate Test reports:  
39-11227/T of 2017-01-05,  
39-11227/A/H of 2017-01-05,  
Technical documents of "Galmet Sp. z o.o." Sp. K.

Temperature application **LOW**  
Reference water temperature 35 °C

Reference heating season **„A“ = average / „W“ = warmer / „C“ = colder**  
Reference design conditions for heating  $T_{designh} = -10\text{ °C} / +2\text{ °C} / -22\text{ °C}$

### Specification of conditions:

Compressor speed control	<b>Fixed</b>	Rated liquid flow rate (indoor heat exchanger)	<b>Variable</b>
Outlet water temperature (indoor heat exchanger)	<b>Variable</b>	Rated liquid flow rate (outdoor heat exchanger)	---
Function	<b>Reversible</b>		

Registered test centre



O-39-00006-18, page 1 (2)

Strojirenský zkušební ústav, s.p., Hudcova 424/56b, 621 00 Brno, Česká republika  
Engineering Test Institute, public enterprise, Hudcova 424/56b, 621 00 Brno, Czech Republic

[www.szutest.cz](http://www.szutest.cz)







## Results:

		Model names				
Low temperature application Reference water temperature 35 °C		Airmax <sup>2</sup> 16GT (Not tested)	Airmax <sup>2</sup> 21GT (Tested)	Airmax <sup>2</sup> 26GT (Not tested)	Airmax <sup>2</sup> 30GT (Not tested)	
Full load heating	$P_{\text{designh}}$ [kW]	A	10.58	14.12	17.58	19.79
		W	10.70	14.27	17.80	20.30
		C	12.36	15.58	19.17	24.99
Bivalent temperature	$T_{\text{bivalent}}$ [°C]	A	-7	-7	-7	-7
		W	2	2	2	2
		C	-10	-10	-10	-10
Seasonal coefficient of performance	SCOP [-]	A	4.07	3.93	3.99	4.01
		W	5.03	4.94	4.99	5.00
		C	3.44	3.33	3.38	3.42
Seasonal space heating energy efficiency	$\eta_s$ [%]	A	159.8	154.2	156.7	157.5
		W	198.4	194.5	196.6	197.1
		C	134.8	130.1	132.2	133.8

(Tested) This test sample was tested at the Testing Laboratory.

(Not tested) The technical data were declared by the Manufacturer according to the model range specifications and were not tested by the Testing Laboratory.

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2018-01-05

**Milan Holomek**

Head of Heat and Environment-Friendly Equipment Test Station



- END OF TEST CERTIFICATE -

[Uwagi tłumacza podane kursywą w nawiasach kwadratowych.]

[Tekst źródłowy dwustronicowy, w języku angielskim i języku trzecim, sporządzony na papierze firmowym Instytutu Badawczego Przemysłu Maszynowego w Brnie.]

[Logo Instytutu Badawczego Przemysłu Maszynowego]

[Tekst w języku trzecim]

Instytut Badawczy Przemysłu Maszynowego, Przedsiębiorstwo Państwowe, Brno,  
Republika Czeska

## Świadectwo badania

Numer **O-39-00007-18**

Klient Galmet Sp. z o.o. Sp. K.  
ul. Raciborska 36  
48-100 Głubczyce  
Polska

Produkt Pompa ciepła powietrze/woda – monoblokowa

Oznaczenie typu / znak towarowy **Airmax<sup>2</sup> 16GT**  
**Airmax<sup>2</sup> 21GT**  
**Airmax<sup>2</sup> 26GT**  
**Airmax<sup>2</sup> 30GT**

Metody badań ČSN EN 14511-2÷4:2014, ČSN EN 14825:2016, ČSN EN 12102:2014,  
Przepisy badań EHPA – Badanie pomp ciepła powietrze/woda, wersja 2.3

Podstawa wydania świadectwa Sprawozdania z badań:  
39-11227/T z 2017-01-05,  
39-11227/A/H z 2017-01-05,  
Dokumentacja techniczna Galmet sp. z o.o. sp. K.

Temperatura stosowania **ŚREDNIA**  
Referencyjna temperatura wody 55°C

Referencyjny sezon ogrzewczy **„A” = umiarkowany / „W” = ciepły / „C” = chłodny**  
Warunki obliczeniowe odniesienia dla ogrzewania:  $T_{designh} = -10^{\circ}C / + 2^{\circ}C / -22^{\circ}C$

### Specyfikacja warunków:

Regulacja prędkości sprężarki	<b>Stała</b>	Znamionowe natężenie przepływu cieczy (wewnętrzny wymiennik ciepła)	<b>Zmienne</b>
Temperatura wody na wylocie (wewnętrzny wymiennik ciepła)	<b>Zmienna</b>	Znamionowe natężenie przepływu cieczy (zewewnętrzny wymiennik ciepła)	---
Działanie	<b>Odwracalne</b>		

[Czerwona okrągła pieczęć z logo Instytutu Badawczego Przemysłu Maszynowego w polu pieczęci i tekstem w języku trzecim oraz numerem CZ 1 w otoku pieczęci]

Zarejestrowane Centrum Badawcze  
[Logo ehpa]

O-30-00007-18, strona 1 (2)

[Tekst w języku trzecim]

Instytut Badawczy Przemysłu Maszynowego, przedsiębiorstwo państwowe, Hudcova 424/56b, 621 00 Brno,  
Republika Czeska  
www.szutest.cz

[Element graficzny]

**Wyniki:**

		Nazwy modeli				
Zastosowanie średnitemperaturowe		<b>Airmax<sup>2</sup> 16GT</b>	<b>Airmax<sup>2</sup> 21GT</b>	<b>Airmax<sup>2</sup> 26GT</b>	<b>Airmax<sup>2</sup> 30GT</b>	
Referencyjna temperatura wody 55°C		(niebadany)	(badany)	(niebadany)	(niebadany)	
Ogrzewanie przy pełnym obciążeniu	<b>P<sub>designh</sub></b> [kW]	A	10,86	14,49	18,20	20,18
		W	11,05	14,63	18,30	20,40
		C	13,29	15,13	21,19	23,53
Temperatura dwuwartościowa	<b>T<sub>bivalent</sub></b> [°C]	A	-7	-7	-7	-7
		W	2	2	2	2
		C	-10	-10	-10	-10
Sezonowy współczynnik efektywności	<b>SCOP</b> [-]	A	3,13	3,04	3,12	3,13
		W	3,71	3,56	3,63	3,63
		C	2,57	2,52	2,53	2,53
Sezonowa efektywność energetyczna ogrzewania pomieszczeń	<b>η<sub>s</sub></b> [%]	A	122,4	118,8	121,7	122,3
		W	145,5	139,3	142,1	142,2
		C	99,8	97,6	98,0	98,0

(Badany) Ten egzemplarz testowy urządzenia został zbadany w Laboratorium Badawczym.

(Niebadany) Dane techniczne zostały zadeklarowane przez Producenta w oparciu o specyfikację gamy modeli i nie były badane przez Laboratorium Badawcze.

Instytut Badawczy Przemysłu Maszynowego, Przedsiębiorstwo Państwowe, potwierdza niniejszym Świadectwem Badania, że odnośny produkt został poddany badaniom, których wyniki są przedstawione powyżej. Instytut Badawczy Przemysłu Maszynowego, Przedsiębiorstwo Państwowe, jest akredytowanym Laboratorium Badawczym 1045.1.

Brno, 2018-01-05

[Nieczytelny podpis]

**Milan Holomek**

Kierownik Stacji Badawczej Urządzeń Ciepłych  
i Przyjaznych dla Środowiska

[Czerwona okrągła pieczęć, jak wyżej]

- KONIEC ŚWIADECTWA -

O-30-00007-18, strona 2 (2)

[Dane teleadresowe, jak na str. 1]

Niniejszym poświadczam zgodność powyższego tłumaczenia z okazanym mi odpisem dokumentu w formacie pdf sporządzonym w języku angielskim, którego kopia jest dołączona do niniejszego tłumaczenia.

Andrzej Saczek, tłumacz przysięgły języka angielskiego, wpisany na listę tłumaczy przysięgłych, prowadzoną przez ministra sprawiedliwości, pod numerem TP/28/17.

Numer w repertorium: 38/2024

Bojano, 05.06.2024 r.



**Strojírenský zkušební ústav, s.p., Brno, Česká republika**  
**Engineering Test Institute, Public Enterprise, Brno, Czech Republic**

# TEST CERTIFICATE

Number **O-39-00007-18**

**Customer** "Galmet Sp. z o.o." Sp. K.  
ul. Raciborska 36  
48-100 Głubczyce  
Poland

**Product** Air/Water Heat Pump – monobloc

**Type designation / Trade mark** **Airmax<sup>2</sup> 16GT**  
**Airmax<sup>2</sup> 21GT**  
**Airmax<sup>2</sup> 26GT**  
**Airmax<sup>2</sup> 30GT**

**Test methods** ČSN EN 14511-2+4:2014, ČSN EN 14825:2016, ČSN EN 12102:2014,  
EHPA Testing regulation – Testing of Air/Water Heat Pumps, version 2.3

**Basis of certificate** Test reports:  
39-11227/T of 2017-01-05,  
39-11227/A/H of 2017-01-05,  
Technical documents of "Galmet Sp. z o.o." Sp. K.

**Temperature application** **MEDIUM**  
Reference water temperature 55 °C

**Reference heating season** „**A**“ = average / „**W**“ = warmer / „**C**“ = colder  
Reference design conditions for heating  $T_{design} = -10\text{ °C} / +2\text{ °C} / -22\text{ °C}$

**Specification of conditions:**

Compressor speed control	<b>Fixed</b>	Rated liquid flow rate (indoor heat exchanger)	<b>Variable</b>
Outlet water temperature (indoor heat exchanger)	<b>Variable</b>	Rated liquid flow rate (outdoor heat exchanger)	---
Function	<b>Reversible</b>		

Registered test centre



O-30-00007-18, page 1 (2)

Strojírenský zkušební ústav, s.p., Hudcova 424/56b, 621 00 Brno, Česká republika  
 Engineering Test Institute, public enterprise, Hudcova 424/56b, 621 00 Brno, Czech Republic

[www.szutest.cz](http://www.szutest.cz)







## Results:

		Model names				
Medium temperature application Reference water temperature 55 °C		Airmax <sup>2</sup> 16GT (Not tested)	Airmax <sup>2</sup> 21GT (Tested)	Airmax <sup>2</sup> 26GT (Not tested)	Airmax <sup>2</sup> 30GT (Not tested)	
Full load heating	$P_{\text{designh}}$ [kW]	A	10.86	14.49	18.20	20.18
		W	11.05	14.63	18.30	20.40
		C	13.29	15.13	21.19	23.53
Bivalent temperature	$T_{\text{bivalent}}$ [°C]	A	-7	-7	-7	-7
		W	2	2	2	2
		C	-10	-10	-10	-10
Seasonal coefficient of performance	SCOP [-]	A	3.13	3.04	3.12	3.13
		W	3.71	3.56	3.63	3.63
		C	2.57	2.52	2.53	2.53
Seasonal space heating energy efficiency	$\eta_s$ [%]	A	122.4	118.8	121.7	122.3
		W	145.5	139.3	142.1	142.2
		C	99.8	97.6	98.0	98.0

(Tested) This test sample was tested at the Testing Laboratory.

(Not tested) The technical data were declared by the Manufacturer according to the model range specifications and were not tested by the Testing Laboratory.

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2018-01-05

**Milan Holomek**

Head of Heat and Environment-Friendly Equipment Test Station



- END OF TEST CERTIFICATE -

[Przyp. tłum.: Do tłumaczenia przedstawiono dokument dwujęzyczny. Treści w języku czeskim nie zostały przetłumaczone.]



Strojírenský zkušební ústav, s.p., Brno, Česká republika  
Techniczny Instytut Badawczy, Przedsiębiorstwo Państwowe, Brno, Czechy

## ŚWIADECTWO BADAŃ

Numer: **0-39-00005-18**

Klient	"Galmet Sp. z o.o." Sp. K. ul. Raciborska 36 48-100 Glubczyce Polska
Produkt	Pompa ciepła powietrze/woda – monoblok
Oznaczenie typu / Znak towarowy	<b>Airmax<sup>2</sup> 16GT</b> <b>Airmax<sup>2</sup> 21GT</b> <b>Airmax<sup>2</sup> 26GT</b> <b>Airmax<sup>2</sup> 30GT</b>
Metoda badawcza	ČSN EN 14511-2+4:2014, ČSN EN 14825:2016, ČSN EN 12102:2014, Rozporządzenie w sprawie badań – Badanie pomp ciepła powietrze/woda Europejskiego Stowarzyszenia Pomp Ciepła ( <i>ang. European Heat Pump Association, EHPA</i> ), wersja 2.3
Podstawa świadectwa	Raporty z badań: 39-11227/T z dnia 05-01-2017 r., 39-11227/A/H z dnia 05-01-2017 r., Dokumentacja techniczna „Galmet Sp. z o.o.” Sp. K.
Temperatura robocza	<b>NISKA, ŚREDNIA</b> Temperatura referencyjna wody 35 °C oraz 55 °C
Referencyjny sezon grzewczy	<b>„A” = średni / „W” = cieplejszy/ „C” = zimniejszy</b> Referencyjne założenia projektowe ogrzewania $T_{designh} = -10\text{ °C} / +2\text{ °C} / -22\text{ °C}$



Ja, Edyta Więclawska, tłumacz przysięgły z języka angielskiego ustanowiony przy Sądzie Okręgowym w Rzeszowie, Polska z siedzibą przy ul. Plac Śreniawitów 3, 35-959; wpisany na listę tłumaczy przysięgłych prowadzoną przez Ministra Sprawiedliwości pod nr TP/1023/05 Polska. Potwierdzam zgodność niniejszego tłumaczenia z fotokopią dokumentu w języku angielskim. Białowa, 22 października 2020 r. Numer Repertorium 435/2020.

Określenie warunków:

Regulacja prędkości sprężarki	Stała	Znamionowa prędkość przepływu cieczy (wewnętrzny wymiennik ciepła)	Zmienna
Temperatura wody na wyjściu (wewnętrzny wymiennik ciepła)	Zmienna	Znamionowa prędkość przepływu cieczy (zewewnętrzny wymiennik ciepła)	---
Funkcja	Odwracalna		

Zarejestrowane centrum badawcze



O-30-00005-18, strona 1 (2)

Strojirenský zkušební ústav, s.p., Hudcova 424/56b, 621 00 Brno, Česká republika  
Techniczny Instytut Badawczy, Przedsiębiorstwo Państwowe, Hudcova 424/56b, 621  
00 Brno, Czechy  
www.szutest.cz



Ja, Edyta Więclawska, tłumacz przysięgły z języka angielskiego ustanowiony przy Sądzie Okręgowym w Rzeszowie, Polska z siedzibą przy ul. Plac Śreniawitów 3, 35-959; wpisany na listę tłumaczy przysięgłych prowadzoną przez Ministra Sprawiedliwości pod nr TP/1023/05 Polska. Potwierdzam zgodność niniejszego tłumaczenia z fotokopią dokumentu w języku angielskim. Błażowa, 22 października 2020 r. Numer Repertorium 435/2020.



/strona 2/



**Wyniki:**

Warunki znamionowe*		Nazwy modeli			
		Airmax <sup>2</sup> 16GT (nietestowany)	Airmax <sup>2</sup> 21GT (testowany)	Airmax <sup>2</sup> 26GT (nietestowany)	Airmax <sup>2</sup> 30GT (nietestowany)
A7/W35	Skorygowana moc cieplna [kW]	15,55	20,981	26,01	29,82
	Rzeczywisty pobór mocy [kW]	3,31	4,586	5,64	6,41
	COP [-]	4,70	4,575	4,61	4,65
	Ustawienia kontrolne [%]	-	-	-	-
A2/W35	Skorygowana moc cieplna [kW]	11,25	15,031	18,75	21,42
	Rzeczywisty pobór mocy [kW]	3,17	4,342	5,34	6,09
	COP [-]	3,55	3,461	3,51	3,52
	Ustawienia kontrolne [%]	-	-	-	-
A7/W55	Skorygowana moc cieplna [kW]	15,75	21,216	26,40	30,10
	Rzeczywisty pobór mocy [kW]	4,85	6,759	8,25	9,47
	COP [-]	3,25	3,139	3,20	3,18
	Ustawienia kontrolne [%]	-	-	-	-

Poziom mocy akustycznej w warunkach A7/W55\*, klasa dokładności: techniczna (poziom 2)

L <sub>WA</sub>	Jednostka wewnętrzna Jednostka zewnętrzna	[dB(A)]	---			
			73,5 ± 1,5	74,4 ± 1,5	75,0 ± 1,5	75,5 ± 1,5



Ja, Edyta Więclawska, tłumacz przysięgły z języka angielskiego ustanowiony przy Sądzie Okręgowym w Rzeszowie, Polska z siedzibą przy ul. Plac Śreniawitów 3, 35-959; wpisany na listę tłumaczy przysięgłych prowadzoną przez Ministra Sprawiedliwości pod nr TP/1023/05 Polska. Potwierdzam zgodność niniejszego tłumaczenia z fotokopią dokumentu w języku angielskim. Białowa, 22 października 2020 r. Numer Repertorium 435/2020.



(\*) Objaśnienie skrótego oznaczenia: np. A7/W35: A (powietrze), 7 (powietrze wchodzące – temperatura termometru suchego w °C) / W (woda), 35 (temperatura wody podgrzanej na wyjściu w °C).

(Testowany) Ta próbka była badana w Laboratorium Badawczym.

(Nietestowany) Dane techniczne zgodnie z deklaracją Producenta na podstawie zakresu specyfikacji modelu, niebadane przez Laboratorium Badawcze.

Na podstawie niniejszego Świadectwa Techniczny Instytut Badawczy, Przedsiębiorstwo Państwowe potwierdza, że podczas badania danego produktu otrzymano wyniki, które zostały przedstawione powyżej.

Techniczny Instytut Badawczy, Przedsiębiorstwo Państwowe jest akredytowanym Laboratorium Badawczym 1045.1.

Brno, 05-01-2018 r.

[Neczytelny podpis, przyp. tłum.]

Milan Holomek

Kierownik stanowiska do badania sprzętu grzewczego i przyjaznego dla środowiska  
(ang. Head of Heat and Environment-Friendly Equipment Test Station)

- KONIEC ŚWIADECTWA -



0-30-00005-18, strona 2 (2)

Strojirenský zkušební ústav, s.p., Hudcova 424/56b, 621 00 Brno, Česká republika  
Techniczny Instytut Badawczy, Przedsiębiorstwo Państwowe, Hudcova 424/56b, 621  
00 Brno, Czechy  
www.szutest.cz



Ja, Edyta Więclawska, tłumacz przysięgły z języka angielskiego ustanowiony przy Sądzie Okręgowym w Rzeszowie, Polska z siedzibą przy ul. Plac Sreniawitów 3, 35-959; wpisany na listę tłumaczy przysięgłych prowadzoną przez Ministra Sprawiedliwości pod nr TP/1023/05 Polska. Potwierdzam zgodność niniejszego tłumaczenia z fotokopią dokumentu w języku angielskim. Błaszowa, 22 października 2020 r. Numer Repertorium 435/2020.



Strojirenský zkušební ústav, s.p., Brno, Česká republika  
Engineering Test Institute, Public Enterprise, Brno, Czech Republic

## TEST CERTIFICATE

Number **O-39-00005-18**

Customer "Galmet Sp. z o.o." Sp. K.  
ul. Raciborska 36  
48-100 Głubczyce  
Poland

Product Air/Water Heat Pump – monobloc

Type designation / Trade mark **Airmax<sup>2</sup> 16GT**  
**Airmax<sup>2</sup> 21GT**  
**Airmax<sup>2</sup> 26GT**  
**Airmax<sup>2</sup> 30GT**

Test methods ČSN EN 14511-2+4:2014, ČSN EN 14825:2016, ČSN EN 12102:2014,  
EHPA Testing regulation – Testing of Air/Water Heat Pumps, version 2.3

Basis of certificate Test reports:  
39-11227/T of 2017-01-05,  
39-11227/A/H of 2017-01-05,  
Technical documents of "Galmet Sp. z o.o." Sp. K.

Temperature application **LOW, MEDIUM**  
Reference water temperature 35 °C and 55 °C

Reference heating season **„A“ = average / „W“ = warmer / „C“ = colder**  
Reference design conditions for heating  $T_{design} = -10\text{ °C} / +2\text{ °C} / -22\text{ °C}$

### Specification of conditions:

Compressor speed control	<b>Fixed</b>	Rated liquid flow rate (indoor heat exchanger)	<b>Variable</b>
Outlet water temperature (indoor heat exchanger)	<b>Variable</b>	Rated liquid flow rate (outdoor heat exchanger)	---
Function	<b>Reversible</b>		

Registered test centre



O-30-00005-18, page 1 (2)

Strojirenský zkušební ústav, s.p., Hudcova 424/56b, 621 00 Brno, Česká republika  
Engineering Test Institute, public enterprise, Hudcova 424/56b, 621 00 Brno, Czech Republic

[www.szutest.cz](http://www.szutest.cz)



**Results:**

## Model names

Rating condition*			Model names			
			Airmax <sup>2</sup> 16GT (Not tested)	Airmax <sup>2</sup> 21GT (Tested)	Airmax <sup>2</sup> 26GT (Not tested)	Airmax <sup>2</sup> 30GT (Not tested)
<b>A7/W35</b>	Corrected heat capacity	[kW]	15.55	20.981	26.01	29.82
	Effective power input	[kW]	3.31	4.586	5.64	6.41
	COP	[-]	4.70	4.575	4.61	4.65
	Control settings	[%]	-	-	-	-
<b>A2/W35</b>	Corrected heat capacity	[kW]	11.25	15.031	18.75	21.42
	Effective power input	[kW]	3.17	4.342	5.34	6.09
	COP	[-]	3.55	3.461	3.51	3.52
	Control settings	[%]	-	-	-	-
<b>A7/W55</b>	Corrected heat capacity	[kW]	15.75	21.216	26.40	30.10
	Effective power input	[kW]	4.85	6.759	8.25	9.47
	COP	[-]	3.25	3.139	3.20	3.18
	Control settings	[%]	-	-	-	-

Sound power level at condition A7/W55\*, accuracy class: Engineering (grade 2)

LWA		[dB(A)]	---			
			Indoor unit	---	---	---
	Outdoor unit		73.5 ± 1.5	74.4 ± 1.5	75.0 ± 1.5	75.5 ± 1.5

(\*) Comment to abbreviated marking: e.g. A7/W35: A (air), 7 (input air – dry bulb temperature in °C) / W (water), 35 (output heating water temperature in °C).

(Tested) This test sample was tested at the Testing Laboratory.

(Not tested) The technical data were declared by the Manufacturer according to the model range specifications and were not tested by the Testing Laboratory.

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2018-01-05

**Milan Holomek**

Head of Heat and Environment-Friendly Equipment Test Station

- END OF TEST CERTIFICATE -





Tłumaczenie przysięgłe z języka angielskiego

[logo]

Strojírenský zkušební ústav, s.p., Brno, Česká republika  
 Instytut Badań Inżynieryjnych, Przedsiębiorstwo Państwowe, Brno, Republika Czeska

**ŚWIADECTWO BADAŃ**

Numer **O-39-00002-18**

Klient	„Galmet Sp. z o.o.” Sp. K. ul. Raciborska 36 48-100 Głubczyce Polska
Produkt	Pompa ciepła powietrze/woda – monoblok
Oznaczenie typu/Znak towarowy	<b>Airmax<sup>2</sup> 21GT</b>
Metody badań	ČSN EN 14825:2016, ČSN EN 12102:2014, Regulamin badań EHPA – badanie pomp ciepła powietrze/woda, wersja 2.3, komunikat Komisji nr 2014/C 207/02
Podstawa wydania świadectwa	Sprawozdania z badań: 39-11227/T z dnia 2017-01-05, 39-11227/A/H z dnia 2017-01-05, Dokumenty techniczne przedstawione przez „Galmet Sp. z o.o.” Sp. K.
Referencyjny sezon grzewczy	„A” = średni Referencyjne projektowe warunki ogrzewania $T_{projh} = -10\text{°C}$

**Wyniki:**

**NISKA TEMPERATURA**  
(referencyjna temperatura wody 35°C)

**WYSOKA TEMPERATURA**  
(referencyjna temperatura wody 55°C)

<b>14,12</b>	<b>P<sub>projh</sub> [kW] ... Ogrzewanie przy pełnym obciążeniu</b>	<b>14,49</b>
<b>3,93</b>	<b>SCOP [-] ... Sezonowy współczynnik wydajności</b>	<b>3,04</b>

Temperatura zewnętrzna	Deklarowana efektywność ogrzewania	Współczynnik wydajności przy deklarowanej efektywności	Temperatura zewnętrzna	Deklarowana efektywność ogrzewania	Współczynnik wydajności przy deklarowanej efektywności
T <sub>j</sub> [°C]	P <sub>dth</sub> [kW]	COP <sub>d</sub> [-]	T <sub>j</sub> [°C]	P <sub>dth</sub> [kW]	COP <sub>d</sub> [-]
T <sub>j</sub> = -7	12,490	2,944	T <sub>j</sub> = -7	12,819	2,171
T <sub>j</sub> = +2	15,016	3,734	T <sub>j</sub> = +2	14,468	2,806
T <sub>j</sub> = +7	20,357	4,949	T <sub>j</sub> = +7	20,496	4,060
T <sub>j</sub> = +12	22,322	5,828	T <sub>j</sub> = +12	21,856	5,046
T <sub>j</sub> = TOL = -10	10,789	2,524	T <sub>j</sub> = TOL = -10	10,932	1,793
T <sub>j</sub> = T <sub>dww</sub> = -7	12,490	2,944	T <sub>j</sub> = T <sub>dww</sub> = -7	12,819	2,171

[pieczęćka z logo i słowami „Strojírenský zkušební ústav, s.p., CZ1” w otoku]

Zarejestrowane centrum badawcze  
[logo EHPA]

O-39-00002-18, strona 1 (2)

[hologram]

Strojírenský zkušební ústav, s.p. Hudcova 424/56b, 621 00 Brno, Česká republika  
 Instytut Badań Inżynieryjnych, Przedsiębiorstwo Państwowe, Hudcova 424/56b, 621 00 Brno, Republika Czeska  
 www.szutest.cz





[logo]

**NISKA TEMPERATURA**  
(referencyjna temperatura  
wody 35°C)

**WYSOKA TEMPERATURA**  
(referencyjna temperatura  
wody 55°C)

**Zużycie mocy w trybach innych niż „tryb aktywny”**

9,8	Tryb wyłączenia	P <sub>OFF</sub>	[W]	9,8
10,0	Tryb wyłączenia termostatu	P <sub>TO</sub>	[W]	9,7
9,8	Tryb czuwania	P <sub>SB</sub>	[W]	9,8
0,0	Tryb ogrzewania karteru	P <sub>CK</sub>	[W]	0,0

**Roczne zużycie energii elektrycznej na ogrzewanie zgodnie z**

7421	ČSN EN 14825:2016	Q <sub>HE</sub>	[kWh]	9834
------	-------------------	-----------------	-------	------

**Sezonowa efektywność energetyczna ogrzewania pomieszczeń**

154,2	ČSN EN 14825:2016	η <sub>s</sub>	[%]	118,8
-------	-------------------	----------------	-----	-------

**Prędkość przepływu cieczy w zewnętrznym wymienniku ciepła**

---	Ciecz źródłowa	min	[m <sup>3</sup> /h]	---
		max		

**Prędkość przepływu cieczy w zewnętrznym wymienniku ciepła**

2,039	Woda grzewcza	min	[m <sup>3</sup> /h]	1,255
3,829		max		2,402

**Poziom mocy akustycznej w warunkach A7/W55\*, inżynierska klasa dokładności (stopień 2)**

LWA - dB(A)      Airmax<sup>2</sup> 21GT      LWA 74,4 ± 1,5 dB(A)

(\*) Uwaga dotycząca skróconego oznaczenia, np. A7/W55: A (powietrze), 7 (temperatura wlotowa - temperatura termometru suchego w °C) / W (woda), 55 (temperatura wylotowa wody w °C)

**Specyfikacja warunków:**

Sterowanie prędkością sprężarki	<b>Stałe</b>	Przepływ objętościowy wody grzewczej (zewnątrzny wymiennik ciepła)	<b>Zmienny</b>
Temperatura wody na wylocie (wewnętrzny wymiennik ciepła)	<b>Zmienna</b>	Objętość przepływu cieczy źródłowej (wewnętrzny wymiennik ciepła)	---
Praca	<b>Odwracalna</b>		

Instytut Badań Inżynierskich, Przedsiębiorstwo Państwowe, poprzez wydanie niniejszego Świadczenia Badania potwierdza, że na podstawie badania danego produktu uzyskano wyniki podane powyżej. Instytut Badań Inżynierskich, Przedsiębiorstwo Państwowe, jest akredytowanym Laboratorium Badawczym nr 1045.1. Brno, 2018-01-05

[nieczytelny podpis]

**Milan Holomek**

Kierownik Stanowiska Badań Urządzeń Grzewczych i Ekologicznych

- KONIEC ŚWIADCZENIA BADAŃ -

O-39-00002-16, strona 2 (2)

Strojirenský zkušební ústav, s.p. Hudcova 424/56b, 621 00 Brno, Česká republika

Instytut Badań Inżynierskich, Przedsiębiorstwo Państwowe, Hudcova 424/56b, 621 00 Brno, Republika Czeska

www.szutest.cz

[pieczęć z logo i słowami  
„Strojirenský zkušební ústav,  
s.p., CZ1” w otoku]

**Niniejszym potwierdzam zgodność powyższego tłumaczenia z przedłożonym mi skanem dokumentu w języku angielskim.**

**Poznań, dnia 28 marca 2024 r.**

**Tłumacz przysięgły języka angielskiego Marcin Kotlicki**

**Nr TP/32/12**

**ul. Rataje 162/13, 61-168 Poznań**

**nr rep 367/2024**





Strojirenský zkušební ústav, s.p., Brno, Česká republika  
Engineering Test Institute, Public Enterprise, Brno, Czech Republic

## TEST CERTIFICATE

Number **O-39-00002-18**

Customer "Galmet Sp. z o.o." Sp. K.  
ul. Raciborska 36  
48-100 Głubczyce  
Poland

Product Air/Water Heat Pump – monobloc

Type designation / Trade mark **Airmax<sup>2</sup> 21GT**

Test methods ČSN EN 14825:2016, ČSN EN 12102:2014, EHPA Testing regulation – Testing of Air/Water Heat Pumps, version 2.3, Commission communication No. 2014/C 207/02.

Basis of certificate Test reports:  
39-11227/T of 2017-01-05,  
39-11227/A/H of 2017-01-05,  
Technical documents of "Galmet Sp. z o.o." Sp. K.

Reference heating season „A“ = average  
(Reference design temperature  $T_{designh} = -10\text{ °C}$ )

### Results:

#### LOW TEMPERATURE

(Reference water temperature 35 °C)

#### MEDIUM TEMPERATURE

(Reference water temperature 55 °C)

<b>14.12</b>	<b><math>P_{designh}</math> [kW] ... Full load heating</b>				<b>14.49</b>
<b>3.93</b>	<b>SCOP [-] ... Seasonal coefficient of performance</b>				<b>3.04</b>
Outdoor temperature $T_j$ [°C]	Heating declared capacity $P_{dh}$ [kW]	Coefficient of performance at the declared capacity $COP_d$ [-]	Outdoor temperature $T_j$ [°C]	Heating declared capacity $P_{dh}$ [kW]	Coefficient of performance at the declared capacity $COP_d$ [-]
$T_j = -7$	12.490	2.944	$T_j = -7$	12.819	2.171
$T_j = +2$	15.016	3.734	$T_j = +2$	14.468	2.806
$T_j = +7$	20.357	4.949	$T_j = +7$	20.496	4.060
$T_j = +12$	22.322	5.828	$T_j = +12$	21.856	5.046
$T_j = TOL = -10$	10.789	2.524	$T_j = TOL = -10$	10.932	1.793
$T_j = T_{bivalent} = -7$	12.490	2.944	$T_j = T_{bivalent} = -7$	12.819	2.171

Registered test centre



O-39-00002-18, page 1 (2)

Strojirenský zkušební ústav, s.p., Hudcova 424/56b, 621 00 Brno, Česká republika  
Engineering Test Institute, public enterprise, Hudcova 424/56b, 621 00 Brno, Czech Republic

[www.szutest.cz](http://www.szutest.cz)







## LOW TEMPERATURE

(Reference water temperature 35 °C)

## MEDIUM TEMPERATURE

(Reference water temperature 55 °C)

### Power consumption in modes other than „active mode“

9.8	Off mode	$P_{OFF}$	[W]	9.8
10.0	Thermostat off mode	$P_{TO}$	[W]	9.7
9.8	Standby mode	$P_{SB}$	[W]	9.8
0.0	Crankcase heater mode	$P_{CK}$	[W]	0.0

### Annual electricity consumption for heating according to

7421	ČSN EN 14825:2016	$Q_{HE}$	[kWh]	9834
------	-------------------	----------	-------	------

### Seasonal Space heating energy efficiency

154.2	ČSN EN 14825:2016	$\eta_s$	[%]	118.8
-------	-------------------	----------	-----	-------

### Liquid flow rate in outdoor heating exchanger

---	Source liquid	Min/ Max	[m <sup>3</sup> /h]	---
-----	---------------	-------------	---------------------	-----

### Liquid flow rate in indoor heating exchanger

2.039 3.829	Heating water	Min/ Max	[m <sup>3</sup> /h]	1.255 2.402
----------------	---------------	-------------	---------------------	----------------

### Sound power level at condition A7/W55\*, Engineering accuracy class (grade 2)

$L_{WA}$	-	dB(A)	Airmax <sup>2</sup> 21GT	$L_{WA}$	74.4 ± 1.5	dB(A)
----------	---	-------	--------------------------	----------	------------	-------

(\*) Comment to abbreviated marking: e.g. A7/W55

A (air), 7 (input air – dry bulb temperature in °C) / W (water), 55 (output heating water temperature in °C).

### Specification of conditions:

Compressor speed control	<b>Fixed</b>	Rated liquid flow rate (indoor heat exchanger)	<b>Variable</b>
Outlet water temperature (indoor heat exchanger)	<b>Variable</b>	Rated liquid flow rate (outdoor heat exchanger)	---
Function	<b>Reversible</b>		

Engineering Test Institute, Public Enterprise, confirms by this Test Certificate that the testing of the product in question was performed with the results as stated above. Engineering Test Institute, Public Enterprise, is an accredited Testing Laboratory 1045.1.

Brno, 2018-01-05

**Milan Holomek**

Head of Heat and Environment-Friendly Equipment Test Station



- END OF TEST CERTIFICATE -

O-39-00002-18, page 2 (2)



## OŚWIADCZENIE

Producent "Galmet Sp. z o.o." Sp.K oświadcza, iż pompy ciepła

1) Airmax2 16GT; Nr.kat.: 09-261600

Oznaczenie/typ/identyfikator modelu

2) Airmax2 21GT; Nr.kat.: 09-262100

Oznaczenie/typ/identyfikator modelu

3) Airmax2 26GT; Nr.kat.: 09-262600

Oznaczenie/typ/identyfikator modelu

4) Airmax2 30GT; Nr.kat.: 09-263000

Oznaczenie/typ/identyfikator modelu

5)

Oznaczenie/typ/identyfikator modelu

Należą do jednego podtypu w danym typoszeregu i spełniają łącznie następujące warunki:

- identyczna konstrukcja obiegu chłodniczego, ten sam czynnik chłodniczy/roboczy;
- ten sam producent, typ i liczba sprężarek;
- ten sam typ elementu rozprężnego;
- ten sam typ skraplacza;
- ten sam typ parownika;
- ten sam typ procesu odszraniania;
- ten sam sterownik i zasada sterowania wydajnością;
- ten sam producent, typ i liczba wentylatorów parownika (w przypadku powietrznych pomp ciepła) i zasada sterowania wydajnością (stała, zmienna lub stopniowana regulacja prędkości obrotowej);
- urządzenia z i bez zaworu czterodrogowego nie mogą być zaliczone do tego samego typoszeregu.

Głubczyce, 14.05.2024

Miejscowość, data

 Galmet Sp. z o.o. Sp. K  
48-100 Głubczyce, ul. Raciborska 36  
inż. Marek Baticz  
Product Manager  
produkcji pomp ciepła

Podpis osoby upoważnionej